

Delaware Department of Transportation

CLARIFICATIONS

T200411210.01

SR 26, ATLANTIC AVENUE FROM CLARKSVILLE TO ASSAWOMAN CANAL

Tuesday, September 24, 2013

Q #	Question	Answer
2	On Breakout sheet 7 you show 350 LF of 8" gravity sewer. The plans show 21 LF so where is the balance found?	The 8" Gravity Sewer item is to be used for the various stub connections between the manholes and terminal cleanouts. These are shown on the plans and always have a slope of 0.28%. The 8" lateral item (breakout item 6) is intended for use where the lateral is connecting directly into the sewer main and running to a terminal cleanout.
1	What is bid item #27 on Breakout Sheet 7 used for on this contract? Is it for concrete buttresses?	No. This is intended as a contingency item to be used in the event that concrete encasements would be needed due to less than standard clearances between the sewer and other Utilities. Concrete buttresses are incidental to the various linear foot items of sewer pipe.