

Delaware Department of Transportation
FINAL QUESTIONS AND ANSWERS
T200401102.01

SR 2, SOUTH UNION STREET FROM RAILROAD BRIDGE TO SYCAMORE STREET, WILMINGTON NEW CASTLE COUNTY
Friday, August 16, 2013

Q #	Question	Answer
Wednesday, August 14, 2013		
11	In questions and answers for this project dated 08/12/2013 you state in Question 2 to refer to the specifications. I checked the Standard Specs as well as Standard Drawings and there is no special provision item for this item. Can you provide a little more detail as where the detail for this item is shown?	The pinned barrier needs to be crash tested in accordance with NCHRP 350/MASH and approved for use by FHWA on the NHS (acceptance letter). The pinning locations shall be precast into the barrier segments. We will not accept the use of bolt down type straps as this design has not be crash tested.
10	What is the size of the 6" concrete bus pad associated with bid item 759500? Where is that detail shown on the plans?	Pad to match existing pad dimensions.
9	Typical section on plan sheet 7 shows 4" hot mix over 8" concrete from station 10+00 to station 19+57. How is the removal of this 4" hot mix paid for or is it incidental to the removal of the PCC Pavement (Item 758000)?	Removal is paid for under 202000
8	What is the depth of the GABC that is placed where the median is removed?	See typical sections for GABC depths.
7	How is the removal of the existing median paid for? Is it under 758000 or a combination of 202000 and 758000?	Per spec., median is removed by combination of 758000 and 202000. <input type="checkbox"/>
6	In stage 1 for SR2 where exactly does the removal of the existing median begin?	SEE note on Sheet 14 for reconstruction limit.
5	Ref Bid Item 202573, Test Holes, what is the maximum depth we would be required to dig?	There is no maximum depth specified for the item.

Q #	Question	Answer
-----	----------	--------

Monday, August 12, 2013

4	Are cross-sections available for this project? What is the cost?	No cross sections were used in the preparation of the contract.
3	How will all the detour signs that are required on this contract be paid for?	Item 743013, Temporary Warning Signs and Plaques
2	Where is the detail for Item 743013 found on the plans?	There is no detail for item 743013. Please refer to the specifications.
1	In the specs for bid item 202560 it indicates that payment for this item is incidental to the excavation item. What is the quantity of item 202560 that the contractor will encounter on this project?	There is no quantity specified for item 202560. The specification is included for use in the event that contamination is encountered.