

Delaware Department of Transportation

**QUESTIONS AND ANSWERS**

**T201207602.01**

**BR 3-558 ON S417 DAISEY ROAD OVER POCOMOKE RIVER**

**Saturday, March 21, 2015**

Q #	Question	Answer
-----	----------	--------

**Friday, March 20, 2015**

4	We are having trouble locating a source for the Ultra High Performance Concrete (Item 618516). The concrete plants indicate it is a bag mix while the supply houses indicate it is a plant item. Can you provide an acceptable product(s)?	Refer to Question 2.
---	--	----------------------

**Thursday, March 19, 2015**

3	Given the short contract duration for this project is it the Department's intent to order the production piles at the same time as the test piles?	It is the Department's intent to have production piles ordered at the same time test piles are ordered. General Pile Note 4 states that an additional 5' has been added to the design length for the production piles as a contingency, which allows for the production piles to be ordered with the test piles.
2	Does the Department know of a manufacturer of the material in Special Provision 618516 – Ultra High Performance Concrete?	Lafarge is a manufacturer per their advertised performance criteria that appears to meet the performance based specification. Other manufacturers may submit a product which meets the performance specifications as well. Lafarge's website is <a href="http://www.lafarge-na.com">www.lafarge-na.com</a> .
1	Please refer to Project Note 5 on plan sheet 3. How is the silicone acrylic concrete sealer measured and paid? There is not a bid item for this.	Silicone acrylic concrete sealer does not need to be applied to any concrete surfaces for this contract. Please disregard the silicone acrylic concrete sealer note.