

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T200504110.01

HSIP NCC, N54, HOWELL SCHOOL ROAD, SR 896 TO SR71, NEW CASTLE COUNTY

Friday, October 23, 2015

Q #	Question	Answer
5	Is there a chance the Bid can be Postponed?	No.
4	Regarding note 16 on plan page 70: If undercut soil has to be replaced with #57 stone we cannot limit ourselves to 150% of the excavation and embankment price as required in section 212 of the standard specifications.	The Project Note #16 on plan sheet 70 is part of the bridge plans. This note applies to areas of unsuitable material encountered below the proposed bridge foundation. Based on soil boring information, it is anticipated that unsuitable material will be limited in this area, in the range of several cubic yards. No. 57 stone shall be used as undercut back-fill in areas under the bridge foundation, and payment for No. 57 stone shall be included under item No. 212000. Undercut excavation areas outside the limits of the bridge foundation shall follow the fill requirements outlined in the standard specifications for undercut excavation.
3	What size pipe goes to the water meter?	The pipe size is 8" DIP, CL52.

Tuesday, October 06, 2015

2	All of the even numbered pages are missing from the Utility Statement. Can it be reissued?	The Utility Statement was revised in Addendum No. 1.
1	Can cross sections be made available to bidders?	Cross sections have been posted to the website.