

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T200907201.01

BR 2-203A ON TODDS MILL ROAD OVER ISAAC BRANCH, KENT COUNTY

Tuesday, June 04, 2013

Q #	Question	Answer
5	Planting: The plan calls for watering plants 9 times from June 15th through October 1st. This project is 39 calendar days long and is supposed to start August 30th. The contract will be over before the 1st day of 2014. Does the contractor have to return next year to water the plantings?	Yes.
4	How are you paid for course aggregate for stabilization under the sheet pile caps?	This quantity will be added to Addendum 1. It will be 10 Tons total.
3	Is Item 762002 used for saw cutting the concrete sheet piles?	Yes. Sheet piles shall be cut to Elevation 34.00.
2	What does Note 5 on Environmental Notes Pg 13 mean? Do you have access on both sides of the stream on the East and West sides?	Access will be provided to the stream from 2 places- the Northeast corner (Parcel 2-R) and the Northwest corner (Parcel 2-R).
1	Is the Excavation and Embankment quantity correct? I get over 200cy just excavating the existing roadway and over 300If if you excavate the new paving footprint.	This quantity is incorrect: an updated quantity will be provided in Addendum 1.