

Delaware Department of Transportation  
**QUESTIONS AND ANSWERS**  
**T201009002.01**  
**ROAD A / SR 7 Improvements New Castle County**  
**Tuesday, November 13, 2018**

Q #	Question	Answer
4	<p>RE: Item 606004 Drilled Shaft, 60”  Please refer to plan sheets 92 &amp; 94, Note 16:  “...1 drilled shaft shall be load tested by the contractor in accordance  With Item #606030 - Load Testing of Drilled Shafts.”  There is no Item #606030 in the Schedule of Items for this project.  Please advise.</p>	<p>No load testing of the drilled shafts is required for this project. Please disregard note 16 on sheets 92 and 94.</p>

**Wednesday, November 07, 2018**

3	Please make the cross sections available as noted on plan sheet 4.	The cross sections are not available to prospective bidders.
---	--	--

**Monday, October 29, 2018**

2	<p>The wingwall details on sheet 48 indicate the Type B Borrow beneath the wingwall section on fill is incidental to the lump sum MSE wall item (607001). There is not enough information on the plans to quantify the B Borrow required. Can this B Borrow be paid separately? If not, please provide either elevations, dimensions or a quantity of B Borrow that we are to include in Item 607001.</p>	<p>The estimate of the Borrow Type B fill quantity used for the “Typical Wingwall Section on Fill” on Sheet 48 is as follows:   Abutment A Wingwall 2 = 750 CY  Abutment B Wingwall 4 = 520 CY</p>
---	---	--

**Friday, October 26, 2018**

1	<p>Plan Sheet No. 47, has a note stating, “The MSE Wall panels shall receive an Architectural Finish.” However, there is no mention of what that finish shall be, could the Dept. provide what the anticipated Architectural Finish is expected to be?</p>	<p>The Architectural Finish shall be “Fractured Fin”.</p>
---	--	---