

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201309003.01

ROAD A / SR 7 / CENTER BLVD INTERSECTION IMPROVEMENTS NEW CASTLE COUNTY

Friday, November 15, 2013

Q #	Question	Answer
10	What is the Access to the F Borrow Stockpile-Since the Fashion Ctr is under construction where will access be located for this Stockpile?	Access to the stockpile will be from state right of way from Center Boulevard and the entrance way between Don Pablo's and Costco's.
9	Will E&S controls be needed at the F Borrow Stockpile? If so who is responsible?	E&S is always needed at disturbed areas. The contractor will be responsible for E&S at the disturbed areas of the DelDOT stockpile as noted in the plans. Contractor is responsible to submit E& S plans for review and approval by the Department prior to commencing any work.
8	Who is responsible for the Restoration of the Del Dot F Borrow?	Restoration of the DelDOT stockpile, if used, will be the contractors responsibility as noted in the plans. Contractor will be responsible to submit a restoration and E&S plan for review and approval to the Department prior to commencing any work. The restoration and E&S plan must address the existing drainage, drainage areas, and slopes of the stockpile during and after construction.
7	On the addendum disk for this project are there supposed to be revised drawings showing the new item 202000 quantities?	The quantities for 20200 and 733002 were corrected in the addendum. There were no changes to the plans as a result of the quantity correction.

Tuesday, November 12, 2013

6	Will all F borrow needed be available from the DelDOT stockpile?	All F Borrow needed is expected to be available from the DelDOT stockpile.
5	In your earthwork summary under excavation you have 5 CY of rock excavation for roadway and trenches. I don't see a rock excavation item on the proposal. Please clarify.	There is no rock excavation anticipated on this project and as such there is no bid item. Please bid according to the proposal.

Q #	Question	Answer
4	The table says we need 1295 CY for Topsoiling. Using the topsoiling quantity (Item 733002 which is 11958 SY) this quantity will require 1993 CY. Your table indicates that only 1594 CY is suitable for topsoiling which means you are short topsoil not excess. Please clarify.	The quantities for items 202000 and 733002 have been found to be in error and will be corrected by addendum.

Wednesday, November 06, 2013

3	There are also two different pay items for loops - Item 746774 - Supply & Installation of Loop Detector Wire, which is the older spec and Item 746924 - Furnish & Install Loop Wire 1- Conductor #14 AWG Encased in 1/4" Flexible Tubing in a Loop Sawcut. Please confirm that both applications are being used.	Both items are being used. Item 746924 for the new signal and Item 746774 for replacement of existing loops at Road A/ SB SR1 ramp intersection that is being milled and resurfaced as part of the project.
2	This bid contains two different pay items for Adjust or Repair Existing Conduit Junction Well - Item 744505 & Item 744544. Can you please confirm that these items are the same thing?	The two pay items are for the same type of work. Please bid per the proposal for the quantity for each.
1	What is the limit of clearing for this project? Is it the CZ or LOC?	The limit of clearing is the LOC.