

Delaware Department of Transportation

**QUESTIONS AND ANSWERS**

**T201330009.02**

**INDUSTRIAL TRACK GREENWAY PHASE III, NEW CASTLE COUNTY**

**Wednesday, July 06, 2016**

Q #	Question	Answer
3	The DBE Specification section of the Proposal document for this bid is not clear on DBE certification requirements. Do DBE's have to be certified through DelDOT, or do DBE's from PAUCP and/or NJUCP also qualify toward the DBE goal?	<i>Response forthcoming.</i>
2	We are looking at providing material quantities on the wire faced MSE walls to contractors for the above referenced project. However, specifications are not provided or noted as "under revision" in the Specification Notes. Is there a wire faced MSE wall specification or special provision for this project that can be provided?	Please reference the specification for Item 602772, Mechanically Stabilized Earth Walls, on pages 81-86 of the bid documents. Welded wire mesh is specifically referenced in the last paragraph under Materials on page 84. Mesh must be designed by the contractor in accordance with AASHTO M32, AASHTO M55, and AASHTO M111 and the design parameters noted on sheet 53 of the plans.
1	Who is responsible for 3rd party testing of items such as driven piles, MSE wall construction, etc.?	DelDOT is responsible for materials testing of each of these elements.