

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201401201.01

SR 8, FORREST AVENUE PEDESTRIAN IMPROVEMENTS, CRANBERRY RUN, KENT COUNTY

Thursday, May 08, 2014

Q #	Question	Answer
7	How can there be 926 LF of new curbing on this project when typical sections only show 780 LF of curbing being installed?	The plan quantity for curb is taken from the curb schedules on the plans and account for the additional distance of curb going around radii. The plan quantity is correct.
6	Is the GABC for driveways paid under item 302007?	Yes.
5	Based on the typical sections that are shown on plan sheets 5 and 6, the quantities for item 401821, 401822, and 401823 do not appear to be correct. Please verify.	There was a discrepancy in the calculation of the bid quantity for Item 401822, the quantity for this Item should be 43 Tons not 85 tons. The quantity will be revised in Addendum No. 1. Bid quantities were verified for Items 401821 & 401823.
4	What is item 401801 used for on this project?	Item 401801 is for the residential driveway section as per Note 6 on Sheet 4.
3	It appears from plan sheet 16 under stage 6 that this work must be done at night. What is the work hours for the balance of the work and where is that shown on the plans?	Note 6 on Plan Sheet 16 states that the crosswalk installation across SR8 is to occur during the hours of 8:00pm – 5:00am Sunday through Friday. This is the only work restricted to night time hours and as such is specifically spelled out under that note. The balance of the work is to occur under daytime operations.

Thursday, May 01, 2014

2	What is the typical section of the existing pavement we are tying into?	Based on historical contract research and the subsurface data available the shoulder typical section varies from 3.75"-6" of hot-mix over 8"-12" of stone. Actual field conditions may vary but it is anticipated to be a maximum of 6" of hot-mix on the shoulder in question.
1	Reference Note 1 under Stage 6 on Plan Sheet 16; under what bid item is this installation paid for?	The HAWK signal will be installed by other State of Delaware forces and is not a bid item for Contract T201401201. The work is phased in with this contract for over all coordination.