

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201407208.01

BR 2-234A ON LAKE FRONT DRIVE OVER RED HOUSE BRANCH, KENT COUNTY

Thursday, September 07, 2017

Q #	Question	Answer
3	What are the limits for measurement and payment for item 207000?	Please refer to the 2001 Standard Specifications, Section 207 for the portion of proposed excavation that extends past the existing pipe footprint. The 207000 excavation within the existing bridge shall be limited to the removal of the sediment buildup within the existing pipes. The existing structure is to be left in place. The 207000 excavation upstream of the bridge shall include sediment removal between the existing railroad bridge and existing Bridge 2-234A to the top of the existing concrete apron.
2	Is GAB Type B to be placed under the type 2 curb and gutter? If so, what is the depth?	Please refer to the 2001 Standard Specifications, Section 701.
1	The full depth pavement section is not shown on the legend plan sheet. What is the full depth pavement section?	Please refer to sheet 2, "Legend", of the Construction Plans. It is located in the top right corner under the pavement section(s) legend.