

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201430001.01

OPEN -END CONSTRUCTION SERVICES, STATEWIDE TRAILS, KENT COUNTY

Thursday, March 13, 2014

Q #	Question	Answer
19	Please confirm the meaning/intent of the planting breakout sheets issued with the CD at the pre-bid meeting. Which breakout sheet do we return with our bid – the one in the special provisions or the one on the pre-bid CD? Are we to price this work ourselves or are we to use the prices & quantities on the CD and bid it as a fixed price item @ \$29,196.00?	The breakout sheet for bidding purposes is on pdf page 171 of bid documents (Also the same shown on website). The breakout sheets provided on the disc at the pre-bid meeting are to be disregarded.
18	Will the transcript of the meeting minutes be posted to the website?	Yes.

Wednesday, March 12, 2014

17	At task #3 location on plan sheet 22 you have a detail for 48" x 30" drainage inlet. Where is that item used on the bid and under what bid item is it paid for?	The detail on sheet 22 is for the inlets at Station 104+27 Rt, 104+44 Rt, and 107+86 Rt. This work will be paid for under item 710001 - Adjusting and Repairing Existing Drainage Inlet. Notes 6 and 7 on Sheet 22 also provide this information
16	At task #3 location what is the width of Maintenance Strip shown on Plan Sheet 10?	The maintenance strip will be three (3) feet wide. The existing pavement shall be sawcut one (1) foot inside the face of the proposed guardrail/construction alignment and the new maintenance pavement will extend the required two (2) feet behind the face of the guardrail.
15	Must work at task II location be done at night? If so I don't see a light plant bid item.	All work will be done during the day.
14	At Task #2 location plan sheet 7 at approximately station 503+00 there is a section of sidewalk that is 5' wide coming off the main trail. Is this 4" sidewalk?	Yes, the sidewalk leading to the Fire Fighters Memorial is 4".

Q #	Question	Answer
13	On Task #2 Plans there are numerous trees (1" and 2" cal) to be relocated and states that the relocation is incidental to Item 737523-Planting. I don't see an item in the breakout sheet for tree relocations. How far away from there present location do they get relocated to?	This plan note will be changed. The City of Dover will accept responsibility to relocate all trees on Task #2.

Thursday, March 06, 2014

12	Will any of the work shown on the proposal be required to be done at night?	No night work is anticipated for the three locations provided in the bid documents.
11	Can details be provided for bid items 602615 and 602704?	Yes. Information for item 602615 Modular Block Retaining Wall will be provided in the construction details of the Task 3 - RT 10 Bridge Crossing to Gateway Shopping Center plans. Information for item 602704 Retaining Wall will be provided in the construction details of the Task 1 - Capital City Trail Phase II plans. The detail information will be included in the addendum.
10	How many day of project layout does the contractor figure for this project since item 763501 is a lump sum bid item?	The lump sum price will be based upon the three locations initially provided in the bid documents. The contractor shall determine the layout required to meet the project needs. Plan information will be included in the addendum. If additional locations are added to the contract we will negotiate an increase based on the proposed work at the new locations.
9	How many mobilizations does the contractor figure for this project since item 763000 is a lump sum bid item?	The lump sum price will be based upon the three locations initially provided in the bid documents. If additional locations are added to the contract we will negotiate an increase based on the proposed work at the new locations.
8	How many ped/bicycle traffic counters are req'd under bid item 763510 since it is a lump sum bid item?	The ped/bicycle counter will be installed as part of Task 1 - Capital City Trail Phase II. The detail information will be included in the addendum.

Q #	Question	Answer
7	Item 743000 lump sum bid item locations not known?	The lump sum price will be based upon the three locations initially provided in the bid documents. Additional information about those locations will be provided at the pre bid meeting and plan information included in the addendum. If additional locations are added to the contract we will negotiate an increase based on the proposed work at the new locations.
6	Since item 737523 is a lump sum item, how many work locations does the breakout sheet quantities represent?	The estimate for the Planting Item takes into account work at all three locations. Plan information will be included in the addendum. If additional locations are added to the contract we will negotiate an increase based on the proposed work at the new locations.
5	Where is the detail for item 727556, steel fence, shown?	Information for this item will be provided in the construction details of the Task 3 - RT 10 Bridge Crossing to Gateway Shopping Center plans and included in the addendum.
4	What is the depth of installation for item 6120022 since according to deldot specs, borrow TY C backfill will be included in the price for the pipe installed?	This item is used in Task 3 - RT 10 Bridge Crossing to Gateway Shopping Center. The maximum depth is approximately 4.5' but an average depth along the 96 feet of pipe would be approximately 18". Plan information will be included in the addendum.
3	Where is the detail for bid item 606503, steel hand railing, shown?	Information for this item will be provided in the construction details of the Task 3 - RT 10 Bridge Crossing to Gateway Shopping Center plans. The detail information will be included in the addendum
2	How many locations will be required for the installation of the tonnage listed for item 401574 (253 tons)?	The Pervious Bituminous Asphalt Pavement will only be used at the Task 3 location - RT 10 Bridge Crossing to Gateway Shopping Center.
1	Lump sum bid for item 201000 work locations are not known at this time?	The estimate is based on the three locations named in the bid documents. The locations will be reviewed at the pre bid meeting and plan information provided in an addendum. If additional locations are added to the contract we will negotiate an increase based on the proposed work at the new locations.

SECTION 1 **BREAKOUT SHEET - 1** **CONTRACT NO. T201430001**
ITEM 737523 - PLANTING

ITEM NO.	APPRO X. QTY.	UOM	DESCRIPTION	UNIT PRICE	AMOUNT
1	2	EACH	Acer Rubrum 'Autumn Blaze', Autumn Blaze Red Maple, 2.5-3" cal., B&B	\$	\$
2	3	EACH	Betula Nigra 'River Birch', 8-10", B&B	\$	\$
3	6	EACH	Cornus Amomun, Silky Dogwood, 24-30"	\$	\$
4	2	EACH	Cornus Florida 'Cherokee Princess', Cherokee Princess Dogwood, 2.5-3" cal., B&B	\$	\$
5	30	EACH	Hypericum 'Hidcote', St. John's Wort, 24-36"	\$	\$
6	39	EACH	Ilex Clabra 'Shamrock', Shamrock Holly, 18-24"	\$	\$
7	1	EACH	Primis X Yedoensis, 'Akebono', Akebono Yoshino Cherry, 2.0-2.5" cal., B&B	\$	\$
8	6	EACH	Quercus bicolor, Swamp White Oak, 2.5-3" cal., B&B	\$	\$
9	2	EACH	Quercus phellos, Willow Oak, 2.5-3" cal., B&B	\$	\$
10	11	EACH	Rhus Aromatica 'Gro Low', Gro Low Fragrant Sumac, #3 Container	\$	\$
11	340	SF	Agastache 'Black Adder', Agastache 'Black Adder', Landscape Plugs (DP38)	\$	\$
12	324	SF	Solidago rugosa 'Fireworks', Solidago rugosa 'Fireworks', Landscape Plugs (DP38)	\$	\$
13	49	CY	Shredded Hard Wood Mulch	\$	\$
14	1.0	M/GAL	WATER	\$	\$

TOTAL ITEM 737523 - PLANTING \$ _____
(LUMP SUM BID PRICE FOR ITEM 737523 - PLANTING)