

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201480107.01

STATEWIDE FABRIC SALT BARNs, OPEN END, FY 15-17

Tuesday, October 20, 2015

Q #	Question	Answer
1	Please refer to details 1-3 on plan page S-06. Based on dimensions the stem height is 9'-6". However, using the noted scale of $\frac{3}{4}'' = 1' - 0''$ the stem height is almost 10'-6". What is the correct stem height?	The listed dimensions should be followed. Contractor shall not scale the drawings when dimensions are provided.