

Delaware Department of Transportation
QUESTIONS AND ANSWERS
T201507605.02
RECORDS POND DAM IMPROVEMENTS
Tuesday, November 26, 2019

Yellow highlighting = previous questions answered in this posting: Q2

Q #	Question	Answer
Monday, November 25, 2019		
3	Please specify if both sides of the sheetpile are to be coated.	Yes, coating is required for both sides of sheet piles.
2	Can the overhead powerlines will be removed by Others prior to NTP.	Per the Utility Statement, Utility Poles 47795/00190 and 47807/55165 are to be removed before construction. In addition, the aerial lines between 47783/00202 and 47795/00190 and between 47807/55165/47817/00150 will also be removed prior to construction.
Wednesday, November 13, 2019		
1	We are limited regarding times that we can work in the water, particularly with the sturgeon. What type of flexibility do we have with working around these dates?	The Contractor may elect to erect a cofferdam within the limits of construction within Broad Creek, preventing sturgeon from entering the work area. By placing this cofferdam, work may continue on the upstream side of the cofferdam during the time restriction. The cofferdam can only be installed and removed during the time when work is allowed in the stream. Placement of this cofferdam does not relieve the contractor of the additional restrictions stated in the Plans. Payment for the cofferdam system will be made under item 604500 – Cofferdams.