

Delaware Department of Transportation

**QUESTIONS AND ANSWERS**

**T201547303.01**

**BR 2-213A ON HOLLERING HILL ROAD OVER COW MARSH CREEK-EMERGENCY REPLACEMENT/KENT COUNTY**

**Friday, September 26, 2014**

<b>Q #</b>	<b>Question</b>	<b>Answer</b>
3	In determining the completion time of 54 calendar days for the subject project did the Department consider concrete cure times, Thanksgiving, Christmas and the possibility that air temperatures may be too low to pave within the specification rules?	Yes, all of these factors were considered in determining the completion time.
2	Is Bayshore Concrete supplying the 56 ea #8 dowel bars in the top of the 14"x14" conc piles ?	No, these bars should be included in the bid price for Item #619061 Install Precast Prestressed Concrete Pile 14" x 14" and/or #619067 Install Precast Prestressed Concrete Test Pile 14" x 14".

**Wednesday, September 24, 2014**

1	What is the length of the dowel inserts in the prestressed-precast concrete piles that are being provided by the Department?	Per plan, they are 8'6" long to accommodate some pile cutoff and still allow installation of the dowel bars at a 3'0" minimum.
---	--	--