

Delaware Department of Transportation

QUESTIONS AND ANSWERS

T201611302.01

US 301 CLEARING, NORTH BUNKER HILL ROAD TO SR 1

Thursday, November 19, 2015

Q #	Question	Answer
4	Is brush smaller than 3" to be cleared and piled on site, mulched in place, or chipped?	Brush smaller than 3" does not need to be cleared except as may be needed for the contractor to perform the work. Cleared brush can be left on site in accordance with the contract documents.
3	Per plan pages sheet #4, Section 200, Item #4 - contractor is to cut trees 3" and larger at approximately 2-4 feet above ground elevation and leave the stumps. What is to be done with the tops; will these be dropped and left in place, moved and piled on site, mulched in place or chipped?	Note #4 on Sheet #4 states, "THE CLEARED MATERIALS ARE TO BE LEFT WITHIN THE LIMITS OF THE PROJECT AT THE LOCATIONS WHERE THEY ARE CLEARED." The intent is to have the cleared materials dropped and left in place within the project limits.
2	Will resource protection fence be provided by DEL-DOT per plans or will contractor provide per Special Provisions page 40?	DelDOT shall provide the resource protection fence materials per Note 10.V on plan sheet 4.
1	Is the contractor to provide construction stakeout per the description for Construction Engineering, or will the DEL-DOT engineer complete stakeout per plans sheet #4, Notes 15 & 16?	The DelDOT Engineer will provide the stakeout.