

Delaware Department of Transportation
QUESTIONS AND ANSWERS
T201906306.01
SLAUGHTER BEACH RD REHABILITATION, SOUTH, 2019
Thursday, March 26, 2020

Q #	Question	Answer
4	Is there any data available on the existing pavement structure of the mainline and shoulders?	The shoulders consist of approx. ½” micro over 1” chip seal over soil/select fill. The mainline is believed to consist of approx. ½” micro over 2”-3” bituminous concrete over soil cement or PCC.
3	Can a detail for the patching be provided?	Patching is anticipated to consist of sawcutting (item 762000), bituminous patching (402000), and 1 lift of 2” top (401029) over 3” base (item 401030). If conditions warrant at the time of construction, the proposed patching box may be adjusted.
2	Will the longitudinal joint between the newly placed hma base in the shoulder and the existing drive lanes require PG 64-22 joint sealer per note 40? Or is this not a requirement since the road will be surface treated and fog sealed?	We will not require the joint between the bituminous base shoulder and the existing drive lanes to be sealed since the road will be chip sealed and fog sealed.
1	Can a construction detail be provided for item 760001 – Rumble Strips, Full-Lane Width? Also, please clarify the construction, method of measurement, and basis of payment for this item.	Item 760001 – Rumble Strips, Full Lane Width – Please refer to the Delaware MUTCD Chapter 3J, Section 3J.02: Transverse Rumble Strip Markings and Table 3J-1 for appropriate Transverse Rumble Strip locations. Also refer to Standard Specification Section 760001 for specifications, method of measurement, and basis of payment, and also refer to the DelDOT Standard Detail P-5, Sheet 1 of 2, Continuous Shallow Depth Rumble Strip for detail of the actual cut shape. The transverse rumble strip shall be cut per this detail but at the pattern specified and described in the Delaware MUTCD Table 3J-1. Note that, depending on pavement type and condition, the contractor may be directed to utilize the thermoplastic rumble strips as described in note 76 of the contract in lieu of using item 760001.