

Delaware Department of Transportation
QUESTIONS AND ANSWERS
T202007403
SR 1 CORRIDOR PHASE ONE DECK SEALING,
NCC, FY 21
Friday, October 09, 2020

Q #	Question	Answer
1	Providing that the contractor follows all federal and state temporary traffic control guidelines, can the contractor perform the washing/cleaning of these structures in a mobile operation? All bridges will need to be power washed prior to the application of the silane-based sealer being applied.	That will be acceptable so long as all specifications are met. We can't wash and clean the deck more than a couple nights prior to applying the sealer. The maximum amount of time allowed to have a lane blocked using a mobile cleaning operation on the bridge is 15 minutes.