SIGN SCHEDULE - SILVER LAKE ROAD (ROAD 442)

#	SHEET NO.	PLAN INDICATOR	CODE	QTY.	DESCRIPTION	SIGN WIDTH (IN)	SIGN HEIGHT (IN)	SIGN AREA (SF)	ITEM 749687 SINGLE POST (EACH)			ITEM 749690 MULTI POST (POST NEEDED)			POST INSTALLATION TYPE	Code X11 12' Post (W/ Basepost)	ITEM 749688 4" HOLE, 0-6" (EACH)	ITEM 749689 4" HOLE, >6" (EACH)	REMARKS
									SIGN DISPOSTION	REMOVE	INSTALL	SIGN DISPOSTION	REMOVE	INSTALL					
4	28	281A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	28	281B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"Noxontown Rd"
1672	28	281C	D3-1(8)	2	STREET NAME (1 Line)	30"	8"		REMAIN							0	0	0	"Silver Lake Rd"
3	29	291	R1-1(30)	1	STOP	30"	30"		REMAIN							0	0	0	
1982	29	292A	S4-3P(36)	1	SCHOOL - 36x12	36"	12"		REMAIN							0	0	0	
1966	29	292B	S1-1(36)	1	SCHOOL SIGN (Symbol) - 36x36	36"	36"		REMAIN							0	0	0	
1286	29	292C	W13-1P-25(24)	1	ADVISORY SPEED (25 MPH) 24x24	24"	24"		REMAIN							0	0	0	
1982	30	301A	S4-3P(36)	1	SCHOOL - 36x12	36"	12"		REMAIN							0	0	0	
1966	30	301B	S1-1(36)	1	SCHOOL SIGN (Symbol) - 36x36	36"	36"		REMAIN							0	0	0	
1286	30	301C	W13-1P-25(24)	1	ADVISORY SPEED (25 MPH) 24x24	24"	24"		REMAIN							0	0	0	
4	30	302A	R1-1(36)	1	STOP	36"	36"	9	RENEW	1	1					0	0	0	
1672	30	302B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"	2	ADD TO EXIST.		1					0	0	0	"Silver Lake Rd"
1672	30	302C	D3-1(8)	2	STREET NAME (1 Line)	42"	8"	2.3	ADD TO EXIST.		1					0	0	0	"Sandburg Blvd"
4	30	303	R1-1(36)	1	STOP	36"	36"	9	RENEW	1	1					0	0	0	
1982	30	304A	S4-3P(36)	1	SCHOOL - 36x12	36"	12"		REMAIN							0	0	0	
1966	30	304B	S1-1(36)	1	SCHOOL SIGN (Symbol) - 36x36	36"	36"		REMAIN							0	0	0	
1286	30	304C	W13-1P-25(24)	1	ADVISORY SPEED (25 MPH) 24x24	24"	24"		REMAIN							0	0	0	
1982	31	311A	S4-3P(36)	1	SCHOOL - 36x12	36"	12"		REMAIN							0	0	0	
1966	31	311B	S1-1(36)	1	SCHOOL SIGN (Symbol) - 36x36	36"	36"		REMAIN							0	0	0	
1286	31	311C	W13-1P-25(24)	1	ADVISORY SPEED (25 MPH) 24x24	24"	24"		REMAIN							0	0	0	
3	31	312	R1-1(30)	1	STOP	30"	30"		REMAIN							0	0	0	
311	31	313	R4-7(24)		KEEP RIGHT (Symbol) - 24x30	24"	30"	5								0	0	0	
1966	31	314A	S1-1(36)		SCHOOL SIGN (Symbol) - 36x36	36"	36"	9	NEW		1				SOIL	1	0	0	
1365	31	314B	W16-7P_FYG(24)L	1	LEFT DOWNWARD DIAGONAL ARROW (plaque) - 24x12	24"	18"	3	ADD TO EXIST.		1					0	0	0	
1966	31	315A	S1-1(36)	1	SCHOOL SIGN (Symbol) - 36x36	36"	36"	9	NEW		1				SOIL	1	0	0	
1365	31	315B	W16-7P_FYG(24)L	1	LEFT DOWNWARD DIAGONAL ARROW (plaque) - 24x12	24"	18"	3	ADD TO EXIST.		1					0	0	0	
4	31	316	R1-1(36)	1	STOP	36"	36"	9	RENEW	1	1					0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
PAGE TOTALS								60.30		3	9		0	0		2	0	0	
JOB TOTALS								60.3		3	9		0	0		2	0	0	

Unofficial Website Copy

SIGN SCHEDULE - EAGLES NEST LANDING ROAD (ROAD 465)

#	SHEET NO.	PLAN INDICATOR	CODE	QTY.	DESCRIPTION	SIGN WIDTH (IN)	SIGN HEIGHT (IN)	SIGN AREA (SF)	ITEM 749687 SINGLE POST (EACH)			ITEM 749690 MULTI POST (POST NEEDED)			POST INSTALLATION TYPE	Code X11 12' Post (W/ Basepost)	ITEM 749688 4" HOLE, 0-6" (EACH)	ITEM 749689 4" HOLE, >6" (EACH)	REMARKS
									SIGN DISPOSTION	REMOVE	INSTALL	SIGN DISPOSTION	REMOVE	INSTALL					
4	32	321A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
392	32	321B	R6-1_R(36)	1	ONE WAY (ENCLOSED IN RIGHT ARROW) - 36x12	36"	12"		REMAIN							0	0	0	
394	32	321C	R6-1_L(36)	1	ONE WAY (ENCLOSED IN LEFT ARROW) - 36x12	36"	12"		REMAIN							0	0	0	
1672	32	321D	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"Dupont Pkwy"
1672	32	321E	D3-1(8)	2	STREET NAME (1 Line)	54"	8"		REMAIN							0	0	0	"Eagles Nest Landing Rd"
871	32	322A	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"		REMAIN							0	0	0	
1367	32	322B	W16-8P	1	ADVANCE STREET NAME (1 - line plaque)	30"	8"		REMAIN							0	0	0	"DuPont Pkwy"
871	32	331A	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"		REMAIN							0	0	0	
1872	32	331B	D14-3-DE	1	ADOPT A HIGHWAY	24"	18"		REMAIN							0	0	0	
1872	32	331C	D14-3-DE	1	ADOPT A HIGHWAY	24"	18"		REMAIN							0	0	0	"CHARLES & ISIS"
4	34	341A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	34	341B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"GUM BUSH RD"
1672	34	341C	D3-1(8)	2	STREET NAME (1 Line)	54"	8"		REMAIN							0	0	0	"Eagles Nest Landing Rd"
871	34	342A	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"		REMAIN							0	0	0	
1367	34	342B	W16-8P	2	ADVANCE STREET NAME (1 - line plaque)	36"	8"		REMAIN							0	0	0	"Gum Bush Rd"
4	34	343A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	34	343B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"GUM BUSH RD"
1672	34	343C	D3-1(8)	2	STREET NAME (1 Line)	54"	8"		REMAIN							0	0	0	"Eagles Nest Landing Rd"
4	38	381A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	38	381B	D3-1(8)	2	STREET NAME (1 Line)	42"	8"		REMAIN							0	0	0	"Eagles Nest Lndg Rd"
1672	38	381C	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"Deer Run Rd"
871	39	391	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"	6.25	NEW		1				SOIL	1	0	0	
4	40	401A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	40	401B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"WALKER SCH RD"
1672	40	401C	D3-1(8)	2	STREET NAME (1 Line)	42"	8"		REMAIN							0	0	0	"EAGLES NEST LNDG RD"
4	40	402A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	40	402B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"WALKER SCH RD"
1672	40	402C	D3-1(8)	2	STREET NAME (1 Line)	42"	8"		REMAIN							0	0	0	"Eagles Nest Landing Rd"
871	40	403	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"		REMAIN							0	0	0	
871	42	421A	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"		REMAIN							0	0	0	
4	42	421A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	42	421B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"PADDOCK RD"
1672	42	421C	D3-1(8)	2	STREET NAME (1 Line)	42"	8"		REMAIN							0	0	0	"EAGLES NEST LNDG RD"
4	42	422A	R1-1(36)	1	STOP	36"	36"		REMAIN							0	0	0	
1672	42	422B	D3-1(8)	2	STREET NAME (1 Line)	36"	8"		REMAIN							0	0	0	"PADDOCK RD"
1672	42	422C	D3-1(8)	2	STREET NAME (1 Line)	42"	8"		REMAIN							0	0	0	"EAGLES NEST LNDG RD"
871	42	423	W3-1(30)	1	STOP AHEAD (Symbol) - 30x30	30"	30"	6.25	NEW		1				SOIL	1	0	0	
																0	0	0	
																0	0	0	
																0	0	0	
PAGE TOTALS								12.50		0	2		0	0		2	0	0	
JOB TOTALS								12.5		0	2		0	0		2	0	0	

Unofficial Website Copy

Y:\TRAFFIC\PROJECTS\T2015\T201506102\SIGNING & STRIPING\5-EAGLE NEST LANDING ROAD\BORDER.DGN

DELAWARE
DEPARTMENT OF TRANSPORTATION

ADDENDUMS / REVISIONS

PAVEMENT & REHABILITATION
NORTH II, 2015 - LOCATION 6
EAGLES NEST LANDING RD (ROAD 465)

CONTRACT	BRIDGE NO.	-
T201506102	DESIGNED BY: JVB	
COUNTY		
NEW CASTLE	CHECKED BY: MS	

SIGN SCHEDULE

SHEET NO. 48
TOTAL SHTS. 48