

STATE OF DELAWARE

DEPARTMENT OF TRANSPORTATION

800 BAY ROAD
P.O. BOX 778
DOVER, DELAWARE 19903

JENNIFER COHAN
SECRETARY

VIA WEBSITE POSTING AND OVERNIGHT DELIVERY

October 31, 2019

Contract No. T200411209.01 Federal Aid Project No. ESTP-S028(8) SR 24, Mulberry Knoll to SR 1 Sussex County

Ladies and Gentlemen:

Enclosed is Addendum No. 2 for the referenced contract consisting of the following:

- 1. The Bid Proposal Cover, revised, to be substituted for the same page of the Proposal.
- 2 Thirteen (13) pages, Utility Statement, revised and replaced with a fifteen (15) page Statement.
- 3. Twelve (12) pages, Bid Proposal Forms, pages 3 through 13, revised, to be substituted for the same pages in the Proposal and page 14 has been added.
 - The following Item Numbers have been added: 403000, 905002 and 905004
 - The following Item Numbers have been deleted: 851003 and 851004
 - The following Item Numbers have revised quantities: 601032, 602009, 701018, 705001, 705002, 905005 and 907017
- 4. One (1) page, Appendix B Technical Specifications for Waterline Work, page 16, revised, to be substituted for the same page in the Appendix.
- 5. Bid Express Amendment File No. 1.

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,
~signature on file~
Connie Ivins
Competitively Bid Contracts Coordinator
Delaware Department of Transportation

STATE OF DELAWARE



DEPARTMENT OF TRANSPORTATION

BID PROPOSAL for

CONTRACT T200411209.01

FEDERAL AID PROJECT NO. ESTP-S028(8)

CFDA NO. 20.205

SR 24, MULBERRY KNOLL TO SR 1

SUSSEX COUNTY

ADVERTISEMENT DATE: September 30, 2019

COMPLETION TIME: <u>537 Calendar Days</u>

SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DELAWARE DEPARTMENT OF TRANSPORTATION AUGUST 2016

Bids will be received in the Bidder's Room at the Delaware Department of Transportation's Administration Building, 800 Bay Road, Dover, Delaware prior to 2:00 P.M. local time October 29 November 19, 2019



STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION

800 BAY ROAD P.O. BOX 778 DOVER, DELAWARE 19903

JENNIFER COHAN SECRETARY

UTILITY STATEMENT
August 26, 2019
REVISED OCTOBER 24, 2019
T200411209
ESTP – S024 (8)
P6 # 06-00909
SR 24 MULBERRY KNOLL TO SR 1 (Phase I)
Sussex County

The following utility companies maintain existing facilities within the project limits:

Delaware Electric Co-Operative Delmarva Power (DPL) Crown Castle/Lightower/ Fibertech Comcast Verizon Chesapeake Utilities Tidewater Sussex County Engineering

The following utility companies are required to perform proposed utility relocations to existing facilities as described. Additional utility relocations during construction will be accomplished by the respective utility owner as directed by the District Engineer.

DEC/ DPL

SR 24, WEST OF PLANTATION & WARRINGTON INTERSECTION

DEC OWNS UTILITY POLES AND MAINTAINS A 3 PHASE AERIAL ELECTRIC SPAN ON THE FOLLOWING POLES, (WITH DPL OCCUPANCY BENEATHE/ "UNDERBUILT")



(BEGINNING AT THE WESTERN LIMITS OF THE CONSTRUCTION PROJECT, AND PROCEEDING EASTWARD.)

DEC # 32877	NW (LEFT) OFFSET	429 + 97	RLO
DEC # 32878	NW (LEFT) OFFSET	432 + 97	RLO
DEC # 32879	NW (LEFT) OFFSET	435 + 90	RLO
DEC # 32880	NW (LEFT) OFFSET	438 + 60	RLO
DEC # 32881	NW (LEFT) OFFSET	441 + 65	RLO
DEC NEW UTILITY	POLE INSTALLED	441 + 50	
		442 + 00	
DEC NEW UTILITY	POLE INSTALLED	443 + 50	
DEC # 32882	NW (LEFT) OFFSET	443 + 90	RLO
DEC # 32884	NW (LEFT) OFFSET	446 + 00	DND
DEC # 32885	NW (LEFT) OFFSET	446 + 70	DND

SR 24, EAST OF PLANTATION & WARRINGTON

DPL OWNS UTILITY POLES AND MAINTAINS A 3 PHASE AERIAL ELECTRIC SPAN ON THE FOLLOWING POLES, (WITH DEC OCCUPANCY BENEATHE/ "UNDERBUILT")

DEC # 32887	NW (LEFT) OFFSET	450 + 00	RLO
DPL # 59975 / 59	NW (LEFT)	450 + 90	DND
	OFFSET		
DPL # 5988 / 20	NW (LEFT)	450 + 95	DND
	OFFSET		
DPL # 59994 / 83	NW (LEFT)	454 + 00	DND
	OFFSET		
DPL # 60009/ 00	NW (LEFT) OFFSET	456 + 53	DND
DPL # 36002 / 24	NW (LEFT) OFFSET	458 + 90	DND
DI L # 30002 / 24	NW (LEFT) OFFSET	436 + 90	DND
DPL # 60039 / 36	NW (LEFT) OFFSET	461 + 05	DND
*DPL # 60055 / 53	NW (LEFT) OFFSET	463 + 30 & 463 +	TRNSFRMR 6 cans
		45	
DPL # 60068 / 68	NW (LEFT) OFFSET	465 + 48	RLO
DPL # 60081 / 83	NW (LEFT) OFFSET	467 + 48	RLO
DIL# 00001 / 63	NW (LEFT) OFFSET	407 + 40	KLU
DND # 94/ 98	NW (LEFT) OFFSET	469 + 48	DND
			Secret Southmen
DND # 10 / 18	NW (LEFT) OFFSET	471 + 62	DND
# 20 / 30 + CBINET	NW (LEET) OFFGET	172 50	DND
# 20 / 30 + CBINE I	NW (LEFT) OFFSET	473 + 50	DND

# SG7/M142/8	NW (LEFT) OFFSET	475 + 60	DND
DPL # 60142 / 55	NW (LEFT) OFFSET	477 + 10	DND
DPL # 60155 / 71	NW (LEFT) OFFSET	479 + 05	NO IMPACT
DPL # 61068 / 85	NW (LEFT) OFFSET	481 + 05	NO IMPACT
DPL # 60178 / 98	NW (LEFT) OFFSET	482 + 50	NO IMPACT
DPL # 60183 / 02	NW (LEFT) OFFSET	483 + 30	NO IMPACT

PLANTATION ROAD (NORTHERN OFFSET OF SR 24 INTERSECTION)

DPL OWNS UTILITY POLES AND MAINTAINS 3 PHASE AERIAL ELECTRIC SPAN ON THE FOLLOWING POLES, (WITH DEC OCCUPANCY BENEATHE/ "UNDERBUILT")

DEC # 32886	NW	448+00	
DPL # 59950/ 06137	WESTERN OFFSET	807 + 50	3 –PHSE SPAN
DEC # 32887			TRAVESES
			PLNTATION UNTO
			NE LEG OF
			INTERSCTN TO
			32887
DPL # 59959/06140	WESTERN OFFSET	805+00	RLO
DEC # 32888			
DEC # 32904	EASTERN OFFSET	804 + 90	RLO
DPL # 59932/06174	WESTERN OFFSET	803+20	RLO
DEC # 32906			
DPL # 59926/06182	WESTERN OFFSET	802+25	RLO
DEC # 06182			
DEC # 32907	EASTERN OFFSET	802 + 25	RLO
UNMARKED POLE	WESTERN OFFSET	799+00	DND

WARRINGTON ROAD (SOUTHERN OFFSET OF SR 24 INTERSECTION)

DEC OWNS UTILITY POLES AND MAINTAINS 3 PHASE AERIAL ELECTRIC SPAN ON THE FOLLOWING POLES, (WITH DPL OCCUPANCY "UNDERBUILT")

DEC # 32909	WESTERN OFFSET	810 + 05	RLO
DEC # 32891	WESTERN OFFSET	811 + 75	RLO
DEC # 32892	WESTERN OFFSET	813 +75	RLO
*DEC # 328933	WESTERN OFFSET	816 + 40	RLO
TRANSFRM CANS			
ATTACHED TO			
TWO POLES			

NOTES SPECIFIC TO UTILITY POLE RELOCATION:

- APPROXIMATELY 18 EXISTING UTILITY POLES REQUIRE UTILITY RELOCATION
- TALLER POLES ARE WARRANTED AT PROPOSED TRAFFIC SIGNAL MAST ARM'S FOR VERTICAL CLEARANCE (AS SHOWN ON PLANS)
- ADVANCED UTILITY POLE RELOCATION IS SCHEDULED TO BEGIN IN OCTOBER 2019; IT IS ANTICIPATED THAT ALL UTILITY POLE RELOCATIONS ARE TO BE ACCOMPLISHED IN ADVANCE OF THE CONSTRUCTION DATE.
- UTILITY POLES LABELED FOR RLO WILL BE MOVED TO A POSITION REARWARD OF ITS EXISTING LOCATION PER COMPLIANT WITH CLEAR-ZONE AND PROPOSED FEATURES AS SHOWN ON PLANS.

10. 24.2019 DEC PROPOSES TO INSTALL A BURIED ELECTRIC CONDUIT IN THE NORTHERN OFFSET OF SR 24 BETWEEN STATIONS 441 + 50 UNTO 448 + 00.

10.24.2019 THE POLE OWNERSHIP WILL TRANSFER UNTO VERIZON. VERIZON SHALL ASSUME RESPONSIBILITY OF MAINTAINING THE UTILITY POLES COMPLIANCE WITH CLEAR ZONE REGULATIONS.

10.24.2019 DEC PROPOSES TO INSTALL A 10" HDPE CASING CONTAINING 3 CONDUITS, VIA DIRECTIONAL DRILL FROM THE NW LEG OF THE PLANTATION RD & SR 24 INTERSECTION, UNTO THE SW LEG OF THE WARRINGTON RD & SR 24 INTERSECTION.

10.24.2019 (THE PROPOSED INSTALLATION WILL OCCUR ON THE WESTERN OFFSET OF THE PLANTATION ROAD AND WARRINGTON ROAD CONSTRUCTION ALIGNMENT).

10.24.2019 THE PROPOSED U.G. INSTALLATION WILL EXTEND (SOUTHWARD ON WARRINGTON RD) UNTO STATION 812 + 00 AND TERMINATE AT NEWLY INSTALLED AT GRADE ELECTRIC CABINETS IN THE WESTERN OFFSET OF WARRINGTON ROAD.

10.24.2019 DEC PROPOSES TO INSTALL TWO 2" HDPE CASING PIPES CONTAINING 3 CONDUITS IN EACH BENEATH WARRINGTON ROAD AT STATION 812 + 00. THE INSTALLATION WILL TERMINATE ON THE EASTERN OFFSET OF WARRINGTON ROAD, BEYOND THE CONSTRUCTION LIMITS.

DEC requires four months to perform utility relocations after receiving 30days advanced notice.

DPL requires four months to perform utility relocations after receiving 30days advanced notice.

10.24.2019 ALL PROPOSED UTILITY POLE RELOCATIONS FOR DEC & DPL ARE ANTICIPATED TO OCCUR BEFORE CONSTRUCTION.

10.24.2019 BEGINNING IN THE SE LEG OF THE WARRINGTON AND SR 24 INTERSECTION, DPL MAINTAINS EXISTING AT GRADE ELECTRIC CABINETS, AND AN

EXISTING BURIED ELECTRIC CABLE BETWEEN STATION 809 + 50 (ON WARRINGTON), UNTO STATION 464 + 00 ON THE SOUTHERN OFFSET OF SR 24.

10.24.2019 THE CABINET BOXES AND EXISTING U.G. CABLE WILL BE RELOCATED REARWARD FROM ITS EXISTING POSITION TO AVOID CONFLICT WITH PROPOSED CONSTRUCTION.

THE CONDUIT SHALL BE BURIED IN A PRIVATE EASEMENT OBTAINED BY DPL.

10.24.2019 ALL DPL UNDERGROUND UTILITY RELOCATIONS ARE ANTICIPATED TO OCCUR BEFORE CONSTRUCTION.

Utility relocations shall occur in advance of the construction project after pertinent features are stakedout/identified in the field as warranted (i.e. right-of-way, proposed road/bridge features, clearing and grubbing; cuts and fills) and upon issuance of Notice to Proceed from the Utility Engineer.

Crown Castle/Lightower/Fibertech

Crown Castle/Lightower/Fibertech maintains an existing aerial fiber optic span on the existing **DEC/DPL** pole span in the northern offset of SR 24 from the beginning of the construction limits on SR 24 unto the NW quadrant of the SR 24 Plantation Rd intersection.

The aerial span will be transferred onto the new DEC/DPL pole span.

Crown Castle/Lightower/Fibertech maintains an existing buried cable on the eastern offset of Plantation Rd.

The existing buried facility has an origin beyond the northern most limits of Plantation Rd (beyond the construction limits); and continues unto the NE quadrant of Plantation Rd and SR 24; and terminates at an existing utility pole at station 450 + 00.

On the northern offset of SR 24 at station $\underline{450 + 00}$ Crown Castle resumes its aerial stationing on the Existing utility pole span unto station $\underline{462 + 10}$.

10.24.2019 REMOVED HIGHLIGHT OVER TEXT

At station 462 +10 Crown Castle maintains an existing buried cable beneath SR 24.

On the southern offset of SR 24 at station 462 + 10 Crown Castle's existing buried cable Is in conflict with proposed pipe 60; and will adjust its existing buried facility.

Utility relocations shall occur in advance of the construction project after pertinent features are stakedout/identified in the field as warranted (i.e. right-of-way, proposed road/bridge features, clearing and grubbing; cuts and fills) and upon issuance of Notice to Proceed from the Utility Engineer.

Crown Castle/Lightower/Fibertech requires 45 days months to perform utility relocations after receiving 30days advanced notice.

Proposed Permit Work Aug/Sept 2019

On the northern offset of the SR 24 between stations 429 + 00 unto 446 + 00 attach a new aerial facility on the existing utility pole span. (Additional slack included to compensate for future utility pole relocation).

10.24.2019 REMOVED HIGHLIGHT OVER TEXT

On the northern offset of SR 24 at station 446 + 00 (at the existing utility pole # 32884) a proposed buried installation will occur that continues in two directions:

- Proceeding northwest on the western offset of Plantations Rd unto the end of the construction limits.
- Bore below existing SR 24 (a 2" conduit at a vertical depth of 48" below existing grade at station 447 + 00, and continue southward unto the end of the Construction limits on Warrington (on the western offset).

On the northern offset of SR 24 at station 462 + 10, Crown Castle/Lightower/Fibertech proposes to install a buried fiber optic in the northern (left) offset SR 24 unto station 475 + 20.

At station 475 + 20 the u.g. proposal turns (90 degrees) perpendicular to the construction baseline), and continues beyond the limits of construction onto private property.

Comcast

Comcast maintains an aerial facility on existing DPL and DEC pole spans as follows:

- On the northern offset of <u>SR 24</u> from the beginning of the project limits at station 429 + 00 unto the end construction limits at station 486 + 00.
- On the eastern offset of the <u>Plantation Rd</u>/ <u>Warrington Rd</u> construction alignment, from the northern construction limits at station 798 +00 unto the southern construction limits at station 817 + 50.

Comcast proposes to follow suit of the existing pole owners, and transfer its existing aerially facilities onto the newly installed pole alignment.

Comcast maintains an existing underground cable on the northern offset of SR 24, between stations 461 + 00 and 465 + 40.

Comcast proposes to install a new buried facility between stations 461 + 00 and 465 + 40 in advance of construction project and abandon the existing facility in place after the new underground line is in service.

In the northern offset of SR 24 at station 471 + 60, Comcast's existing cable descends/dips underground at existing pole # 60107 / 06314 and continues north-westward on the western offset of Bryn Mawr Drive (i.e. private drive) beyond the construction limits.

The existing buried facility is in conflict with proposed Pipe 2. Comcast will elect to relocate the existing facility or perform adjustments during construction.

On the north-eastward offset of Bryn Mawr Drive, Comcast maintains an existing underground cable that originates at the existing at-grade cabinet box (at station 473 + 50 (left)), and proceeds unto station 472 + 90 and extends beneath the SR 24 construction alignment (perpendicularly), unto the southern offset of SR 24. Thereafter it continues onto private property beyond the construction limits.

Comcast will elect to adjust/ or relocate the existing facility during construction to avert conflict with PC 1 on the northern offset of station 472 + 90; and with the proposed swale on the southern offset of 472 + 90.

Comcast's existing underground facility (in the northern offset of SR 24) between stations 473 + 00 unto 473 + 50 will remain.

Comcast's spot - adjustments during construction will coincide with the construction schedule. The state's contractor will perform open-cut/exposure of existing road, sidewalk, and other existing items as warranted and allot a time to be determined in the field for Comcast to make adjustments to its existing buried facilities proportional to the scope of work determined at that time.

Comcast is proposed to perform portions of its utility relocations in advance of the construction project after pertinent features are staked-out/identified in the field as warranted (i.e. right-of-way, proposed road/bridge features, clearing and grubbing; cuts and fills) and upon issuance of Notice to Proceed from the Utility Engineer.

Comcast requires 2 months to perform advanced utility relocations after receiving 30days advanced notice.

VERIZON

Verizon maintains two existing aerial fiber optic cables on the northern offset of the SR 24 on existing utility poles as follows:

- At the beginning of the construction limits at station 428 + 50 unto station 461 + 00.
- Between stations 465 + 00 unto 484 + 00 (i.e. the end of the construction limits)

Verizon's two aerial fiber optic cables will be transferred onto newly installed /relocated utility poles owned by DPL and or DEC.

Verizon's existing underground facilities within the construction limits are as follows:

• Verizon maintains an existing 450 pair buried cable on the **SOUTHERN OFFSET** of the SR 24 construction baseline between stations 428 + 50 (*i.e.* at the beginning of the construction limits) unto the **SW** leg of the **SR 24 & Warrington Road** intersection.

• At station 446 + 75 a 100 pair buried cable extends perpendicular to the construction baseline from the northern offset of SR 24 unto its southern offset road shoulder.

The (existing) buried cable proceeds southward along the western offset of **Warrington Road**'s road shoulder; extends beneath Warrington Rd into the **SE** leg of the SR 24 & Warrington Road intersection at station 809 + 50; and from there, a 600 pair cable proceeds northward (*for approx. 200 ft. along the eastern offset of Warrington Road's – road shoulder*); and then eastward onto the **SOUTHERN OFFSET** of the SR 24 road shoulder unto station 455 + 00.

On the **SOUTHERN** offset of SR 24's road shoulder at station 455 + 00, a 600 pair cable, and a 200 pair cable continue eastward on SR 24 unto station 456 + 48L.

On the **SOUTHERN** offset of SR 24's road shoulder, at station 456 + 48L a buried fiber-optic cable (encased in a conduit), and (2) 200 pair u.g. cables extend perpendicularly to the construction baseline from the northern offset of SR 24 into the southern offset road shoulder.

On the **SOUTHERN** offset of SR 24's road shoulder at station 456 + 48L a 600 pair buried cable continues eastward unto station 473 + 00.

On the **SOUTHERN OFFSET** of SR 24's road shoulder an existing 300 pair cable is buried between stations 473 + 00 unto 476 + 25.

In the **NORHTERN OFFSET of SR 24's** road shoulder Verizon maintains (2) existing buried fiber optic cables between stations 461 + 00 and 465 + 00.

In the **NORTHERN OFFSET of SR 24's** road shoulder Verizon maintains a 25 pair buried cable between stations 467 + 25 and 470 + 97.

In the **NORTHERN OFFSET of SR 24** at station 470 + 97 a 1500 pair buried cable extends perpendicularly to the construction baseline from the northern offset unto the southern offset road shoulder.

In the **NORTHERN OFFSET of SR 24** a 600 pair buried cable continues eastward from station 470 + 97 unto the end of the SR 24 construction limits.

Verizon maintains an existing 100 pair buried cable on the WESTERN offset of Plantations Road. The buried cable extends from the NW leg of the SR 24 & Plantations Rd intersection unto a northward position beyond the construction limits of Plantations Rd.

The buried facility will be relocated rearward of the proposed sidewalk as shown on plans.

Verizon maintains an existing 50 pair buried cable, perpendicular to the construction alignment at station 805 + 00. The existing u.g. facility extends from the northern offset of Plantations Rd unto the southern.

The existing facility will be replaced with a new underground cable perpendicular to the construction alignment, and thereafter proceed westward and attach to the existing underground facility at station 802 + 00.

Verizon maintains an existing 50 pair buried cable on the western offset of Warrington Rd. beneath the existing road shoulder.

The cable begins at station 809 + 50 in SW leg of the SR 24 & Warrington Rd intersection and continues southward on Warrington Rd unto a position beyond the construction limits.

Verizon proposes to remain in place beneath the proposed road box.

Additionally, Verizon proposes underground utility relocations on the (left) offset of Plantation Road: Beginning at station 802 + 00 install a new 100 pair underground facility rearward of the edge of the proposed sidewalk's & on the interior of the proposed pole alignment.

The proposed installation begins at station 802 + 00 and extends southward along the western offset of Plantation Road unto the NW leg of the Plantation Rd & SR 24 intersection.

The proposed 100 pair extends into the SW leg of the SR 24 & Warrington Rd intersection at Station 446 + 75; and terminates at an existing pedestal/splice point on the WESTERN offset of Warrington Rd at station 810 + 00.

Additionally, on Plantation Rd, Verizon's proposed u.g. facility extends from the western offset of Plantation Rd unto the EASTERN OFFSET of Plantation Rd at station 804 + 95.

Additionally, in the SW leg of the SR 24 & Warrington Rd intersection, Verizon proposes to extend a 200 pair cable into the SE leg of SR 24 and Warrington Rd at station 809 + 75.

The 200 pair proposed cable will continue eastward onto SR 24 unto station 457 + 30 where it converts into a 600 pair buried cable, and continues unto station 465 + 50 and converts unto a 400 pair proposed cable unto station 467 + 90, where it connects to an existing 600 pair cable.

The buried facility will be relocated rearward of the proposed sidewalk as shown on plans.

Verizon's aerial utilities on DEC/DPL pole spans are to be transferred unto the new utility pole alignment in advance of the construction project, and subsequent to the proposed aerial transfers of existing aerial utilities (vertically above) their existing aerial span.

Verizon's underground utility relocations are to occur prior to the construction schedule and precede Verizon's aerial utility relocation.

Verizon requires four months to perform utility relocations after receiving 30days advanced notice.

CHESAPEAKE UTILITIES

Chesapeake Utilities maintains an existing 8 ½" HDPE buried gas main within the project limits as follows:

On the **Southern Offset of SR 24** at the beginning of the construction limits between stations 429+00 unto station 448 + 00 (i.e. the **SW** quadrant of the SR 24 & Warrington Intersection).

The 8 ½" gas measured 4.68ft below existing grade, and will remain in place.

The (8 ½") HDPE gas main extends into the SW leg of the Warrington Rd and SR 24 intersection it maintains 9.53ft of cover.

The existing 8 ½" gas main is proposed to remain in place during construction of the proposed channelized island and installation of the proposed signal mast arm & base. The location of the base will be determined in the field to assess if space/location tolerances allow the existing gas main to remain in place, and achieve a lateral offset.

The (8 ½") HDPE gas main proceeds into the SE offset of the SR 24 & Warrington Rd intersection at station 809+70; and from there proceeds into (2) two directions:

1. Southward on the eastern offset of Warrington Rd, and continuing therein unto the end of the construction limits on Warrington Rd.

(TH 89) The 8 ½" gas main is measured at 2.74ft below existing grade.

2. At station 809 + 75 it extends into the eastern offset of Warrington Rd; and proceeds northward (beneath SR 24) into the NE offset of Plantation Rd, and continues northward unto the end of the construction limits.

In the NE leg of SR 24 and Plantation Rd the existing 8 ½" gas main is measured as 2.98ft below existing grade.

At station 802 + 50 the existing $8 \frac{1}{2}$ " gas main is in conflict with the proposed P/74 and DI / 45. (TH #86 3.19ft below existing grade).

A second assessment of the exact location of the gas main and the location of the proposed pipe and proposed drainage inlet will occur during construction to determine the final placement relocation of the existing gas main/and or the proposed pipe and inlet.

NEW: THE CONTRACTOR IS TO PERFORM TEST HOLES IN THE FIELD TO DETERMINE THE DEPTH OF THE EXISTING GAS MAIN.

CHESAPEAKE UTILITIES SHALL PREPARE A UTILITY RELOCATION DESIGN PRIOR TO THE START OF CONSTRUCTION. IF THE EXISTING GAS MAIN WARRANTS UTILITY RELOCATION DURING CONSTRUCTION, THIS DESIGN WILL BE IMPLEMENTED DURING CONSTRUCTION HAVING AN ALLOTMENT OF 30DAYS TO COMPLETE. (ADDITIONAL TIME SHALL BE ALLOTTED BY THE DIRECTION OF THE DELDOT CONSTRUCTION SUPERVISOR.)

Project Notes Specific to Chesapeake Utilities:

The contractor shall be aware that Chesapeake Utilities has requirements while working near Chesapeake Utilities pipelines. These requirements are general in nature and not specific. These requirements are not intended to be all-inclusive. Actual field conditions may change the requirements. Contractor should contact Chesapeake Utilities and consult with their engineer prior to initiating construction and abide by all Federal, State, and Local rules and regulations.

Please coordinate construction activity with your assigned line locator according to the general guidelines below. Your line locator can help determine if additional contacts are required with Chesapeake Utilities Engineering Department before start of excavation activity.

- 1. It shall be the contractor's responsibility to use the Miss Utility One Call System.
- 2. It shall be the contractor's responsibility to contact and coordinate with Chesapeake Utilities before starting any construction above or near the pipeline. Chesapeake Utilities may elect to have standby personnel on the job site during construction activity.
- 3. It shall be the contractor's responsibility to contact and coordinate with Chesapeake Utilities before moving heavy equipment above or near the pipeline. Chesapeake Utilities may require extra cover, berm or ramp, timber mats, etc. These measures are to be determined by Chesapeake Utilities depending on field conditions.
- 4. If the pipeline is exposed and suspended, it shall be the responsibility of the contractor to coordinate with Chesapeake Utilities the appropriate supporting measures. These measures are to be determined by Chesapeake Utilities depending on field conditions.
- 5. If the pipeline is exposed, it shall be the responsibility of the contractor to protect the pipeline from construction activity and the traveling public.
- 6. A minimum clearance of 12" shall be maintained between Chesapeake Utilities' pipeline and other underground utilities and structures. If this cannot be maintained, Chesapeake Utilities shall determine an appropriate means of protection to the pipeline.

IN EVENT OF PIPELINE EMERGENCY, CALL TOLL FREE 1-800-427-2883.

TIDEWATER

Tidewater maintains an existing water main in the northern offset of SR 24, from the beginning of the construction limits on SR 24 (at station 429 + 00) unto the end of the construction limits on SR 24 (at station 486 + 00).

The existing water main varies in sizes as noted:

SIZE	BEGINNING	END
12"	STA. 429 + 00	STA. 463 + 10
8"	STA. 463 + 10	STA. 477 + 00
8"	STA. 477 + 00	STA. 483 + 00
6"	STA. 483 + 00	STA. 486 + 50

Tidewater maintains an existing 12" water main on the eastern (left) offset Plantation Rd/Warrington Rd construction alignment between construction limit stationing 798 + 00 (on Plantation Rd) unto construction limit stationing 817 + 50 (on Warrington Rd).

Tidewater maintains an existing 8" buried water main on the northwestern offset of the proposed construction alignment of the existing service road between stations 10 + 50 unto 13 + 00.

Tidewater maintains an existing 8" encased buried water main beneath SR 24, that extends northward and southward (perpendicular to the construction alignment) at station 463 + 52.

Tidewater maintains an existing 8" buried water main beneath SR 24, that extends northward and southward (perpendicular to the construction alignment) at station 477 + 20.

Tidewater maintains an existing 8" buried water main beneath Plantation Rd, that extends eastward and westward (perpendicular to the construction alignment) at station 799 + 51.

Tidewater proposes to install a new 12" buried water main in the northern offset of <u>SR 24</u> from the beginning of the construction limits unto station 444 + 25 wherein it connects into An existing 12" water main.

The abandoned main between noted construction limits will be cut/capped and filled and/or removed / discarded as debris by the State's contractor.

Tidewater proposes to install a new 12" water main on the northern offset of \underline{SR} 24, beginning at station 459 + 00 unto station 463 + 25. The existing 8" water main between the noted construction limits will be abandoned and cut/capped and filled and/or removed / discarded as debris by the State's contractor.

Tidewater proposes to install a new 12" water main on the eastern offset of <u>Plantation Rd</u> Between station 798 + 10 unto station 807 + 25 in the NE quadrant of the SR 24 and Plantation Rd intersection. At station 807 + 25 the proposed 12" water main connects into an existing 15" water main in the NE quadrant that abides rearward of the proposed sidewalk and will remain in place.

Tidewater's proposed utility relocations will be performed by the state's contractor. Any adjustments to existing tidewater service lines shall be performed as warranted by the state contractor during the utility relocation and/or new installation of tidewater underground facilities throughout the project limits.

Sussex County Engineering

Sussex County maintains an existing sanitary sewer in the southern offset of SR 24.

The existing sewer consists of 4" PVC force main and 8" PVC gravity sewer.

The 4" PVC force main begins at pump station on the backside of the Beacon Middle School along Mulberry Knoll Road, approximately 1,200 LF south of the intersection with SR 24 (at station 419 + 00).

The existing force main runs below grade along the eastern shoulder of Mulberry Knoll road unto to SR 24.

The force main then continues along the southern offset of SR 24 until it discharges into a manhole at the beginning of the 8" gravity sewer (SR 24 station 463+60).

The 8" PVC gravity sewer continues from that manhole unto the end of the construction limits on SR 24 (at station 486 + 00) where it ties-in to a larger sewer.

The gravity sewer includes eight (8) existing connections, primarily laterals that cross SR 24 from the northern side.

The gravity sewer includes lateral connections on the south side as well.

Sussex County also maintains a second separate existing 4" force main on the northern offset of SR 24 from station 464+35 until the end of the construction limits.

The existing sewer varies in sizes as noted:

SIZE	BEGINNING	END
4" force main (south)	STA. 419 + 00	STA. 463 + 60
8" gravity	STA. 463 + 60	STA. 485 + 90
4" force main (north)	STA. 464 + 35	STA. 486 + 00

Sussex County proposes to install a new 4" buried force main in the southern offset of <u>SR 24</u> from a tie-in point to the existing 4" force main (approximately 300 LF south along Mulberry Knoll Road) to the discharge into the existing manhole at the start of the 8" gravity sewer (at station 463+60). This new force main will be a replacement for the existing 4" force main in the southern offset.

The existing 4" force main along this area in the southern offset will be removed and demolished. A select area from approximately STA 447+50 to STA 448+80 will be abandoned in place and filled with flowable fill.

The existing 8" gravity sewer will remain in place. Proposed work related to the 8" gravity sewer will include the additional of new laterals on the southern side of SR 24 and the relocation of existing cleanouts on the north side to move them out of the proposed roadway.

Sussex County Engineering's proposed utility relocations will be performed by the State's Contractor.

General Notes:

- 1. The Contractor's attention is directed to Section 105.09 <u>Utilities</u>, Delaware Standard Specifications, August 2016. The Contractor shall contact Miss Utility (1-800-282-8555) two working days prior to any excavation. The Contractor is responsible for the support and protection of all utilities when excavating. The Contractor is responsible for ensuring proper clearances, including safety clearances, from overhead utilities for construction equipment. The Contractor is advised to check the site for access and operating purposes for his equipment and, if necessary, make arrangements directly with the utility companies for field adjustments for adequate clearances.
- 2. The information shown in the Contract Documents, including the Utility Statement and the Utility Schedule contained herein, concerning the location, type and size of existing and proposed utilities, their locations, and construction timing has been compiled by the preparer based on information furnished by each of the involved Utility Companies. It shall be the responsibility of the State's Contractor to verify all information and coordinate with the Utility Companies prior to and during construction, as specified in Section 105.09 of the Standard Specifications.
- 3. It is understood and agreed that the Contractor has considered in his bid all permanent and temporary utility appurtenances in their present and relocated positions as shown on the plans or described in the Utility Statement or are readily discernible and that no additional compensation will be allowed for any delays, inconvenience, or damage due to any interference from the utility facilities and appurtenances or the operation of moving them, except that the Contractor may be granted an equitable extension of time unless the delay is caused by the Contractor's delay in having the site conditions ready for the utility relocation work after the Contractor has provided the advance notice that the site conditions would be ready for the utility relocation work. The contractor's means and method of construction are not taken into account when known utility conflicts are identified. If the Contractor's means and method of construction create a utility conflict the Utility Statement will prevail in discussions with the utility and the Contractor. The


State's Contractor shall be responsible for any costs associated with any temporary outages; holding, bracing and shielding of utility facilities; temporary relocations; or permanent relocations that are not specifically identified in this utility statement or shown in the contract plan set.

- 4. Coordination and cooperation among the Utility Companies and the State's Contractor are of prime importance. Therefore, the Contractor is directed to contact the following Utility Company representatives with any questions regarding this work prior to submitting bids and work schedules. Proposed work schedules should reflect the Utility Companies' proposed relocations. The Utility Companies do <u>not</u> work on weekends, nights or legal holidays.
- 5. As outlined in Chapter 3 of the DelDOT Utilities Manual, individual utility companies are responsible for obtaining all required permits from municipal, State and federal government agencies and railroads. This includes but is not limited to water quality permits/DNREC Water Quality Certification, DNREC Subaqueous Lands/Wetlands permits, DNREC Coastal Zone Consistency Certification, County Floodplain permits (New Castle County only), U.S. Coast Guard permits, US Army Corps 404 permits, sediment and erosion permits, and railroad crossing permits.
- 6. Individual utility companies are required to restore any areas disturbed in conjunction with their relocation work. If an area is disturbed by a utility company and is not properly restored, the Department may have the State's Contractor perform the necessary restoration. Any additional costs incurred as a result will be forwarded to the utility company.
- 7. 16 Del. C. § 7405B requires notification to and mutually agreeable measures from the public utility operating the electric line for any person intending to carry on any function, activity, work or operation within dangerous proximity of any high voltage overhead electric lines. All contractors/other utilities must also maintain a minimum distance of 10'-0" from all energized lines. Additional clearance may be required from high voltage transmission lines.
- 8. Any existing facilities that are comprised of hazardous materials will be removed by the Utility Company unless otherwise outlined in the contract documents or language above. Any existing facilities containing hazardous materials will be purged by the Utility Company unless otherwise outlined in the contract documents or language above.

10.24.2019

NEW UTILITY RELOCATION BAR CHART





Troy Dickerson	DEC	tdickerson@delaware.coop	302-349-3144
Tom Wright	DEC	twright@delaware.coop	302-349-3130
Tony Rutherford	DEC	trutherford@delaware.coop	302-349-3125
William Whitaker	DPL	William.whitaker@delmarva.com	302-934-3356
Bill McBane	DPL	bill.mcbane@delmarva.com	302-934-3358
Mike Sullivan	COMCAST	Mike Sullivan2@comcast.com	302-841-6316
George Zang	VERIZON	george.w.zang@verizon.com	302-422-1238
Eric Pulliman	VERIZON	eric.t.pulliman@verizon.com	302-422-1431
Garth Jones	CHESPK UTIL.	gjones@chpk.com	302-734-6797
Greg Courey	TIDEWATER	gcoury@tidewater.com	302-747-1306
Brad Hawks	SUSSEX CO. ENG.	bhawkes@sussexcountyde.gov	302-855-7379

DIVISION OF TRANSPORTATION SOLUTIONS

DELDOT UTILITY SECTION
For Jeff Steward

3

DELAWARE DEPARTMENT OF TRANSPORTATION SCHEDULE OF ITEMS

PAGE: DATE:

CONTRACT ID: T200411209.01 PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE		APPROX.	UNIT PRIC	CE	BID AM	OUNT
NO	DESCRIPTION	QUANTITY AND UNITS	DOLLARS	CTS	DOLLARS	CTS
	403000 BITUMINOUS CONCRETE AND/OR COLD-LAID BITUMINOUS (TRM) CONCRETE	545.000				
	601032 REINFORCED CONCRETE PIPE, 15", CLASS IV	521.000 LF				
0220	601033 REINFORCED CONCRETE PIPE, 18", CLASS IV	28.000 LF				
0230	601053 REINFORCED CONCRETE PIPE, 15", CLASS V	1150.000 LF				
	601054 REINFORCED CONCRETE PIPE, 18", CLASS V	239.000 LF				
	601141 REINFORCED CONCRETE FLARED END SECTION, 15"	2.000 EACH				
	601142 REINFORCED CONCRETE FLARED END SECTION, 18"	1.000 EACH				
	602003 DRAINAGE INLET, 34" X 24"	11.000 EACH				
	602004 DRAINAGE INLET, 48" X 30"	4.000 EACH				
	602005 DRAINAGE INLET, 48" X 48"	7.000				

4

DELAWARE DEPARTMENT OF TRANSPORTATION SCHEDULE OF ITEMS

PAGE: DATE:

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE	l .	APPROX.		UNIT PR	ICE	BID AM	OUNT
NO	DESCRIPTION	QUANTITY AND UNITS		DOLLARS	CTS	DOLLARS	CTS
	602009 DRAINAGE INLET, 72" X 24"	6.	000				
	602010 DRAINAGE INLET, 72" X 48"	2.	000				
0320	602031 MANHOLE, 48" X 48"	2.	000				
	602100 REPLACE DRAINAGE INLET GRATE(S)	12.	000				
0340	602101 REPLACE DRAINAGE INLET FRAME(S)	12.	000				
0350	602130 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	4.	000				
	602132 ADJUSTING AND REPAIRING EXISTING MANHOLE	1.	000				
0370	602502 CONVERTING EXISTING CATCH BASIN TO MANHOLE	10.	000				
0380	701013 PORTLAND CEMENT CONCRETE CURB, TYPE 1-8	360.	000				
0390	701014 PORTLAND CEMENT CONCRETE CURB, TYPE 2	934.	000				

SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE		APPROX.	UNIT PR	ICE	BID AM	OUNT
NO	DESCRIPTION	QUANTITY AND UNITS	DOLLARS	CTS	DOLLARS	CTS
	701018 INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 1-8	6033.000 LF				
	701023 INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 3-8	400.000 LF				
	701032 CURB OPENING, 4' OPENING	7.000 EACH				
0430	702000 TRIANGULAR CHANNELIZING ISLANDS	2903.000 SF				
0440	705001 PORTLAND CEMENT CONCRETE SIDEWALK, 4"	36124.000				
0450	705002 PORTLAND CEMENT CONCRETE SIDEWALK, 6"	6623.000 SF				
0460	705005 PORTLAND CEMENT CONCRETE SIDEWALK, 8"	773.000				
0470	705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	290.000 SF				
0480	705008 PEDESTRIAN CONNECTION, TYPE 1	105.000				
0490	706000 MONUMENT	15.000 EACH				

SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

CONTRA	ACTOR :			
LINE	ITEM DESCRIPTION	APPROX. OUANTITY	UNIT PRICE	BID AMOUNT
		AND UNITS	DOLLARS CTS	DOLLARS CTS
0500	706001 RELOCATE MONUMENT	11.000 EACH		
	706500 RIGHT-OF-WAY MARKER, CAPPED REBAR	350.000 EACH		
0520	707001 RIPRAP, R-4	184.000		
0530	708002 GEOTEXTILES, SEPARATION	1092.000 SY		
0540	709006 PERFORATED PIPE UNDERDRAINS, 24"	728.000 LF		
	710500 INSTALLATION OF WATERMAIN AND ACCESSORIES	LUMP	LUMP	
	711501 SANITARY SEWER SYSTEM	LUMP	LUMP	
	727006 TEMPORARY CONSTRUCTION FENCE	1408.000 LF		
0580	760002 BIKE-FRIENDLY RUMBLE STRIPS, BITUMINOUS PAVEMENT	3075.000 LF		
	760012 PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT, VARIABLE DEPTH	87174.000 SYIN		

SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE		APPROX. QUANTITY AND UNITS		UNIT PRICE		BID AMOUNT	
NO	DESCRIPTION			DOLLARS	CTS	DOLLARS	CTS
	762000 SAW CUTTING, BITUMINOUS CONCRETE	LF	17724.000				
0610	762001 SAW CUTTING, CONCRETE, FULL DEPTH	LF	125.000				
0620	763000 INITIAL EXPENSE/DE-MOBILIZATION	LUMP		LUMP			
0630	763501 CONSTRUCTION ENGINEERING	LUMP		LUMP			
0640	763503 TRAINEE	HOUR	720.000		0.80000		576.0
	763509 CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	EAMO	20.000				
	763598 FIELD OFFICE, SPECIAL I	EAMO	20.000				
	801000 MAINTENANCE OF TRAFFIC	LUMP		LUMP			
0680	802003 ARROW PANELS TYPE C	EADY	1034.000				
	803001 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	EADY	84.000				

SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE	1	APPROX.	UNIT PRICE	BID AMOUNT	
NO	DESCRIPTION	QUANTITY AND UNITS	DOLLARS CTS	DOLLARS CTS	
0700	804001 FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY (FLOOD LIGHTS)	122.000 EADY			
0710	805001 PLASTIC DRUMS	119591.000 EADY			
0720	806001 TRAFFIC OFFICERS	558.000 HOUR	75.00000	41850.0	
	808002 FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	1012.000 EADY			
0740	810001 TEMPORARY WARNING SIGNS AND PLAQUES	18458.000			
0750	811003 FLAGGER, SUSSEX COUNTY, STATE	6672.000 HOUR			
0760	811015 FLAGGER, SUSSEX COUNTY, STATE, OVERTIME	1668.000 HOUR			
0770	813001 TEMPORARY BARRICADES, TYPE III	4720.000 LFDY			
0780	817002 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND, ALKYD-THERMOPLASTIC	5955.000 SF			
0790	817003 TEMPORARY MARKINGS, PAINT, 4"	63732.000 LF			

SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

	ACTOR :			
LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
0800	 817004 TEMPORARY MARKINGS, PAINT, SYMBOL/LEGEND	AND ONTIS 1171.000 SF		DOLLARS CIS
0810	817013 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	47459.000 LF		
0820	817015 PREFORMED RETROREFLECTIVE THERMOPLASTIC MARKINGS, BIKE SYMBOL	51.000 EACH		
0830	817031 REMOVAL OF PAVEMENT STRIPING	22415.000 SF		
0840	819016 INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH	4.000 EACH		
0850	819018 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	166.000 EACH		
0860	819019 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON MULTIPLE SIGN POSTS	52.000 SF		
0870	830001 CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE	29.000 EACH		
0880	830002 CONDUIT JUNCTION WELL, TYPE 4, 20" X 42-1/2" PRECAST CONCRETE	15.000 EACH		

DELAWARE DEPARTMENT OF TRANSPORTATION PAGE: SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

CONTR.	ACTOR :				
LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE	BID AMOUNT	
			DOLLARS CTS	DOLLARS CTS	
0890	830004 CONDUIT JUNCTION WELL, TYPE 7, 36" X 60" PRECAST POLYMER CONCRETE	6.000 EACH			
0900	830010 REMOVAL OF EXISTING JUNCTION WELL	13.000 EACH			
0910	830011 FURNISH AND INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 1	3.000 EACH			
0920	830012 FURNISH AND INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 4	1.000 EACH			
0930	831513 FURNISH AND INSTALL 2" SCHDULE 80 PVC CONDUIT (TRENCH)	25.000 LF			
0940	831514 FURNISH AND INSTALL 2-1/2" SCHEDULE 80 PVC CONDUIT (TRENCH)	10.000			
0950	831515 FURNISH AND INSTALL 3" SCHEDULE 80 PVC CONDUIT (TRENCH)	1114.000 LF			
0960	831516 FURNISH AND INSTALL 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	6538.000	·	 	
0970	831523 FURNISH AND INSTALL 2" GALVANIZED CONDUIT (TRENCH)	152.000 LF	·		

DELAWARE DEPARTMENT OF TRANSPORTATION PAGE: SCHEDULE OF ITEMS

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

DATE:

CONTRACTOR :__ ITEM DESCRIPTION APPROX. UNIT PRICE BID AMOUNT
QUANTITY -----AND UNITS DOLLARS CTS DOLLARS CTS LINE NO ______ 831545 FURNISH AND 0980 INSTALL 4" HDPE SDR-13.5 CONDUIT (BORE) LF 831572 FURNISH AND 0990 INSTALL SECOND AND 30.000 SUBSEQUENT ADDITIONAL LF 2-1/2" SCHEDULE 80 PVC CONDUITS IN TRENCH OR OPEN CUT 832008 FURNISH AND 1000 INSTALL 1-CONDUCTOR #6
STRANDED COPPER, TYPE LF 2850.000 USE-2 832506 FURNISH AND 160.000 1010 INSTALL #1/0 AWG STRANDED COPPER 834005 POLE BASE, TYPE 17.000 1020 | 4A |834006 POLE BASE, TYPE 6 | 7.000 1030 EACH |834501 PARTIAL REMOVAL AND CABINET FOUNDATIONS CY 1040 OF CONCRETE POLE BASES |835003 CABINET BASE TYPE | 3.000 EACH 1050 P |835004 CABINET BASE TYPE | 1.000 1060 R EACH

DATE:

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

CONTRACTOR :__ LINE ITEM DESCRIPTION ITEM NO ______ 842501 FURNISH AND 1.000 1070 INSTALL ELECTRIC UTILITY EACH SERVICE EQUIPMENT 120/240 (100 AMP) 847002 INSTALL OR 1.000 1080 REMOVAL OF BASE OR PAD MOUNTED CABINET EACH 847004 LIGHTING CONTROL 1090 AND DISTRIBUTION 1.000 ENCLOSURE (120/240;100 EACH AMP) |850521 LUMINAIRE (LED), | 12.000 | EACH 1100 250 WATTS, HPS EQUIVALENT |851001 ALUMINUM LIGHTING 7.000 905001 SILT FENCE 3487.000 1120 905002 REINFORCED SILT 600.000 LF 1130 FENCE 905004 INLET SEDIMENT 27.000 1140 CONTROL, DRAINAGE INLET EACH |905005 INLET SEDIMENT 63.000 EACH 1150 CONTROL, CURB INLET 907017 COMPOST FILTER 3110.000 1160 LOGS

DELAWARE DEPARTMENT OF TRANSPORTATION PAGE: SCHEDULE OF ITEMS DATE:

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

CONTR	ACTOR :					
LINE NO	ITEM DESCRIPTION	APPROX. OUANTITY	UNIT PRICE		BID AMOUNT	
		AND UNITS	DOLLARS 0	CTS	DOLLARS	CTS
1170	908004 TOPSOIL, 6" DEPTH	10914.000 SY				
1180	908014 PERMANENT GRASS SEEDING, DRY GROUND	16020.000 SY				
1190	908015 PERMANENT GRASS SEEDING, STORMWATER	30370.000 SY				
1200	908017 TEMPORARY GRASS SEEDING	165040.000				
1210	908020 EROSION CONTROL BLANKET MULCH	23210.000 SY				
1220	908022 TURF REINFORCEMENT MATTING, TYPE 2	60.000 SY				
1230	908023 STABILIZED CONSTRUCTION ENTRANCE	556.000 SY				
1240	910001 INFILTRATION STONE, NO. 3	2526.000 CY				
1250	910006 OUTLET STRUCTURE	2.000 EACH				
	910008 STORMWATER MANAGEMENT POND	1655.000 CY				

DELAWARE DEPARTMENT OF TRANSPORTATION SCHEDULE OF ITEMS

PAGE: DATE:

14

CONTRACT ID: T200411209.01

PROJECT(S): ESTP-S024(8)

All figures must be typewritten.

LINE	LINE ITEM NO DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
NO			DOLLARS	CTS	DOLLARS	CTS
1 -	.0009 INFILTRATION ENCH	3196.000 CY				
s	ECTION 0001 TOTAL					
т	'OTAL BID					

JJID, Inc.

Jim Julian 100 Julian Lane Bear, DE 19701 P: 302-836-0414

F: 302-836-4275

Kent Construction Co.

Rick Davison 2 Big Oak Road Smyrna, DE 19977 P: 302-653-6469 F: 302-653-2108

Melvin L. Joseph Construction Co, Inc.

Chuck Ewing 25136 DuPont Boulevard Georgetown, DE 19947 P: 302-856-7396

Pearce & Moretto Inc.

Bill Smagala 314 Baywest Boulevard, Suite C PO Box 272 New Castle, DE 19720 P: 302-326-0707

Teal Construction

Chad Reed PO Box 779 Dover, DE 19901 P: 302-678-9500

Allan Myers, MD, Inc.

Bill Beaudet PO Box 478 Fallston, MD 21047

Requests to pre-qualify other firms may be submitted. Such requests shall be submitted to dot-ask@state.de.us DelDOT Contract Administration (attn. Mr. Scott Gottfried) a minimum of 10 calendar days in advance of the contract bid date. The requests should include the following information:

- Contractor name and contact information
- Name and resume of the project superintendent that will be assigned to this project
- List and detailed description of work on similar projects performed in the past 5 years with points of contact for the owners of the projects.
- Any other information deemed relevant to demonstrate that the Contractor has the experience and capabilities to successfully complete the work
- Additional information that may be requested

Approval or denial of the request shall lie solely with Tidewater Utilities, Inc. The approved Superintendent must be on-site during performance of the work. If a firm other than those listed above is being proposed, DelDOT Contract Administration must respond by letter or email to the bidder indicating approval or disapproval prior to award. The Contract cannot be awarded until an approved contractor for the water main item has been established.