

#### **DELMARVA POWER (GAS)**

Delmarva Power -- gas maintains underground facilities within the limits of the project with no anticipated impacts.

Any other relocations/adjustments to any existing gas lines shall be arranged, if necessary, with the owners during the construction of the project. The time to complete any adjustments will depend on the nature of the work.

#### **General**

No existing gas facilities can be taken out of service until the replacement facilities are installed and in operation.

#### **VERIZON DELAWARE INC.**

Verizon owns and maintains aerial facilities within the limits of the project requiring the following actions. Verizon will temporarily relocate our facilities to allow clearance for the State's contractor to work under the SR 141 bridge at Ayre Street. The following work, as discussed on site June 2<sup>nd</sup>, will be performed: Ayre Street, a temporary new pole will be placed on west side of the bridge on Ayre Street to provide clearance over Newport Builders parking lot and allow clearance under the bridge. The cables will be disconnected from the old pole under the bridge and let sag down. The State or State's contractor is responsible to provide barriers under the bridge to deny access under our cables until they are reattached to the existing pole at the completion of construction. Also, the State's contractor is to work around the pole under the bridge and not damage or cut off the pole. At the completion of the bridge construction, Verizon will reattach our facilities to the existing pole under the bridge and remove the temporary pole.

Verizon will require Approved Final Plans, Notice to Proceed, Estimate approval and a signed Letter Agreement before work can begin.

Any additional relocations/adjustments to any existing aerial/underground lines or poles shall be arranged, if necessary, with the owners during the construction of the project. The time to complete any additional relocations/adjustments will depend on the nature of the work.

#### **COMCAST CABLE OF NEW CASTLE COUNTY**

Comcast Cable of New Castle County maintains aerial facilities within the limits of the project requiring a temporary relocation of their cable to the new, temporary pole placed by Verizon on the west side of Ayre Street.

Any additional relocations/adjustments to any existing facilities shall be arranged, if necessary, with the owners during the construction of the project. The time to complete any additional relocations/adjustments will depend on the nature of the work.

### **FIBERTECH**

Fibertech maintains aerial facilities within the limits of the project requiring a temporary relocation of their cable to the new, temporary pole placed by Verizon on the west side of Ayre Street.

Any additional relocations/adjustments to any existing facilities shall be arranged, if necessary, with the owners during the construction of the project. The time to complete any additional relocations/adjustments will depend on the nature of the work.

### **UNITED WATER**

United Water maintains facilities within the limits of the project with no anticipated impacts.

Any relocations/adjustments to any existing water lines shall be arranged, if necessary, with the owners during the construction of the project. The time to complete any relocations/adjustments will depend on the nature of the work.

### **General**

No existing water facilities can be taken out of service until the replacement facilities are installed and in operation.

### **NEW CASTLE COUNTY DEPT. OF SPECIAL SERVICES**

New Castle County Department of Special Services maintains underground facilities within the limits of the project with no anticipated impacts.

Any relocations/adjustments to any existing underground facilities shall be arranged, if necessary, with the owners and performed by the state's contractor during the construction of the project. The time to complete any relocations/adjustments will depend on the nature of the work.

### **AT&T**

The company maintains underground facilities within the limits of the project at the following locations: Parallel with the Amtrak Lines approximately 5.5' from the face of the pier.

The AT&T fiber cable is buried underground paralleling the Amtrak Line through this area. The exact locations will need to be marked in the field when the technician responds to the ticket from Miss Utility Dig Center of Delaware. Depending on the extent of the proposed construction, the AT&T cables may or may not be impacted. Any adjustments of relocations will be coordinated between AT&T and the States' contractor. The time to complete any relocations/adjustments will depend on the nature of the work.

### General Notes

1. The Contractor's attention is directed to Section 105.09 Utilities, Delaware Standard Specifications, August 2001. The Contractor shall contact Miss Utility (1-800-282-8555) two working days prior to any excavation. The Contractor is responsible for the support and protection of all utilities when excavating. The Contractor is responsible for ensuring proper clearances, including safety clearances, from overhead utilities for construction equipment. The Contractor is advised to check the site for access purposes for his equipment and, if necessary, make arrangements directly with the utility companies for field adjustments for adequate clearances.
2. It is understood and agreed that the Contractor has considered in his bid all permanent and temporary utility appurtenances in their present and relocated positions as shown on the plans or described in the Utility Statement or are readily discernible and that no additional compensation will be allowed for any delays, inconvenience, or damage due to any interference from the utility facilities and appurtenances or the operation of moving them, except that the Contractor may be granted an equitable extension of time.
3. Coordination and cooperation among the Utility Companies and the State's Contractor are of prime importance. Therefore, the Contractor is directed to contact the following Utility Company representatives with any questions regarding this work prior to submitting bids and work schedules. Proposed work schedules should reflect the Utility Companies' proposed relocations. The Utility Companies do not work on weekends or legal holidays.

Angel Collazo	Delmarva Power – Electric Distribution	(302) 454-4370
Mark Smith	Delmarva Power – Electric Distribution	(302) 454-4138
Ted Waugh	Delmarva Power – Gas	(302) 429-3706
George Zang	Verizon Delaware, Inc.	(302) 422-1238
Wayne Keller	Verizon Delaware, Inc.	(302)-424-4350
Knol Merae	Comcast Cablevision, Inc.	(302) 661-4431
Lou Lucarelli	Fibertech	(856) 981-6072
John Licht	United Water	(302) 633-5905 ext. 306
Kevin Penozza	New Castle County Dept. of Sp. Srves.	(302) 395-5723
Louis Marello	AT&T	(973) 927-1114

### DIVISION OF TRANSPORTATION SOLUTIONS

1-25-2011  
DATE

  
UTILITY COORDINATOR

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 1  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE 1-501						
0010	201000 CLEARING AND GRUBBING	LUMP	LUMP			
0020	202000 EXCAVATION AND EMBANKMENT	9949.000 CY				
0030	202536 SITE SAFETY PLAN	LUMP	LUMP			
0040	207000 EXCAVATION AND BACKFILL FOR STRUCTURES	407.000 CY				
0050	207501 SHEETING AND SHORING	LUMP	LUMP			
0060	209003 BORROW, TYPE C	855.000 CY				
0070	209008 BORROW, TYPE A	80.000 TON				
0075	209013 BORROW, TYPE F	360.000 TON				
0080	211000 REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	LUMP			



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 2  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0090	211002 REMOVAL OF STRUCTURES AND OBSTRUCTIONS (GUARDRAIL)	2140.000 LF				
0100	251000 SILT FENCE	95.000 LF				
0110	252002 INLET SEDIMENT CONTROL, AT GRADE INLET	8.000 EACH				
0120	254000 STONE CHECK DAM	3.000 TON				
0130	268000 STABILIZED CONSTRUCTION ENTRANCE	113.000 TON				
0140	269000 TURBIDITY CURTAIN, FLOATING	720.000 LF				
0150	302005 GRADED AGGREGATE BASE COURSE, TYPE B	5115.000 TON				
0160	401654 SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 70-22	2075.000 TON				
0170	401663 SUPERPAVE, BITUMINOUS CONCRETE BASECOURSE, 160 GYRATIONS, PG 64-22	4680.000 TON				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 3  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0180	401708 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)	TON 1545.000				
0190	501012 PORTLAND CEMENT CONCRETE PAVEMENT, 14"	SY 195.000				
0200	601502 TEMPORARY PROTECTIVE SHIELD	LUMP	LUMP			
0210	602518 WATER BASED ACRYLIC CONCRETE SEALER	SF 50840.000				
0220	602546 WATERPROOFING P.C. C. MASONRY	SF 28592.000				
0230	602574 DECK REPAIR, 1/4" TO 1" DEPTH	SF 15.000				
0240	602575 DECK REPAIR, 1" TO 3" DEPTH	SF 36.000				
0250	602576 DECK REPAIR, 3" TO < FULL DEPTH	SF 127.000				
0260	602577 DECK REPAIR, FULL DEPTH	SF 23.000				
0270	602579 DRILLING HOLES AND INSTALLING DOWELS	EACH 545.000				





DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 4  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0280	602580 PARTIAL REMOVAL OF P.C.C. MASONRY	CY 499.000				
0290	602586 REHABILITATION OF CONCRETE STRUCTURE	CF 245.000				
0300	602611 REPAIR OF CONCRETE STRUCTURES BY EPOXY INJECTION	LF 4478.000				
0310	602697 FURNISHING LOW PERMEABILITY CONCRETE	CY 1225.000				
0320	602698 CONSTRUCTING LOW PERMEABILITY CONCRETE OVERLAY	SY 22038.000				
0330	602709 REPAIRING EXISTING PCC STRUCTURES	CF 401.000				
0340	602783 REPAIRING EXISTING PCC STRUCTURES, IN SPLASH ZONE OR UNDERWATER	CF 489.000				
0350	602784 REHABILITATION OF CONCRETE STRUCTURE, IN SPLASH ZONE OR UNDERWATER	CF 571.000				
0360	605512 PREFABRICATED EXPANSION JOINT SYSTEM, 4"	LF 827.000				
0370	605522 URETHANE PAINT SYSTEM, EXISTING STEEL	LUMP	LUMP			



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 5  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0380	605584 STEEL STRUCTURE REPAIR	45650.000 LB				
0390	605585 STEEL STRUCTURE REPAIR	LUMP	LUMP			
0400	605589 EXPANSION JOINT	LUMP	LUMP			
0410	605601 REPLACING BRIDGE BEARING	192.000 EACH				
0420	605618 CLEANING EXISTING STEEL STRUCTURE BY VACUUM POWER TOOLS (HAZARDOUS), S.F.	6120.000 SF				
0430	605629 CLEANING EXISTING STEEL STRUCTURES, HAZARDOUS (S.F.)	208300.000 SF				
0440	605651 REPLACING BRIDGE BEARING, SPECIAL	12.000 EACH				
0450	605656 CLEANING BRIDGE DRAINS	LUMP	LUMP			
0460	605689 ANCHOR BOLT REPAIR	80.000 EACH				
0470	605724 INSTALL STRUCTURE MOUNTED SIGNS	LUMP	LUMP			



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE:  
DATE:

6

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0480	614202 CORRUGATED ALUMINUM PIPE, 18", 14 GAGE, 2 2/3" X 1/2" CORRUGATION	LF 54.000				
0490	701010 PORTLAND CEMENT CONCRETE CURB, TYPE 1	LF 415.000				
0500	701012 PORTLAND CEMENT CONCRETE CURB, TYPE 3	LF 1245.000				
0510	705001 P.C.C. SIDEWALK, 4"	SF 615.000				
0520	710502 ADJUSTING CATCH BASINS	EACH 4.000				
0530	713002 GEOTEXTILES, SEPARATION	SY 300.000				
0540	715001 PERFORATED PIPE UNDERDRAINS, 6"	LF 4820.000				
0550	720005 STEEL RAIL ELEMENT, STRAIGHT	LF 100.000				
0560	720033 GALVANIZED W-BEAM OFFSET BLOCK	EACH 24.000				
0570	720050 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1	LF 500.000				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 7  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0580	720052 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 3	1575.000 LF				
0590	720506 RELOCATING PORTABLE P.C.C. SAFETY BARRIER	15587.000 LF				
0600	720526 PORTABLE P.C.C. STRUCTURE-MOUNTED SAFETY BARRIER	1116.000 LF				
0610	720531 GLARE SCREEN	4656.000 LF				
0620	720532 INSTALL PORTABLE IMPACT ATTENUATOR	12.000 EACH				
0630	720534 FURNISH PORTABLE IMPACT ATTENUATOR	7.000 EACH				
0640	720539 RELOCATE PORTABLE IMPACT ATTENUATOR	10.000 EACH				
0650	720552 REFLECTOR PANELS	80.000 EACH				
0660	720554 IMPACT ATTENUATOR, TYPE III	1.000 EACH				
0670	720567 FURNISH AND MAINTAIN PORTABLE P.C.C. SAFETY BARRIER	8676.000 LF				





DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 8  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0680	720620 FURNISH AND MAINTAIN PORTABLE P.C.C. PINNED SAFETY BARRIER, SINGLE FACED	250.000 LF				
0690	720621 RELOCATING PINNED PORTABLE P.C.C. SAFETY BARRIER	450.000 LF				
0700	720624 REMOVE AND REINSTALL W-BEAM FOR GUARDRAIL	8.000 EACH				
0710	720636 FURNISH AND MAINTAIN PORTABLE P.C.C. PINNED SAFETY BARRIER, DOUBLE FACE	250.000 LF				
0720	720660 INSTALL PORTABLE IMPACT ATTENUATOR, DOUBLE WIDE	4.000 EACH				
0730	720661 FURNISH PORTABLE IMPACT ATTENUATOR, DOUBLE WIDE	2.000 EACH				
0740	725001 GUARDRAIL TO BARRIER CONNECTION (EXIT TYPE)	2.000 EACH				
0750	725002 GUARDRAIL TO BARRIER CONNECTION, APPROACH TYPE 1	2.000 EACH				
0760	727004 CHAIN-LINK FENCE, 6' HIGH	1330.000 LF				
0770	727006 TERMINAL POSTS FOR 6' CHAIN-LINK FENCE	18.000 EACH				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 9  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0780	727014 CONSTRUCTION SAFETY FENCE	2090.000 LF				
0790	727547 REMOVAL OF FENCE	1330.000 LF				
0800	733001 TOPSOILING, 4" DEPTH	3730.000 SY				
0810	734013 PERMANENT GRASS SEEDING, DRY GROUND	3610.000 SY				
0820	734017 TEMPORARY GRASS SEEDING, DRY GROUND	3460.000 SY				
0830	734018 TEMPORARY GRASS SEEDING, WET GROUND	110.000 SY				
0840	734521 WETLAND MITIGATION SEED MIX	300.000 SY				
0850	743003 ARROWPANELS, TYPE C	280.000 EADY				
0860	743004 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	2022.000 EADY				
0870	743005 FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	200.000 EADY				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 10  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0880	743006 PLASTIC DRUMS	111670.000 EADY				
0890	743007 TRAFFIC OFFICERS	1500.000 HOUR	75.000000		112500.00	
0900	743050 FLAGGER, NEW CASTLE COUNTY, STATE	160.000 HOUR	41.670000		6667.20	
0910	743062 FLAGGER, NEW CASTLE COUNTY, STATE, OVERTIME	20.000 HOUR	60.420000		1208.40	
0920	743501 WARNING LIGHTS , TYPE B	60.000 EADY				
0930	743504 WARNING SIGNS	393.000 EACH				
0940	743507 TEMPORARY BARRICADE, TYPE III	12080.000 LFDY				
0950	743525 TEMPORARY WARNING SIGNS	4280.000 EADY				
0960	743537 FURNISH AND MAINTAIN TRUCK-MOUNTED ATTENUATOR, TYPE II	140.000 EADY				
0970	744505 ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	2.000 EACH				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 11  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0980	745523 SUPPLY OF 4" SCHEDULE 40 PVC CONDUIT	45.000 LF				
0990	745544 INSTALLATION OF CONDUIT IN UNPAVED TRENCH	15.000 LF				
1000	745546 INSTALLATION OF CONDUIT ON STRUCTURE	30.000 LF				
1010	746536 TEMPORARY LIGHTING	1.000 EACH				
1020	746596 JUNCTION BOX ON STRUCTURE	1.000 EACH				
1030	748015 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	60.000 SF				
1040	748020 TEMPORARY MARKINGS, PAINT, 6"	95762.000 LF				
1050	748026 TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	64.000 SF				
1060	748507 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, 6"	28500.000 LF				
1070	748509 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, 12"	6650.000 LF				





DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 12  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1080	748526 TEMPORARY MARKINGS, TAPE, 6"	34836.000 LF				
1090	748527 TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	64.000 SF				
1100	748530 REMOVAL OF PAVEMENT STRIPING	75049.000 SF				
1110	748538 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 10"	6450.000 LF				
1120	748540 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 16"	2405.000 LF				
1130	749500 SIGN PANEL	140.000 SF				
1140	749502 SIGN PANEL OVERLAY ON EXISTING SIGN	320.000 SF				
1150	758000 REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	115.000 SY				
1160	759501 FIELD OFFICE, SPECIAL	31.000 EAMO				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 13  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1170	760003 PAVEMENT - MILLING, HOT-MIX, VARIABLE DEPTH	1200.000 SY				
1180	760504 RUMBLE STRIPS, HOT MIX	13052.000 LF				
1190	760506 RUMBLE STRIPS, CONCRETE	8744.000 LF				
1200	760508 PROFILE MILLING, CONCRETE	44076.000 SYIN				
1210	762001 SAW CUTTING, HOT MIX	12300.000 LF				
1220	762002 SAW CUTTING, CONCRETE, FULL DEPTH	115.000 LF				
1230	763000 INITIAL EXPENSE	LUMP	LUMP			
1240	763500 MAINTENANCE OF TRAFFIC	LUMP	LUMP			
1250	763501 CONSTRUCTION ENGINEERING	LUMP	LUMP			
1260	763502 MAINTENANCE OF RAILROAD TRAFFIC	LUMP	LUMP			



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 14  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1270	763508 PROJECT CONTROL SYSTEM DEVELOPMENT PLAN	LUMP	LUMP			
1280	763509 CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	EAMO 31.000				
1290	763522 COAST GUARD SPECIFIC CONDITIONS	LUMP	LUMP			
1300	763652 CLASS 1 TOW TRUCK	HOUR 3373.000				
1310	763653 CLASS 2 TOW TRUCK	EACH 62.000				
	SECTION 0001 TOTAL					

SECTION 0002 FIXED QUANTITY

1320	602013 PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D	CY 192.000				
1330	602014 PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	CY 329.000				
1340	602015 PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	CY 83.000				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 15  
DATE:

CONTRACT ID: T200907403.01 PROJECT(S): EBHOS-N 271(2)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1350	602017 PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A	235.000 CY				
1360	603000 BAR REINFORCEMENT	59646.000 LB				
1370	604000 BAR REINFORCEMENT, EPOXY COATED	77918.000 LB				
	SECTION 0002 TOTAL					
	TOTAL BID					





**Diesel Fuel Cost Price Adjustment Option**

The Bidder is required to submit this form with his/her Bid Proposal at the time of bid opening. When this form is not provided by the Bidder at the time of Bid, the Option-OUT will be automatically selected and no further option is available to the Contractor and no Diesel Fuel Cost Adjustments will be made.

**OPTION-IN**

☐ Checking here selects the option to participate in the 763626 - Diesel Fuel Cost Price Adjustment.

**OPTION-OUT**

☐ Checking here declines the option to participate in the 763626 - Diesel Fuel Cost Price Adjustment.

The undersigned hereby certifies that he/she is authorized to make this Option on behalf of the bidder in compliance with the special provision 763626 - Diesel Fuel Cost Price Adjustment.

Sealed and dated this \_\_\_\_\_ day of \_\_\_\_\_ in the year of our Lord two thousand and \_\_\_\_\_ ( 20\_\_ ).

\_\_\_\_\_  
Name of Bidder (Organization)

Corporate  
Seal

By: \_\_\_\_\_

\_\_\_\_\_  
Authorized Signature

Attest \_\_\_\_\_

\_\_\_\_\_  
Title

SWORN TO AND SUBSCRIBED BEFORE ME this \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Notary  
Seal

\_\_\_\_\_  
Notary

