

**THIS COPY IS FOR
INFORMATION ONLY.
YOU MUST PURCHASE
THE PROPOSAL IN ORDER
TO SUBMIT A BID.**



STATE OF DELAWARE
DEPARTMENT OF TRANSPORTATION
PO BOX 778
DOVER, DELAWARE 19903

JACK MARKELL
GOVERNOR

CAROLANN WICKS
SECRETARY

VIA OVERNIGHT DELIVERY

(302) 760-2030
FAX (302) 739-2254

March 17, 2011

Contract No. T201006305.02
Federal Aid Project No. ERRA-2010(25)
PAVEMENT & REHABILITATION, SOUTH II-V, 2010
Sussex County

Ladies and Gentlemen:

Enclosed is Addendum No. 2 for the referenced contract consisting of the following:

1. Quantities for the following items have been revised, 743003, 743007, 743058, 743067, and 743537.
2. The following Special Provisions are DELETED to be removed from the Proposal:
 - 720506
 - 720532
 - 720534
 - 720539
 - 720567
 - 743507
3. Seven (7) pages, Bid Proposal Forms, pages 1 through 7, revised, to be substituted for the same pages in the Proposal and one (1) page Bid Proposal Forms, page 8, DELETED, to be removed from the Proposal.
4. Six (6) sheets, Construction Plans, sheets 24, 25, 26, 27, 29, and 30, revised, to be substituted for the same sheets in the Plan Set.
5. For proposal holders with the electronic bid option only, Amendment Disk No. 1.

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott S. Gottfried". The signature is written in a cursive style with a horizontal line crossing through the middle of the letters.

Scott S. Gottfried
Competitively Bid Contracts Coordinator
:ssg
Enclosures

CONTRACT ID: T201006305.02 PROJECT(S): ERR-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Category 0001

0010	208000 EXCAVATION AND BACKFILLING FOR PIPE TRENCHES	64.000 CY				
0020	210000 FURNISHING BORROW TYPE "C" FOR PIPE, UTILITY TRENCH, AND STRUCTURE BACKFILL	4.000 CY				
0030	302005 GRADED AGGREGATE BASE COURSE, TYPE B	20.000 TON				
0040	302008 GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	37.000 CY				
0050	401645 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)	3143.000 TON				
0060	401665 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING	3.000 TON				
0070	401667 SUPERPAVE, BITUMINOUS CONCRETE BASECOURSE, 160 GYRATIONS, PG 64-22 PATCHING	283.000 TON				
0080	401696 ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE	320.000 TON				

CANNOT BE
USED FOR
BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 2
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERR-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0090	401827 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (NON-CARBONATE STONE)	5409.000 TON				
0100	402000 HOT-MIX BITUMINOUS CONCRETE AND/OR COLD-LAID BITUMINOUS CONCRETE (TRM)	40.000 TON				
0110	406001 HOT-MIX PATCHING	3200.000 SYIN				
0120	602002 PORTLAND CEMENT CONCRETE MASONRY, CLASS B	1.000 CY				
0130	612021 REINFORCED CONCRETE PIPE, 15", CLASS IV	178.000 LF				
0140	612022 REINFORCED CONCRETE PIPE, 18", CLASS IV	25.000 LF				
0150	612025 REINFORCED CONCRETE PIPE, 30", CLASS IV	57.000 LF				
0160	612525 CORRUGATED POLYETHYLENE PIPE, TYPE S, 30"	34.000 LF				
0170	612529 PIPE VIDEO INSPECTION	304.000 LF				
0180	701011 PORTLAND CEMENT CONCRETE CURB, TYPE 2	110.000 LF				

CANNOT BE USED FOR BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 3
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERRRA-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0190	705002 P.C.C. SIDEWALK, 6"	100.000 SF				
0200	705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	370.000 SF				
0210	705008 CURB RAMP, TYPE 1	450.000 SF				
0220	705009 CURB RAMP, TYPE 2, 3, AND/OR 4	1520.000 SF				
0230	705010 CURB RAMP, TYPE 5	98.000 SF				
0240	708050 DRAINAGE INLET, 34" X 18"	5.000 EACH				
0250	708052 DRAINAGE INLET, 48" X 30"	1.000 EACH				
0260	708112 MANHOLE, 48" X 48"	3.000 EACH				
0270	708500 REPLACING CATCH BASIN GRATES	37.000 EACH				
0280	708504 REPLACING CATCH BASIN FRAMES	37.000 EACH				

CANNOT BE USED FOR BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 4
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERRRA-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0290	710001 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	41.000 EACH				
0300	710002 ADJUSTING AND REPAIRING EXISTING MANHOLE	47.000 EACH				
0360	732004 TOPSOIL (TON)	40.000 TON				
0370	734013 PERMANENT GRASS SEEDING, DRY GROUND	500.000 SY				
0380	735534 SOIL RETENTION BLANKET MULCH, TYPE 4	500.000 SY				
0390	743001 ARROWPANELS, TYPE A	14.000 EADY				
0400	743003 ARROWPANELS, TYPE C	50.000 EADY				
0410	743004 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	14.000 EADY				
0420	743005 FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	22.000 EADY				
0430	743007 TRAFFIC OFFICERS	570.000 HOUR	75.00000		42750.00	

CANNOT BE USED FOR BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 5
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERR-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	743058 FLAGGER, SUSSEX COUNTY, FEDERAL	2280.000 HOUR	41.53000		94688.40	
0450	743067 FLAGGER, SUSSEX COUNTY, FEDERAL, OVERTIME	342.000 HOUR	60.22000		20595.24	
0470	743537 FURNISH AND MAINTAIN TRUCK-MOUNTED ATTENUATOR, TYPE II	50.000 EADY				
0480	744505 ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	8.000 EACH				
0490	744520 CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE	9.000 EACH				
0500	744523 CONDUIT JUNCTION WELL, TYPE 4, 20" X 42 1/2" PRECAST CONCRETE	1.000 EACH				
0510	744525 REMOVAL OF EXISTING JUNCTION WELL	2.000 EACH				
0520	745527 SUPPLY OF 2 1/2" GALVANIZED STEEL CONDUIT	320.000 LF				
0530	745529 SUPPLY OF 1 1/2" GALVANIZED STEEL CONDUIT	10.000 LF				
0540	745542 INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-DIRECTIONAL BORE	120.000 LF				

CANNOT BE USED FOR BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 6
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERRR-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	745543 INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-OPEN CUT	210.000 LF				
0560	746774 SUPPLY AND INSTALLATION OF LOOP DETECTOR WIRE	7500.000 LF				
0570	746830 REMOVAL OF CONCRETE POLE BASES AND CABINET FOUNDATIONS	1.000 CY				
0580	746850 POLE BASE, TYPE 4	12.000 EACH				
0590	748015 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	3556.000 SF				
0600	748019 TEMPORARY MARKINGS, PAINT, 4"	69360.000 LF				
0610	748026 TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	9453.000 SF				
0620	748502 RAISED/RECESSED PAVEMENT MARKER	156.000 EACH				
0630	748506 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, 4"	34650.000 LF				
0640	748553 PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL	65.000 EACH				

CANNOT BE USED FOR BIDDING

DELAWARE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 7
DATE:

CONTRACT ID: T201006305.02 PROJECT(S): ERRR-2010(25)

All figures must be typewritten.

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	750000 ADJUST WATER VALVE BOXES	21.000 EACH				
0660	758000 REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	35.000 SY				
0670	760507 PROFILE MILLING, HOT-MIX	144889.000 SYN				
0680	762001 SAW CUTTING, HOT MIX	2990.000 LF				
0690	762002 SAW CUTTING, CONCRETE, FULL DEPTH	50.000 LF				
0700	763000 INITIAL EXPENSE	LUMP			LUMP	
0710	763501 CONSTRUCTION ENGINEERING	LUMP			LUMP	
0720	763621 CONSTRUCTION ENGINEERING, RE-SURFACING	LUMP			LUMP	
0730	763643 MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LUMP			LUMP	
	SECTION 0001 TOTAL					
	TOTAL BID					

CANNOT BE
USED FOR
BIDDING

CONTRACT T201006305

PAGE 25 OF 30

SOUTH
MAINTENANCE

PAVEMENT & REHABILITATION, SOUTH II-V, 2010

LOCATION 2 SR1, COASTAL HIGHWAY (S50) - (FENWICK)

LENGTH AADT 11377

GENERAL IMPROVEMENTS

DRAINAGE AND CROSSPIPE REPLACEMENT/REPAIRS.

COMMENTS:

Please see attached sheets for comments

MATERIAL ESTIMATE FOR LOCATION 2

743507	△	TEMPORARY BARRICADE, TYPE III	22.00 LFDY
743058	**	FLAGGER, SUSSEX COUNTY, FEDERAL	△ 480.00 HOUR
743067	**	FLAGGER, SUSSEX COUNTY, FEDERAL, OVERTIME	△ 72.00 HOUR
743537	△	FURNISH AND MAINTAIN TRUCK-MOUNTED ATTENUATOR, TYPE II	5.00 EA-DY
748019		TEMPORARY MARKINGS, PAINT, 4"	60.00 L.F.
758000		REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	35.00 S.Y.
762001		SAW CUTTING, HOT MIX	650.00 L.F.
762002		SAW CUTTING, CONCRETE, FULL DEPTH	50.00 L.F.
763501		CONSTRUCTION ENGINEERING	1.00 L.S.

** DENOTES FIXED PRICE ITEM

ADDENDUM No. 2 - Deleted & Added Items and Revised Qty's - (03/16/11-PGF)

SOUTH
MAINTENANCE

PAVEMENT & REHABILITATION, SOUTH II-V, 2010

LOCATION 2 SRI, COASTAL HIGHWAY (S50) - (FENWICK)

COMMENTS:

1. RECOMMENDED M.O.T. CASE NO. 7 (TRAVEL LANES) ²
CASE NO. 16 (SIDEWALK).

2. 24 HOUR WORK SCHEDULE ²

A. THE DRAINAGE WORK SHALL BE A 24 HOUR CONTINUOUS OPERATION UNTIL ALL WORK IS COMPLETED WITH THE EXCEPTION OF THE OUTFALL PIPE INTO THE CANAL (UNLESS TIME PERMITS) LOCATED BETWEEN DAGSBORO AND ESSEX STREETS WHICH MAY BE COMPLETED DURING REGULAR HOURS. HOWEVER, ANY WORK HOURS SCHEDULED FOR THE OUTFALL PIPE SHALL BE BASED AROUND THE EXISTING BUSINESSES HOURS OF OPERATION.

B. THE FOLLOWING WORK SCHEDULE IS PERMITTED AS FOLLOWS;
START - SUNDAY NIGHT @ 7:00P.
END - FRIDAY AFTERNOON @ 12:00P.

C. TRAFFIC LANES MUST BE MAINTAINED AT 11 FT WIDTH OR AS DIRECTED BY THE ENGINEER.

D. BIKE LANES MUST BE MAINTAINED AT ALL TIMES (SHARE THE ROAD SIGNS SHALL BE PERMITTED IN APPLICABLE CASES) AS DIRECTED BY THE ENGINEER.

E. ALL LANES FOR TRAFFIC AND PEDESTRIAN ACTIVITY SHALL BE COMPLETELY OPEN ON THE LAST DAY BY 12:00P.

3. ON THE MAIN CONSTRUCTION ROAD AND ALL INTERSECTING ROADS, "ROAD WORK AHEAD AND END" SIGNS FACING THE TRAFFIC SHALL BE PLACED AT 1500', 1000' AND 500' APPROACHING THE WORK ZONE. IN THOSE CASES, WHERE IT IS DIFFICULT TO MEET THE ABOVE CRITERIA BECAUSE OF DISTANCE LIMITATIONS, THE SIGN SHALL BE PLACED AS DIRECTED BY THE FIELD ENGINEER.

~~4. THE M.O.T. ITEMS 720527, 720532, 720534, 720539 AND 720567 ARE TO BE UTILIZED FOR THE DRAINAGE REPAIR LOCATIONS ONLY.~~ ²

THIS LOCATION SHALL BE COMPLETED FIRST AND IN ITS ENTIRETY PRIOR TO STARTING THE MILL AND OVERLAY OPERATIONS.

5. DRAINAGE REPAIR NOTES

A. OUTFALL PIPE LOCATED AT CANAL:
EXISTING 26' (30") CORRUGATED METAL PIPE TO BE REPLACED IN KIND WITH 30" CORRUGATED POLYETHYLENE PIPE. PIPE REPLACEMENT IS CONTINGENT UPON OBTAINING A APPROVED ENVIRONMENTAL PERMIT. THE COST FOR ANY PUMPING REQUIRED TO COMPLETE THIS PROJECT SHALL BE INCIDENTAL TO ITEM 612525 - CORRUGATED POLYETHYLENE PIPE, 30".

B. NO SURVEY DATA WILL BE PROVIDED. ALL SURVEY WORK REQUIRED TO COMPLETE THE DRAINAGE SYSTEM REPAIRS IS INCIDENTAL TO ITEM 763501 - CONSTRUCTION ENGINEERING. THIS INCLUDES ALL PIPE, MANHOLE, DRAINAGE INLET INVERTS, ETC...AS WELL AS TOP OF GRATES AND ALL OTHER MISCELLANEOUS WORK TO FULLY COMPLETE THE PROJECT.

C. THE CONTRACTOR SHALL MATCH THE EXISTING INVERTS FOR ALL PIPE, MANHOLE AND DRAINAGE INLET REPLACEMENTS. ANY ADJUSTMENTS REQUIRED SHALL BE BY THE APPROVAL OF THE FIELD ENGINEER.

ADDENDUM No. 2 - Deleted, Added and Revised Notes - (03/16/11-PGF)

SOUTH
MAINTENANCE

PAVEMENT & REHABILITATION, SOUTH II-V, 2010

LOCATION 2 SR1, COASTAL HIGHWAY (S50) - (FENWICK)

D. A NUMBER OF EXISTING TRAFFIC UTILITY CONDUITS HAVE BEEN IDENTIFIED WITHIN THE LIMITS OF THE DRAINAGE REPLACEMENT/REPAIRS. REFERENCE DETAIL SHEETS. CARE SHALL BE TAKEN WHEN EXCAVATING WITHIN THESE AREAS AND HAND TOOLING WILL BE REQUIRED TO EXCAVATE AROUND THE CONDUITS. ANY DAMAGE INCURRED BY THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR/REPLACE.

6. PIPE JOINT REPAIR

A. A CONCRETE COLLAR SHALL BE PLACED AFTER WRAPPING THE PIPE WITH A WELDED WIRE MESH AND APPROVED GEO-TEXTILE MATERIAL FASTENED SECURELY AROUND THE PIPE WITH EPOXY COATED TIE WIRE.

B. THE COLLAR (SEE DETAIL SHEET PAGE 19) SHALL CONSIST OF A 4x4 INCH WELDED WIRE MESH GEO-TEXTILE WRAP OFFSET FROM THE PIPE WALL WITH CEMENT BRICK AS REQUIRED AND A CONCRETE COLLAR. THE COLLAR SHALL SURROUND THE LENGTH OF THE PIPE FAILURE (TOP, BOTTOM AND SIDES). ALL MATERIALS NEEDED (WELDED WIRE MESH, GEO-TEXTILE, FORMS, MORTAR, NON-SHRINK GROUT, ETC...) INCLUDING LABOR AND EQUIPMENT TO FULLY COMPLETE THE REPAIR SHALL BE INCIDENTAL TO ITEMS 208000 AND 602002.

C. NO CONCRETE SHALL BE RELEASED OR PLACED UNTIL THE DEPTH AND THE CHARACTER OF THE FOUNDATION MATERIAL, THE ADEQUACY OF THE FORMS AND FALSE WORK, AND THE PLACING OF REINFORCEMENTS HAVE BEEN INSPECTED AND APPROVED BY THE FIELD ENGINEER.

ADDENDUM No. 2 – Deleted, Added and Revised Notes - (03/16/11-PGF)

COPY

DELAWARE DEPARTMENT OF TRANSPORTATION

CONTRACT: T201006305

PAGE 29 OF 30

SOUTH PAVEMENT & REHABILITATION, SOUTH II-V, 2010
MAINTENANCE

CONTRACT QUANTITIES SUMMARY SHEET

710001	ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	41.00 EACH
710002	ADJUSTING AND REPAIRING EXISTING MANHOLE	47.00 EACH
720506	2 RELOCATING PORTABLE P.C.C. SAFETY BARRIER	6,600.00 L.F.
720532	2 INSTALL PORTABLE IMPACT ATTENUATOR	22.00 EACH
720534	2 FURNISH PORTABLE IMPACT ATTENUATOR	41.00 EACH
720539	2 RELOCATE PORTABLE IMPACT ATTENUATOR	41.00 EACH
720567	2 FURNISH AND MAINTAIN PORTABLE P.C.C. SAFETY BARRIER	600.00 L.F.
732004	TOPSOIL (TON)	40.00 TON
734013	PERMANENT GRASS SEEDING, DRY GROUND	500.00 S.Y.
735534	SOIL RETENTION BLANKET MULCH, TYPE 4	500.00 S.Y.
743001	ARROWPANELS, TYPE A	14.00 EA-DY
743003	ARROWPANELS, TYPE C	2 50.00 EA-DY
743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	14.00 EA-DY
743005	FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	22.00 EA-DY
743007	** TRAFFIC OFFICERS	2 500.00 HOUR
743058	** FLAGGER, SUSSEX COUNTY, FEDERAL	2 2,280.00 HOUR
743067	** FLAGGER, SUSSEX COUNTY, FEDERAL, OVERTIME	2 342.00 HOUR
743507	2 TEMPORARY BARRICADE, TYPE III	22.00 LFDY
743537	FURNISH AND MAINTAIN TRUCK-MOUNTED ATTENUATOR, TYPE II	2 50.00 EA-DY
744505	ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	8.00 EACH
744520	CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE	9.00 EACH
744523	CONDUIT JUNCTION WELL, TYPE 4, 20" X 42 1/2" PRECAST CONCRETE	1.00 EACH
744525	REMOVAL OF EXISTING JUNCTION WELL	2.00 EACH
745527	SUPPLY OF 2 1/2" GALVANIZED STEEL CONDUIT	320.00 L.F.
745529	SUPPLY OF 1 1/2" GALVANIZED STEEL CONDUIT	10.00 L.F.
745542	INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-DIRECTIONAL BORE	120.00 L.F.
745543	INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-OPEN CUT	210.00 L.F.
746774	SUPPLY AND INSTALLATION OF LOOP DETECTOR WIRE	7,500.00 L.F.

ADDENDUM No. 2 - Deleted & Added Items and Revised Qty's - (03/16/11-PGF)

DELAWARE DEPARTMENT OF TRANSPORTATION

CONTRACT: T201006305

PAGE 30 OF 30

SOUTH
MAINTENANCE

PAVEMENT & REHABILITATION, SOUTH II-V, 2010

CONTRACT QUANTITIES SUMMARY SHEET

746830	REMOVAL OF CONCRETE POLE BASES AND CABINET FOUNDATIONS	1.00 C.Y.
746850	POLE BASE, TYPE 4	12.00 EACH
748015	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLASTIC	3,556.00 S.F.
748019	TEMPORARY MARKINGS, PAINT, 4"	69,360.00 L.F.
748026	TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	9,453.00 S.F.
748502	RAISED/RECESSED PAVEMENT MARKER	156.00 EACH
748506	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, 4"	34,650.00 L.F.
748553	PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL	65.00 EACH
750000	ADJUST WATER VALVE BOXES	21.00 EACH
758000	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	35.00 S.Y.
760507	PROFILE MILLING, HOT-MIX	144,889.00 SY-IN
762001	SAW CUTTING, HOT MIX	2,990.00 L.F.
762002	SAW CUTTING, CONCRETE, FULL DEPTH	50.00 L.F.
763000	INITIAL EXPENSE	LUMP SUM
763501	CONSTRUCTION ENGINEERING	1.00 L.S.
763621	CONSTRUCTION ENGINEERING, RE-SURFACING	1.00 L.S.
763643	MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LUMP SUM

** DENOTES FIXED PRICE ITEM

ADDENDUM No. 2 – Deleted & Added Items and Revised Qty's - (03/16/11-PGF)