



STATE OF DELAWARE  
DEPARTMENT OF TRANSPORTATION  
PO BOX 778  
DOVER, DELAWARE 19903

JACK MARKELL  
GOVERNOR

CAROLANN WICKS  
SECRETARY

**VIA OVERNIGHT DELIVERY**

(302) 760-2030  
FAX (302) 739-2254

June 16, 2011

Contract No. T201106202.01  
Federal Aid Project No. ESTP-K002(05)  
PAVEMENT & REHABILITATION, SOUTH I-II, 2010  
Kent County

Ladies and Gentlemen:

Enclosed is Addendum No. 1 for the referenced contract consisting of the following:

1. One (1) page, Table of Contents, page iv, revised, to be substituted for the same page in the Proposal.
2. One (1) page, Special Provisions 503503 - Patching Concrete, page 71, **DELETED**, to be removed from the Proposal.
3. Nine (9) pages, Bid Proposal Forms, pages 1 through 9, revised, to be substituted for the same pages in the Proposal.
4. Two (2) sheets, Construction Plans, sheets 38 and 46, revised, to be substituted for the same sheets in the Plan Set.
5. For proposal holders with the electronic bid option only, Amendment Disk No. 1.

#### Questions and Answers

1. Could you clarify the limits on location 1 (Court St/South Little Creek Rd)? The plans say the length is 950 feet, and the hot mix quantities are fairly close for the length, however, the description indicates the project is from Rt 13 to Rt 113, which is approximately 1 mile. In regards to calculating the required MOT signage, a more detailed description of the paving limits is required.

**The length and limits are correct. See location map or ADC road map**

2. In regards to the above contract, the documents mentions the City of Dover Water Main contract No. WQ09.07. There was extensive mill and overlay on Rte 13 as a part of that contract. Does this bid solicitation take that work into consideration? The Paving and milling limits for locations 5-6 are unclear in regards to this question.

**The general contractor for the City of Dover water main project is responsible for the milling and overlay of the Southbound lanes within the limits of contract WQ09.07. Water Main project limits are from North State St to White Oak Rd, Southbound lanes only. The Pave Rehab contractor will tie into the Water Main project limits.**

3. What is bid item 401645 used for at this location?  
What is bid item 760000 used for at this location?

**For the above questions 1 & 2 the two items are used for the business entrances impacted by the sidewalk construction.**

4. Other than pcc curb ty1, pcc curb ty 2 what are removing under item 758000 at this location?

**In addition to the PCC curb type 1 & 2, several PCC median islands located at the business entrances will be partially removed including an existing lawn basin and drainage pipe located at Windham Travel.**

5. At loc #3, deldot is showing one 34" x 24" inlet and 16 lf of 12" rcp being installed. Since the contractor does not get paid for pipe excavation (item 208000) or select borrow (item 210000) since this pipe is less than 24" in diameter and are to be considered incidental to bid item 612020 the contractor needs to know at what depth these items will be installed.

**The area to be impacted by this drainage is located on a slightly sloped embankment. Beginning at the drainage inlet the depth is 3' +/- progressing down to 1'+/- depth at the discharge end.**

6. At location #6 you have bid item 503503 which is normally used on contracts that have concrete patching shown. There is no concrete patching on this contract so what is bid item 503503 used for?


**This item will be deleted from the contract under addendum.**

7. At location #3 what is bid item 209006 used for?

**Borrow type F will be used as fill material to raise/level the existing grade to accommodate the new construct sidewalk located between the Windham Travel and Auto garage entrances.**

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott S. Gottfried". The signature is written in a cursive style with a large initial "S" and a distinct "G".

Scott S. Gottfried  
Competitively Bid Contracts Coordinator  
:ssg  
Enclosures

401667 - SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG-64-22, PATCHING .....	<a href="#"><u>47</u></a>
401711 - SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE) .....	<a href="#"><u>47</u></a>
401696 - ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE .....	<a href="#"><u>53</u></a>
401699 - QUALITY CONTROL/QUALITY ASSURANCE OF BITUMINOUS CONCRETE ...	<a href="#"><u>54</u></a>
401752 - SAFETY EDGE FOR ROADWAY PAVEMENT .....	<a href="#"><u>70</u></a>
705528 - TEMPORARY CURB RAMP .....	<a href="#"><u>72</u></a>
705529 - RELOCATING TEMPORARY CURB RAMP .....	<a href="#"><u>73</u></a>
708500 - REPLACING CATCH BASIN GRATES .....	<a href="#"><u>74</u></a>
708504 - REPLACING CATCH BASIN FRAMES .....	<a href="#"><u>74</u></a>
708583 - PERSONNEL GRATE FOR PIPE INLET .....	<a href="#"><u>75</u></a>
716502 - CONVERTING EXISTING CATCH BASIN TO DRAINAGE INLET .....	<a href="#"><u>76</u></a>
720573 - ADJUSTING GUARDRAIL HEIGHT .....	<a href="#"><u>78</u></a>
735534 - SOIL RETENTION BLANKET MULCH, TYPE 4 .....	<a href="#"><u>79</u></a>
743507 - TEMPORARY BARRICADES, TYPE III .....	<a href="#"><u>81</u></a>
743525 - TEMPORARY WARNING SIGNS .....	<a href="#"><u>81</u></a>
744520 - CONDUIT JUNCTION WELL, TYPE 1, 20" x 20" PRECAST CONCRETE .....	<a href="#"><u>84</u></a>
744523 - CONDUIT JUNCTION WELL, TYPE 4, 20" x 42 1/2" PRECAST CONCRETE .....	<a href="#"><u>84</u></a>
744505 - ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL .....	<a href="#"><u>86</u></a>
744525 - REMOVAL OF EXISTING JUNCTION WELL .....	<a href="#"><u>87</u></a>
745527 - SUPPLY OF 2 1/2" GALVANIZED STEEL CONDUIT .....	<a href="#"><u>88</u></a>
745529 - SUPPLY OF 1 1/2" GALVANIZED STEEL CONDUIT .....	<a href="#"><u>88</u></a>
745542 - INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT - DIRECTIONAL BORE .....	<a href="#"><u>90</u></a>
745543 - INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT - OPEN CUT .....	<a href="#"><u>90</u></a>
745544 - INSTALLATION OF CONDUIT IN UNPAVED TRENCH .....	<a href="#"><u>90</u></a>
746776 - LOOP DETECTOR SPLICE .....	<a href="#"><u>93</u></a>
746847 - POLE BASE TYPE 3 .....	<a href="#"><u>95</u></a>
746850 - POLE BASE TYPE 4 .....	<a href="#"><u>95</u></a>
748502 - RAISED/RECESSED PAVEMENT MARKER .....	<a href="#"><u>97</u></a>
748548 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5" .....	<a href="#"><u>98</u></a>
748520 - INSTALLING PAVEMENT MARKINGS, 4" .....	<a href="#"><u>107</u></a>
748527 - TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS .....	<a href="#"><u>110</u></a>
748553 - PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL .....	<a href="#"><u>113</u></a>
749688 - INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" IN DEPTH .....	<a href="#"><u>117</u></a>
760507 - PROFILE MILLING, HOT-MIX .....	<a href="#"><u>118</u></a>
763621 - CONSTRUCTION ENGINEERING, RE-SURFACING .....	<a href="#"><u>120</u></a>
763643 - MAINTENANCE OF TRAFFIC - ALL INCLUSIVE .....	<a href="#"><u>121</u></a>
763646 - MAINTENANCE OF TRAFFIC FOR PEDESTRIAN ACCESS .....	<a href="#"><u>126</u></a>
UTILITY STATEMENT .....	<a href="#"><u>129</u></a>
RIGHT OF WAY CERTIFICATE .....	<a href="#"><u>131</u></a>
ENVIRONMENTAL STATEMENT .....	<a href="#"><u>133</u></a>
<b>BID PROPOSAL FORMS .....</b>	<b><a href="#"><u>135</u></a></b>
<b>BREAKOUT SHEETS .....</b>	<b><a href="#"><u>155</u></a></b>

**THIS PAGE IS BLANK FOR SEQUENCING PURPOSES**

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 1  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Category 0001

0010	202000 EXCAVATION AND EMBANKMENT	175.000 CY				
0020	209006 BORROW, TYPE F	79.000 CY				
0030	252001 INLET SEDIMENT CONTROL, CURB INLET	6.000 EACH				
0040	252002 INLET SEDIMENT CONTROL, AT GRADE INLET	2.000 EACH				
0050	302005 GRADED AGGREGATE BASE COURSE, TYPE B	617.000 TON				
0060	302008 GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	484.000 CY				
0070	401645 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)	6677.000 TON				
0080	401665 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING	41.000 TON				
0090	401667 SUPERPAVE, BITUMINOUS CONCRETE BASECOURSE, 160 GYRATIONS, PG 64-22 PATCHING	1523.000 TON				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 2  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	401696 ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE	299.000 TON				
0110	401711 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)	22505.000 TON				
0120	402000 HOT-MIX BITUMINOUS CONCRETE AND/OR COLD-LAID BITUMINOUS CONCRETE (TRM)	285.000 TON				
0130	406001 HOT-MIX PATCHING	9246.000 SYIN				
0140	406002 HOT-MIX PATCHING, CONCRETE	41184.000 SYIN				
0160	612020 REINFORCED CONCRETE PIPE, 12", CLASS IV	16.000 LF				
0170	617001 REINFORCED CONCRETE FLARED END SECTION, 12"	1.000 EACH				
0180	701010 PORTLAND CEMENT CONCRETE CURB, TYPE 1	2823.000 LF				
0190	701011 PORTLAND CEMENT CONCRETE CURB, TYPE 2	3084.000 LF				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 3  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	701022 INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 3	57.000 LF				
0210	705001 P.C.C. SIDEWALK, 4"	7450.000 SF				
0220	705002 P.C.C. SIDEWALK, 6"	8865.000 SF				
0230	705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	2475.000 SF				
0240	705008 CURB RAMP, TYPE 1	5638.000 SF				
0250	705009 CURB RAMP, TYPE 2, 3, AND/OR 4	8286.000 SF				
0260	705010 CURB RAMP, TYPE 5	6828.000 SF				
0270	705528 TEMPORARY CURB RAMP	30.000 EACH				
0280	705529 RELOCATING TEMPORARY CURB RAMP	15.000 EACH				
0290	708051 DRAINAGE INLET, 34" X 24"	1.000 EACH				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 4  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	708500 REPLACING CATCH BASIN GRATES	21.000 EACH				
0310	708504 REPLACING CATCH BASIN FRAMES	21.000 EACH				
0320	708583 PERSONAL GRATE FOR PIPE INLET	1.000 EACH				
0330	710001 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	164.000 EACH				
0340	710002 ADJUSTING AND REPAIRING EXISTING MANHOLE	48.000 EACH				
0350	712005 RIPRAP, R-4	2.000 SY				
0360	713003 GEOTEXTILES, RIPRAP	2.000 SY				
0370	716502 CONVERTING EXISTING CATCH BASIN TO DRAINAGE INLET	19.000 EACH				
0380	720573 ADJUSTING GUARDRAIL HEIGHT	700.000 LF				
0390	732004 TOPSOIL (TON)	587.000 TON				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 5  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	734013 PERMANENT GRASS SEEDING, DRY GROUND	6222.000 SY				
0410	735534 SOIL RETENTION BLANKET MULCH, TYPE 4	6222.000 SY				
0420	738004 TRANSPLANTING - EVERGREEN & DECIDUOUS SHRUBS MORE THAN 4'	4.000 EACH				
0430	743003 ARROWPANELS, TYPE C	222.000 EADY				
0440	743004 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	126.000 EADY				
0450	743005 FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	1019.000 EADY				
0460	743006 PLASTIC DRUMS	4020.000 EADY				
0470	743007 TRAFFIC OFFICERS	2220.000 HOUR	75.00000		166500.00	
0480	743010 FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	217.000 EADY				
0490	743057 FLAGGER, KENT COUNTY, FEDERAL	20340.000 HOUR	41.81000		850415.40	

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 6  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	743066 FLAGGER, KENT COUNTY, FEDERAL, OVERTIME	3051.000 HOUR	60.62000		184951.62	
0510	743507 TEMPORARY BARRICADE, TYPE III	1677.000 LFDY				
0520	743525 TEMPORARY WARNING SIGNS	1229.000 EADY				
0530	744505 ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	11.000 EACH				
0540	744520 CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE	19.000 EACH				
0550	744523 CONDUIT JUNCTION WELL, TYPE 4, 20" X 42 1/2" PRECAST CONCRETE	17.000 EACH				
0560	744525 REMOVAL OF EXISTING JUNCTION WELL	25.000 EACH				
0570	745527 SUPPLY OF 2 1/2" GALVANIZED STEEL CONDUIT	2049.000 LF				
0580	745529 SUPPLY OF 1 1/2" GALVANIZED STEEL CONDUIT	1016.000 LF				
0590	745542 INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-DIRECTIONAL BORE	695.000 LF				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 7  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0600	745543 INSTALLATION OF CONDUIT UNDER EXISTING PAVEMENT-OPEN CUT	105.000 LF				
0610	745544 INSTALLATION OF CONDUIT IN UNPAVED TRENCH	2230.000 LF				
0620	746776 LOOP DETECTOR SPLICE	309.000 EACH				
0630	746847 POLE BASE, TYPE 3	2.000 EACH				
0640	746850 POLE BASE, TYPE 4	52.000 EACH				
0650	748015 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	22312.000 SF				
0660	748019 TEMPORARY MARKINGS, PAINT, 4"	321520.000 LF				
0670	748026 TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	36178.000 SF				
0680	748027 PERMANENT PAVEMENT STRIPING, ALKYD-THERMOPLASTIC, 12"	820.000 LF				
0690	748502 RAISED/RECESSED PAVEMENT MARKER	1202.000 EACH				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 8  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0700	748520 INSTALLING PAVEMENT MARKINGS, 4"	1920.000 LF				
0710	748527 TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	2896.000 SF				
0720	748548 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	160760.000 LF				
0730	748553 PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL	152.000 EACH				
0740	749688 INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH	4.000 EACH				
0750	750000 ADJUST WATER VALVE BOXES	57.000 EACH				
0760	758000 REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	2354.000 SY				
0770	760000 PAVEMENT - MILLING, HOT-MIX	1384.000 SYIN				
0780	760507 PROFILE MILLING, HOT-MIX	506201.000 SYIN				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 9  
DATE:

CONTRACT ID: T201106202.01 PROJECT(S): ESTP-K002(05)

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0790	762001 SAW CUTTING, HOT MIX	18702.000 LF				
0800	762002 SAW CUTTING, CONCRETE, FULL DEPTH	7169.000 LF				
0810	763000 INITIAL EXPENSE	LUMP	LUMP			
0820	763621 CONSTRUCTION ENGINEERING, RE-SURFACING	LUMP	LUMP			
0830	763643 MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LUMP	LUMP			
0840	763646 MAINTENANCE OF TRAFFIC FOR PEDESTRIAN ACCESS	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

DELAWARE DEPARTMENT OF TRANSPORTATION

CONTRACT T201106202

PAGE 38 OF 49

SOUTH  
MAINTENANCE

PAVEMENT & REHABILITATION, SOUTH I-II, 2010

**LOCATION 6** US13, NORTH DUPONT HWYN.B. & S.B.(K7) - (DOVER) FROM US13/113 MERGE  
SPLIT TO NORTH STATE ST(K3)

LENGTH 5806.44 m 19050 L.F. AADT 54169

**GENERAL IMPROVEMENTS**

2" MILLING, HM PATCHING-(CONCRETE) AND 2" HOT-MIX TYPE C OVERLAY.

**COMMENTS:**

Please see attached sheets for comments

**MATERIAL ESTIMATE FOR LOCATION 6**

302005	GRADED AGGREGATE BASE COURSE, TYPE B	2.00 TON
302008	GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	240.00 C.Y.
401645	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)	1,847.00 TON
401667	SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22 PATCHING	730.00 TON
401696	ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE	224.00 TON
401711	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)	9,384.00 TON
402000	HOT-MIX BITUMINOUS CONCRETE AND/OR COLD-LAID BITUMINOUS CONCRETE (TRM)	109.00 TON
406001	HOT-MIX PATCHING	133.00 SY-IN
406002	HOT-MIX PATCHING, CONCRETE	27,248.00 SY-IN
<del>503503</del>	<del>* PATCHING CONCRETE</del>	<del>14,214.00 SY-IN</del>
701011	PORTLAND CEMENT CONCRETE CURB, TYPE 2	20.00 L.F.
705002	P.C.C. SIDEWALK, 6"	60.00 S.F.
705007	SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	300.00 S.F.
705008	CURB RAMP, TYPE 1	1,350.00 S.F.
705009	CURB RAMP, TYPE 2, 3, AND/OR 4	2,090.00 S.F.
705010	CURB RAMP, TYPE 5	156.00 S.F.
708500	REPLACING CATCH BASIN GRATES	6.00 EACH
708504	REPLACING CATCH BASIN FRAMES	6.00 EACH
710001	ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	67.00 EACH
710002	ADJUSTING AND REPAIRING EXISTING MANHOLE	20.00 EACH
716502	CONVERTING EXISTING CATCH BASIN TO DRAINAGE INLET	6.00 EACH
732004	TOPSOIL (TON)	172.00 TON
734013	PERMANENT GRASS SEEDING, DRY GROUND	2,087.00 S.Y.
735534	SOIL RETENTION BLANKET MULCH, TYPE 4	2,087.00 S.Y.
743003	ARROWPANELS, TYPE C	90.00 EA-DY
743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	28.00 EA-DY
743005	FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	360.00 EA-DY

**ADDENDUM No. 1 - Deleted Item 503503 - (06/15/11-PGF)**


**DELAWARE DEPARTMENT OF TRANSPORTATION**

**CONTRACT: T201106202**

**PAGE 46 OF 49**

**SOUTH PAVEMENT & REHABILITATION, SOUTH I-II, 2010  
MAINTENANCE**

**CONTRACT QUANTITIES SUMMARY SHEET**

202000	EXCAVATION AND EMBANKMENT	175.00 C.Y.
209006	BORROW, TYPE F	79.00 C.Y.
252001	INLET SEDIMENT CONTROL, CURB INLET	6.00 EACH
252002	INLET SEDIMENT CONTROL, AT GRADE INLET	2.00 EACH
302005	GRADED AGGREGATE BASE COURSE, TYPE B	617.00 TON
302008	GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	484.00 C.Y.
401645	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)	6,677.00 TON
401665	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING	41.00 TON
401667	SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22 PATCHING	1,523.00 TON
401696	ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE	299.00 TON
401711	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)	22,505.00 TON
402000	HOT-MIX BITUMINOUS CONCRETE AND/OR COLD-LAID BITUMINOUS CONCRETE (TRM)	285.00 TON
406001	HOT-MIX PATCHING	9,246.00 SY-IN
406002	HOT-MIX PATCHING, CONCRETE	41,184.00 SY-IN
<del>503503</del>	<del>** PATCHING CONCRETE </del>	<del>14,214.00 SY-IN</del>
612020	REINFORCED CONCRETE PIPE, 12", CLASS IV	16.00 L.F.
617001	REINFORCED CONCRETE FLARED END SECTION, 12"	1.00 EACH
701010	PORTLAND CEMENT CONCRETE CURB, TYPE 1	2,823.00 L.F.
701011	PORTLAND CEMENT CONCRETE CURB, TYPE 2	3,084.00 L.F.
701022	INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 3	57.00 L.F.
705001	P.C.C. SIDEWALK, 4"	7,450.00 S.F.
705002	P.C.C. SIDEWALK, 6"	8,865.00 S.F.
705007	SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	2,475.00 S.F.
705008	CURB RAMP, TYPE 1	5,638.00 S.F.
705009	CURB RAMP, TYPE 2, 3, AND/OR 4	8,286.00 S.F.
705010	CURB RAMP, TYPE 5	6,828.00 S.F.
705528	TEMPORARY CURB RAMP	30.00 EACH
705529	RELOCATING TEMPORARY CURB RAMP	15.00 EACH

**ADDENDUM No. 1 – Deleted Item 503503 - (06/15/11-PGF)**