#### STATE OF DELAWARE

THIS COPY IS FOR INFORMATION ONLY. YOU MUST PURCHASE THE PROPOSAL IN ORDER TO SUBMIT A BID.



### DEPARTMENT OF TRANSPORTATION

#### BID PROPOSAL

for

## CONTRACT <u>T201106304.01</u>

PAVEMENT & REHABILITATION, SOUTH II-IV, 2011 SUSSEX COUNTY

Completion Date 80 Calendar Days

SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DELAWARE DEPARTMENT OF TRANSPORTATION AUGUST 2001

Bids will be received in the Bidder's Room (B1.11.01), Transportation Administration Center, 800 Bay Road,

Dover, Delaware until 2:00 P.M. local time August 2 16, 2011



#### STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION

JACK MARKELL GOVERNOR

PO BOX 778 DOVER, DELAWARE 19903

SHAILEN P. BHATT SECRETARY

VIA FACSIMILE

(302) 760-2030 FAX (302) 739-2254

July 29, 2011

Contract No. T201106304.01 PAVEMENT & REHABILITATION, SOUTH II-IV, 2011 Sussex County

Ladies and Gentlemen:

Enclosed is Addendum No. 1 for the referenced contract consisting of the following:

1. One (1) page, Bid Proposal Cover, revised, to be substituted for the same page in the Proposal.

**NOTE:** 

The date for the receipt of bids has been extended until August 16, 2011. Bids will be received until 2:00 P.M., Local Time, the Bidder's Room (B1.11.01), in the DelDOT Transportation Administration Center, 800 Bay Road, U.S. Route 113 South, Dover, DE.

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,

Scott S. Gottfried

Competitively Bid Contracts Coordinator

:ssg Enclosure

#### Contract No.T201106304.01

## PAVEMENT & REHABILITATION, SOUTH II-IV, 2011 SUSSEX COUNTY

#### **LOCATION**

These improvements are located in SUSSEX County more specifically shown on the Location Map(s) of the enclosed Plans.

#### **DESCRIPTION**

The improvements consist of furnishing all materials for PAVEMENT & REHABILITATION, SOUTH II-IV, 2011, and other incidental construction in accordance with the location, notes and details shown on the plans and as directed by the Engineer.

#### **COMPLETION DATE**

All work on this contract must be complete within 80 Calendar Days.

It is the Department's intent to issue a Notice to Proceed such that work starts on or about August 1, 2011

#### **ELECTRONIC BIDDING**

This project incorporates the electronic bidding system Expedite 5.2b. Bidder wishing to use the electronic bidding option should request a bid file disk and installation CD.

#### PROSPECTIVE BIDDERS NOTE:

No retainage will be withheld on this contract.

The Department has adopted an External Complaint Procedure. The procedure can be viewed on our website at; http://www.deldot.gov/information/business/, or you may request a copy by calling (302) 760-2555.

# STATE OF DELAWARE CONSTRUCTION ITEMS UNITS OF MEASURE

English Code	English Description	Multiply By	Metric Code	Metric Description	Suggested CEC Metric Code
ACRE	Acre	0.4047	ha	Hectare	HECTARE
BAG	Bag	N/A	Bag	Bag	BAG
C.F.	Cubic Foot	0.02832	m³	Cubic Meter	M3
C.Y.	Cubic Yard	0.7646	m³	Cubic Meter	M3
EA-DY	Each Day	N/A	EA-DY	Each Day	EA-DY
EA-MO	Each Month	N/A	EA-MO	Each Month	EA-MO
EA/NT	Each Night	N/A	EA-NT	Each Night	EA/NT
EACH	Each	N/A	EA	Each	EACH
GAL	Gallon	3.785	L	Liter	L
HOUR	Hour	N/A	h	Hour	HOUR
INCH	Inch	25.4	mm	Millimeter	MM
L.F.	Linear Foot	0.3048	m	Linear Meter	L.M.
L.S.	Lump Sum	N/A	L.S.	Lump Sum	L.S.
LA-MI	Lane Mile	1.609	LA-km	Lane-Kilometer	LA-KM
LB	Pound	0.4536	kg	Kilogram	KG
MFBM	Thousand Feet of Board Measure	2.3597	m³	Cubic Meter	M3
MGAL	Thousand Gallons	3.785	kL	Kiloliter	KL
MILE	Mile	1.609	km	Kilometer	KM
S.F.	Square Foot	0.0929	m²	Square Meter	M2
S.Y.	Square Yard	0.8361	m²	Square Meter	M2
SY-IN	Square Yard-Inch	0.8495	m²-25 mm	Square Meter-25 Millimeter	M2-25 MM
TON	Ton	.9072	t	Metric Ton (1000kg)	TON
N.A.*	Kip	4.448	kN	Kilonewton	N.A.*
N.A.*	Thousand Pounds per Square Inch	6.895	MPa	Megapascal	N.A.*

<sup>\*</sup>Not used for units of measurement for payment.

#### Contract No. T201106304.01

LOCATION
DESCRIPTION
CONSTRUCTION ITEMS UNITS OF MEASURE i
GENERAL NOTICES
SPECIFICATIONS
CLARIFICATIONS
ATTESTING TO NON-COLLUSION
QUANTITIES
PREFERENCE FOR DELAWARE LABOR
TAX CLEARANCE
LICENSE
DIFFERING SITE CONDITIONS
PREVAILING WAGES
PREVAILING WAGE DETERMINATION - Highway Construction
SUPPLEMENTAL SPECIFICATIONS
SPECIAL PROVISIONS
CONSTRUCTION ITEM NUMBERS
401502 - ASPHALT CEMENT COST ADJUSTMENT
304508 – BITUMINOUS STABILIZED FULL-DEPTH RECLAMATION
401576 – RECYCLED ASPHALT PAVEMENT
401667 - SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG-64-
22, PATCHING
401699 - QUALITY CONTROL/QUALITY ASSURANCE OF BITUMINOUS CONCRETE
401099 - QUALITT CONTROL/QUALITT ASSURANCE OF BITUMINOUS CONCRETE
401713 - EMULSIFIED ASPHALT
401752 – SAFETY EDGE FOR ROADWAY PAVEMENT
401801 – WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)
$4\dot{2}$
705519 - PATTERNED PORTLAND CEMENT CONCRETE SIDEWALK, 6"
735534 - SOIL RETENTION BLANKET MULCH, TYPE 4
746774 - SUPPLY AND INSTALLATION OF LOOP DETECTOR WIRE 53
746776 - LOOP DETECTOR SPLICE
748506 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, $\overline{4}'$
760509 - RUMBLE STRIPS, FULL LANE WIDTH
763502 - MAINTENANCE OF RAILROAD TRAFFIC (NORFOLK SOUTHERN)
763643 - MAINTENANCE OF RAILROAD TRAFFIC (NORPOLK SOUTHERN)
UTILITY STATEMENT
RIGHT OF WAY CERTIFICATE
ENVIRONMENTAL STATEMENT
BID PROPOSAL FORMS
BREAKOUT SHEETS99

#### **GENERAL NOTICES**

#### SPECIFICATIONS:

The specifications entitled "Delaware Standard Specifications, for Road and Bridge Construction, August, 2001", hereinafter referred to as the Standard Specifications, Supplemental Specifications issued as of the advertisement date of this proposal, the Special Provisions, notes on the Plans, this Bid Proposal, and any addenda thereto shall govern the work to be performed under this contract.

#### **CLARIFICATIONS:**

Under any Section or Item included in the Contract, the Contractor shall be aware that when requirements, responsibilities, and furnishing of materials are outlined in the details and notes on the Plans and in the paragraphs preceding the "Basis of Payment" paragraph in the Standard Specifications or Special Provisions, no interpretation shall be made that such stipulations are excluded because reiteration is not made in the "Basis of Payment" paragraph.

#### ATTESTING TO NON-COLLUSION:

The Department requires as a condition precedent to acceptance of bids a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with such contract. The form for this sworn statement is included in the proposal and must be properly executed in order to have the bid considered.

#### **QUANTITIES:**

The quantities shown are for comparison of bids only. The Department may increase or decrease any quantity or quantities without penalty or change in the bid price. Under no circumstances will the total value of the contract exceed 150% of the awarded value.

#### REQUIREMENT BY DEPARTMENT OF LABOR FOR SWORN PAYROLL INFORMATION

Delaware Code, Title 29, Chapter 69, Section 6960, Paragraph (c)

- "(c) Every contract based upon these specifications shall contain a stipulation that certified sworn payroll reports be maintained by every contractor and subcontractor performing work upon the site of construction. The contractor and subcontractor shall keep and maintain the sworn payroll information for a period of two (2) years from the last day of the work week covered by the payroll. A certified copy of these payroll reports shall be made available:
  - 1. For inspection or furnished upon request to a representative of the Department of Labor:
  - 2. Upon request by the public or for copies thereof. However, a request by the public must be made through the Department of Labor. The requesting party shall, prior to being provided the records, reimburse the costs of preparation by the Department of Labor in accordance with the Department's copying fee policy. The public shall not be given access to the records at the principal office of the contractor or subcontractor; and
  - 3. The certified payroll records shall be on a form provided by the Department of Labor or shall contain the same information as the form provided by the Department and shall be provided within ten (10) days from receipt of notice requesting the records from the Department of Labor."

#### Contractor may contact:

Department of Labor Division of Industrial Affairs 4425 No. Market Street Wilmington, DE 19802 Telephone (302) 761-8200

#### PREFERENCE FOR DELAWARE LABOR:

Delaware Code, Title 29, Chapter 69, Section 6962, Paragraph (d), Subsection (4)b

"In the construction of all public works for the State or any political subdivision thereof, or by firms contracting with the State or any political subdivision thereof, preference in employment of laborers, workmen or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State. Each public works contract for the construction of public works for the State or any political subdivision thereof shall contain a stipulation that any person, company or corporation who violates this section shall pay a penalty to the Secretary of Finance equal to the amount of compensation paid to any person in violation of this section."

#### EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS:

Delaware Code, Title 29, Chapter 69, Section 6962, Paragraph (d), Subsection (7)

"a. As a condition of the awarding of any contract for public works financed in whole or in part by State appropriation, such contracts shall include the following provisions:

`During the performance of this contract, the contractor agrees as follows:

- 1. The contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex or national origin. The contractor will take positive steps to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, creed, color, sex or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
- 2. The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex or national origin.'

#### TAX CLEARANCE:

As payments to each vendor or contractor aggregate \$2,000, the Division of Accounting will report such vendor or contractor to the Division of Revenue, who will then check the vendor or contractor's compliance with tax requirements and take such further action as may be necessary to insure compliance.

#### LICENSE:

A person desiring to engage in business in this State as a contractor shall obtain a license upon making application to the Division of Revenue. Proof of said license compliance to be made prior to, or in conjunction with, the execution of a contract to which he has been named.

#### DIFFERING SITE CONDITIONS,

#### SUSPENSIONS OF WORK and SIGNIFICANT CHANGES IN THE CHARACTER OF WORK:

<u>Differing site conditions</u>: During the progress of the work, if subsurface or latent physical conditions are encountered at the site differing materially from those indicated in the contract of if unknown physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract are encountered at the site, the party discovering such conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

Upon written notification, the engineer will investigate the conditions, and if he/she determines that the conditions materially differ and cause an increase or decrease in the cost or time required for the performance of any work under the contract, an adjustment, excluding loss of anticipated profits, will be made and the contract modified in writing accordingly. The engineer will notify the contractor of his/her determination whether or not an adjustment of the contract is warranted.

No contract adjustment which results in a benefit to the contractor will be allowed unless the contractor has provided the required written notice.

No contract adjustment will be allowed under their clause for any effects caused on unchanged work.

<u>Suspensions of work ordered by the engineer:</u> If the performance of all or any portion of the work is suspended or delayed by the engineer in writing for an unreasonable period of time (not originally anticipated, customary or inherent to the construction industry) and the contractor believes that additional compensation and/or contract time is due as a result of such suspension or delay, the contractor shall submit to the engineer in writing a request for adjustment within 7 calendar days of receipt of the notice to resume work. The request shall set fourth the reasons and support for such adjustment.

Upon receipt, the engineer will evaluate the contractor's request. If the engineer agrees that the cost and/or time required for the performance of the contract has increased as a result of such suspension and the suspension was caused by conditions beyond the control of and not the fault of the contractor, its suppliers, or subcontractors at any approved tier, and not caused by weather, the engineer will make an adjustment (excluding profit) and modify the contract in writing accordingly. The engineer will notify the contractor of his/her determination whether or not an adjustment of the contract is warranted.

No contract adjustment will be allowed unless the contractor has submitted the request for adjustment within the time prescribed.

No contract adjustment will be allowed under this clause to the extent that performance would have been suspended or delayed by any other cause, or for which an adjustment is provided for or excluded under any other term or condition of this contract.

<u>Significant changes in the character of work:</u> The engineer reserves the right to make, in writing, at any time during the work, such changes in quantities and such alterations in the work as are necessary to satisfactorily complete the project. Such changes in quantities and alterations shall not invalidate the contract nor release the surety, and the contractor agrees to perform the work as altered.

If the alterations or changes in quantities significantly change the character of the work under the contract, whether or not changed by any such different quantities or alterations, an adjustment, excluding loss of anticipated profits, will be made to the contract. The basis for the adjustment shall be agreed upon prior to the performance of the work. If a basis cannot be agreed upon, then an adjustment will be made either for or against the contractor in such amount as the engineer may determine to be fair and equitable.

The term "significant change" shall be construed to apply only to the following circumstances:

- (A) When the character of the work as altered differs materially in kind or nature from that involved or included in the original proposed construction or
- (B) When a major item of work, as defined elsewhere in the contract, is increased in excess of 125 percent or decreased below 75 percent of the original contract quantity. Any allowance for an increase in quantity shall apply only to that portion in excess of 125 percent of original contract item quantity, or in case of a decrease below 75 percent, to the actual amount of work performed.

#### PREVAILING WAGES

Included in this proposal are the minimum wages to be paid various classes of laborers and mechanics as determined by the Department of Labor of the State of Delaware in accordance with Title 29 <u>Del.C.</u> §6960, relating to wages and the regulations implementing that Section.

#### Contract No. T201106304.01

Title 29 <u>Del.C.</u> §6960 relating to wages further stipulates "that the employer shall pay all mechanics and laborers employed directly upon the site of the work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics", and ... "that the scale of wages to be paid shall be posted by the employer in a prominent and easily accessible place at the site of the work, and that there may be withheld from the employer so much of accrued payments as may be considered necessary by the Department of Labor to pay to laborers and mechanics employed by the employer the difference between the rates of wages required by the contract to be paid laborers and mechanics on the work and rates of wages received by such laborers and mechanics to be remitted to the Department of Labor for distribution upon resolution of any claims."

Bidders are specifically directed to note the Department of Labor's regulations implementing §6960 relating to the effective date of the wage rates, at Part VI., Section C., which in relevant part states:

"Public agencies (covered by the provisions of 29 <u>Del.C.</u> §6960) are required to use the rates which are in effect on the date of the publication of specifications for a given project. In the event that a contract is not executed within one hundred twenty (120) days from the date the specifications were published, the rates in effect at the time of the execution of the contract shall be the applicable rates for the project."

# STATE OF DELAWARE DEPARTMENT OF LABOR DIVISION OF INDUSTRIAL AFFAIRS OFFICE OF LABOR LAW ENFORCEMENT

PHONE: (302) 451-3423

Mailing Address: 225 CORPORATE BOULEVARD SUITE 104 NEWARK, DE 19702 Located at: 225 CORPORATE BOULEVARD SUITE 104 NEWARK, DE 19702

PREVAILING WAGES FOR HIGHWAY CONSTRUCTION EFFECTIVE MARCH 15, 2011

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
BRICKLAYERS	44.98	44.98	14.51
CARPENTERS	40.86	48.31	38.62
CEMENT FINISHERS	28.11	24.68	23.29
ELECTRICAL LINE WORKERS	22.50	54.05	54.05
ELECTRICIANS	57.10	57.10	57.10
IRON WORKERS	42.20	22.98	25.35
LABORERS	25.44	23.33	24.00
MILLWRIGHTS	16.11	15.63	13.49
PAINTERS	41.42	41.42	41.42
PILEDRIVERS	59.23	23.75	26.95
POWER EQUIPMENT OPERATORS	31.46	26.00	26,31
SHEET METAL WORKERS	22.75	20.31	18.40
TRUCK DRIVERS	26.54	21.58	19.96

CERTIFIED: 5/17/11

BY:

ADMENISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

NOTE:

THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE (302) 451-3423.

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: T201106304.01 Pavement and Rehabilitation, South II-IV, 2011, Sussex County

# SUPPLEMENTAL SPECIFICATIONS TO THE AUGUST 2001 STANDARD SPECIFICATIONS

# EFFECTIVE AS OF THE ADVERTISEMENT DATE OF THIS PROPOSAL AND INCLUDED BY REFERENCE

The Supplemental Specifications can be viewed and printed from the Department's Website.

#### To access the Website:

- in your internet browser, enter; http://www.deldot.gov
- on the left side of the page under 'INFORMATION', Click; 'Publications'
- scroll down under 'MANUALS' and Click; "Standard Specifications 2001"

#### The full Website Link is:

http://www.deldot.gov/information/pubs\_forms/manuals/standard\_specifications/index.shtml

Printed copies of the Supplemental Specifications are available upon request. A printed copy of the above referenced Supplemental Specifications will be included in the final contract documents upon award.

The Contractor shall make himself aware of these revisions and corrections (Supplemental Specifications), and apply them to the <u>applicable item(s)</u> of this contract.

# **SPECIAL PROVISIONS**

#### Contract No. T201106304.01

#### **CONSTRUCTION ITEM NUMBERS**

All construction pay items are assigned a six (6) digit number, shown as Item Number on the Plans and/or in the Special Provisions, and shall be interpreted in accordance with the following:

#### **Standard Item Number:**

The first three digits of the construction item numbers indicates the Section number as described in the Standard Specifications, and all applicable requirements of the Section shall remain effective unless otherwise modified by the Special Provisions. The last three digits of the construction item identifies the item by sequential number under that Section. Sequential numbers for all items covered under Standard Specifications range from 000 to 499. A comprehensive list of construction item numbers begins on page 421 of the Standard Specifications. Additions to this list will be made as required.

#### **Special Provisions Item Number:**

The first three digits of the construction items, covered under Special Provisions, indicates the applicable Section number of the Standard Specifications, and shall be governed fully by the requirements of the Special Provisions. The last three digit of the items covered under Special Provisions identifies the item by sequential number. Sequential numbers for Special Provision items, range from 500 to 999.

#### **Examples**

#### Standard Item Number - 202000 Excavation and Embankment

202 Indicates Section Number

000 Indicates Sequential Number

#### Special Provision Item Number - 202500 Grading and Reshaping Roadway

202 Indicates Section Number

500 Indicates Sequential Number

#### Contract No. T201106304.01

#### **401502 - ASPHALT CEMENT COST ADJUSTMENT**

For Sections 304, 401, 402, 403, 404, and 405, payments to the Contractor shall be adjusted to reflect increases or decreases in the Delaware Posted Asphalt Cement Price when compared to the Project Asphalt Cement Base Price, as defined in these Special Provisions.

The Delaware Posted Asphalt Cement Price will be issued monthly by the Department and will be the industry posted price for Asphalt Cement, F.O.B. Philadelphia, Pennsylvania.

The Project Asphalt Cement Base Price will be the anticipated Delaware Posted Asphalt Cement Price expected to be in effect at the time of receipt of bids.

All deviations of the Delaware Posted Asphalt Cement Price from the Project Asphalt Cement Base Price are eligible for cost adjustment. No minimum increases or decreases or corresponding percentages are required to qualify for cost adjustment.

Actual quantity of asphalt cement qualifying for any Asphalt Cement Cost Adjustment will be computed on the basis of weight tickets and asphalt percentage from the approved job mix formula.

For Recycled Hot-Mix the asphalt percentage eligible for cost adjustment shall be  $\underline{\text{only}}$  the  $\underline{\text{new}}$  asphalt cement added to the mix.

There shall be no separate payment per ton (metric ton) cost of asphalt cement. That cost shall be included in the various unit prices bid per ton (metric ton) for those bid items that contain asphalt cement (mentioned above).

The Asphalt cement cost adjustment will be calculated on grade PG 64-22 asphalt regardless of the actual grade of asphalt used. The Project Asphalt Cement Base Price for the project will be  $\underline{\$635.00}$  per ton ( $\underline{\$699.97}$  per metric ton).

If the Contractor exceeds the authorized allotted completion time, the price of asphalt cement on the last authorized allotted work day, shall be the prices used for cost adjustment during the time liquidated damages are assessed. However, if the industry posted price for asphalt cement goes down, the asphalt-cement cost shall be adjusted downward accordingly.

#### NOTE

Application of Asphalt Cement Cost Adjustment requirements as indicated above shall apply only to those contracts involving items related to bituminous base and pavements, and with bitumen, having a total of 1,000 tons (1,000 metric tons) or more of hot-mix bid quantity in case of Sections 401, 402 and 403; and 15,000 gallons (60 000 liters) or more in case of Sections 304, 404 and 405.

#### 304508 - BITUMINOUS STABILIZED FULL-DEPTH RECLAMATION

#### **Description:**

This work shall consist of stabilization of road pavements by in-place pulverizing and blending of the existing underlying granular material with an appropriate percentage of bituminous and/or chemical additives. To adjust the grade, Graded Aggregate Base Course (GABC), Recycled Concrete Aggregate (RCA), or Recycled Asphalt Pavement (RAP) may be added to meet the requirements. The process shall result in a uniformly mixed, fully compacted and cured mixture of sub-grade and roadway materials to produce a working platform for subsequent paving operations and a structural support for the pavement.

Unless otherwise referenced, the depth of full-depth reclamation shall be 6".

#### **Materials:**

**Reclaimed Material.** Once this material is pulverized, the following gradations shall be met: 95% passing the 2" sieve. If more than 5% is retained on the 2" sieve the pavement pulverizing process shall be adjusted to reduce the amount to less than 5%.

**Stabilizing Agents.** Recycling agents, such as CSS 1h emulsion, will be accepted under certification from the Contractor. All recycling agents delivered shall be sampled in the presence of the Engineer. The Contractor shall place a representative sample in a clean plastic container, note the date of sample, load number, and gallons verified. The sample shall be provided to the Engineer for testing.

**Additives.** Additives to help in the mixing operation or curing process shall be approved by the Engineer prior to incorporation into the mix.

**Aggregates.** If imported aggregates are required, they shall meet the material requirements of Section 302 of the Standard Specifications for GABC or RCA. If RAP is required, it shall have 100% passing the 2" sieve.

#### **Preconstruction:**

**Sampling and Pre-Testing Reclaimed Materials.** The Contractor shall obtain samples of the granular base and sub-grade soils from test pits or cores to the depth to be reclaimed for laboratory evaluation. The Contractor shall provide to the Engineer the following information:

- 1. Test Pit and cores location, one sample for every 1500 lane-feet with a minimum of six samples for each mix design, with additional locations selected upon pavement conditions and variability.
- 2. Depth of the existing road structure to be reclaimed unless shown otherwise on plans.
- 3. Laboratory test results:

DESCRIPTION OF TEST METHOD	AASHTO TEST
Determination of water moisture content	T265
Liquid Limit, Plastic Limit, and Plasticity Index of Soil	T89, T90
Sand Equivalent Value of Soils and Fine Aggregate	T176
Sieve Analysis of Fine and Coarse Aggregate	T27
Classification of Soils	M145

**Mix Design.** The Contractor shall be responsible for determining what recycling agent, and additives are necessary to produce an acceptable mix. The design shall be performed by the Contractor in accordance with these specifications and submitted to the Engineer for approval a minimum of 10 working days prior to the planned start of the work. The mixture design shall determine: the suitability of the reclaimed material, optimum moisture content determine the optimum bitumen content, and confirmation of the mechanical properties of the stabilized mix. The Contractor shall submit, to the Engineer for approval, the mix design listing the name, source, and amount of each recycling agent.

#### **Construction Methods:**

Weather Limitations. This recycling operation shall be performed with asphalt emulsion when the atmospheric temperature, in the shade, is 55°F and rising and it is not foggy. Recycling operations shall not be performed when rain is occurring or rain is imminent or night temperatures are forecast to fall below 35°F.

Subsequent lifts shall not be placed on the cured recycled base course within forty eight hours of any rain event.

**Equipment.** The equipment shall be capable of reclaiming in-place bituminous overlays and road base materials to the depth called for in the plans and pulverizing them down to the gradation as defined above. Only a single lane shall be pulverized and mixed at a time to ensure the least practical obstruction to the traveling public. When the adjoining lane is pulverized, the lane already reclaimed shall be overlapped 6" unless otherwise directed by the Engineer. The adjoining lane shall be used as a reference for the finished grade at the centerline of the roadway unless otherwise shown on the Plans or as directed by the Engineer.

Mixing of all reclaimed materials, aggregates, and emulsified asphalt shall be conducted in-place. The GABC, RCA, and/or RAP, recycling agent, and additives shall be combined in the quantities required by the specifications or as directed by the Engineer. The mixing operation shall result in the GABC, RCA, and/or RAP being completely and uniformly coated with the recycling agent and additives, if used.

The mix in-place operation shall spread the required quantity of reclaimed material and aggregate, if required, on the prepared area in a uniform loose layer to obtain the specified compacted depth. Adjust the speed of the mixer to obtain a thorough and uniform mixture.

Ensure that positive displacement pumps accurately meter the planned amount of bituminous material and the pulverizing machine mixes it thoroughly with the GABC, RCA, and/or RAP materials. The pump shall be mechanically or electronically interlocked with the ground speed of the machine. The bituminous metering system and water metering system shall be capable of continuous monitoring (gallons per minute) flow, and totalizing the quantity of the bituminous material applied into the mixing chamber. The travel speed, in feet, shall be visible on the computer readout screen.

Self-propelled asphalt pavers shall conform to Subsection 401.05 of the Standard Specifications and shall be utilized to spread the recycled mixture to the established grade and cross slope. The paving operations shall be conducted to protect existing and finished pavement sections. The paver shall be equipped with a floating averaging beam or non-contact averaging beam.

**Test Rolling.** After the cure time has elapsed, test rolling shall be performed with a fully legally loaded ten-wheel dump truck or other equipment approved by the Engineer that will reveal any soft or yielding areas. The equipment shall be run longitudinally with less than 18" of unrolled area between the tire strips.

If the test rolling reveals any soft or yielding areas, the Contractor shall be required to stabilize, compact, and cure the designated areas to achieve the required stability.

Acceptance of the test roll by the Engineer will be required prior to placement of subsequent lifts.

**Grading & Compaction.** After the mixture has been spread, allowed to cure as necessary, and any surface irregularities corrected, the mat shall be uniformly compacted without displacement and cracking.

A minimum of one pneumatic tire roller (minimum 25 tons) operated at a maximum of 4 mph and one double drum vibratory steel-wheeled roller (minimum 12 tons), operated in a vibratory mode, shall be utilized at all times in the rolling operation. The sequence of rolling operations shall provide a minimum density of 88% of the theoretical maximum density (AASHTO T209), or a minimum density of 93% of laboratory specimens made of production materials obtained.

When the rolling operations are to be based on the control strip method of density control, the control strip shall be constructed of mixture produced with the reclamation equipment and within the pavement section. The Contractor shall construct at least two (2) control strips by varying the roller sequence to achieve

maximum density. Compact the remaining recycled mixture to a target density of at least 96% of the highest average control strip density. Whenever there is a change in the reclaimed materials or compaction method or equipment, or when unacceptable results occur, at least two (2) new test control strips shall be constructed by varying the roller sequence to achieve maximum density.

Excess material from the operation shall be removed and disposed of in an approved manner by the Contractor.

**Surface Tolerance.** When directed by the Engineer, the completed layer shall be tested for smoothness and accuracy of grade. Difference of level between any two points of the surface, controlled by the 10-foot straightedge, shall not exceed 0.5".

**Depth Check.** One drilled core for each 500' or less of completed recycled bituminous base shall be utilized to determine the depth of the recycled base. The Contractor shall remove and replace any section deficient by 1/2" or greater from the specified depth at no expense to the Department

**Curing.** Allow the recycled base course to cure for at least one week before placing subsequent lifts unless otherwise permitted by the Engineer.

#### **Method of Measurement:**

The quantity of stabilized pavement will be measured as the actual number of square yards of pavement stabilized and accepted.

The quantity of GABC, RAC, or RAP added will be measured by the ton in accordance with Subsection 302.05 of the Standard Specifications.

The quantity of emulsified asphalt will be measured in accordance with Subsection 109.01 of the Standard Specifications as the number of gallons of emulsified asphalt used in the completed and accepted stabilized pavement not to exceed, in the proportion of the mix for payment purposes, more than 10% of the theoretical design percentage.

There will be no measurement for water or any stabilizing agents, other than emulsified asphalt.

#### **Basis of Payment:**

The quantity of stabilized pavement will be paid for at the Contract unit price per square yard. Price and payment will constitute full compensation for sampling, designing the mix, furnishing water and stabilizing agents (other than emulsified asphalt), pulverizing the sub-grade, mixing, compacting, grading, and for all labor, equipment, tools and incidentals required to complete the work.

The quantity of GABC, RCA, or RAP will be paid for at the Contract unit price per ton. Price and payment will constitute full compensation for furnishing and spreading the material. GABC, RCA, or RAP will be paid for under it respective item.

The quantity of emulsified asphalt will be paid for at the Contract unity price per gallon. Price and payment will constitute full compensation for furnishing, mixing and applying the emulsified asphalt, and for all labor, equipment, tools and incidentals required to complete the work. Emulsified asphalt will be paid for under its respective item.

5/4/11

#### 401576 - RECYCLED ASPHALT PAVEMENT

#### **Description:**

This work consists of hauling and placing recycled asphalt pavement (RAP) on a scarified surface in conformance with the lines, grades, and typical cross sections, or as directed by the Engineer at the locations shown on the plans to allow for the incorporation of RAP prior to reclamation of the roadway.

#### **Construction Methods:**

The contractor shall place the RAP with an approved hot-mix asphalt paver in the areas directed by the Engineer to achieve a uniform cross-slope transversely in the roadway. The RAP shall not be compacted to a minimum of 95% compaction as it will be incorporated in the reclamation process.

#### **Method of Measurement:**

The quantity of recycled asphalt pavement will be measured as the actual number of tons (metric tons) accepted.

#### **Basis of Payment:**

The quantity of recycled asphalt pavement will be paid for at the Contract unit price per tons (metric tons). Price and payment will constitute full compensation for hauling and placing the recycled asphalt pavement and for all labor, equipment, tools, and incidentals required to complete the work, including the correction of defective work.

11/4/03

- 401644 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 64-22 (CARBONATE STONE) 401645 - SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22 (CARBONATE STONE) 401646 - SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 64-22 (CARBONATE STONE)
  - 401647 SUPERPAVE, TYPE B HOT-MIX, 115 GYRATIONS, PG 64-22 401648 SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 64-22 401649 SUPERPAVE, TYPE B HOT-MIX, 205 GYRATIONS, PG 64-22
- 401650 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 70-22 (CARBONATE STONE) 401651 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 70-22 (CARBONATE STONE) 401652 SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 70-22 (CARBONATE STONE)
  - 401653 SUPERPAVE, TYPE B HOT-MIX, 115 GYRATIONS, PG 70-22 401654 SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 70-22 401655 SUPERPAVE, TYPE B HOT-MIX, 205 GYRATIONS, PG 70-22
- 401656 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 76-22 (CARBONATE STONE) 401657 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22 (CARBONATE STONE) 401658 SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 76-22 (CARBONATE STONE)
  - 401659 SUPERPAVE, TYPE B HOT-MIX, 115 GYRATIONS, PG 76-22 401660 - SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 76-22 401661 - SUPERPAVE, TYPE B HOT-MIX, 205 GYRATIONS, PG 76-22
- 401662 SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 115 GYRATIONS, PG 64-22
- 401663 SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22
- 401664 SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 205 GYRATIONS, PG 64-22
- 401665 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING 401666 SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING 401667 SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG-64-22, PATCHING
  - 401668 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG-64-22, WEDGE 401669 SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG-64-22, WEDGE
- 401704 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
- 401705 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
- 401706 SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
- 401707 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
- 401708 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
- 401709 SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
- 401710 SUPERPAVE, TYPE C HOT-MIX, 115 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)
- 401711 SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)
- <u>401712 SUPERPAVE, TYPE C HOT-MIX, 205 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)</u>

#### **Description**:

The following Subsections of the Standard Specifications shall be applicable: 401.01, 401.03 - 401.12, and 401.13. All other subsections have been modified herein.

The Contractor shall read and thoroughly understand the requirements of the QA/QC specification as defined in item 401699. It is the responsibility of the Contractor to determine all costs associated with meeting these requirements and to include them in the per ton bids for the various Superpave bituminous concrete items. The Contractor shall also be aware that the pay adjustment factors in item 401699 will be applied to the Superpave bituminous concrete payments to determine the bonus or penalty for the item.

#### **Materials:**

Materials for hot-mix, hot-laid bituminous concrete shall conform to the requirements of Subsections 823.01, 823.05-823.17, and 823.25 - 823.28 of the Standard Specifications and the following.

#### **Asphalt Binder:**

The asphalt binder shall meet the requirements of Superpave PG 64-22, PG 70-22, or PG 76-22 performance grade asphalt, as referenced in the Plans, according to M-320, Table 1 and tested according to AASHTO PP6 with the following test ranges:

TEST PROCEDURE	AASHTO REFERENCE	SPECIFICATION LIMITS
Temperature, °C	M-320	Per Grade
Original DSR, G*/sin (δ)	T-315	1.00 - 2.00 kPa
RTFO DSR, G*/sin (δ)	T-315	2.20 - 5.00 kPa
PAV DSR, G*/sin (δ)	T-315	1400 - 5000 kPa
BBR Creep Stiffness	T-313	90.0 - 300.0 kPa
BBR — value	T-313	0.300 - 0.440

Substitution of a higher temperature grade will require prior approval by the Engineer.

#### **Recycled Materials:**

The percentage allowance of recycled materials (recycled asphalt pavement and/or shingles) shall be controlled through the use of the Materials & Research recycled mixture program available through the Materials & Research Section. The program can be used by the Contractor to determine which materials and combinations of materials can be used to meet the specified material on the contract.

If the Contractor proposes to use a combination of materials that are not covered by this program, the mix design shall be submitted and reviewed by the Engineer.

#### **Shingles:**

Only shingles reclaimed from shingle manufacturers such as tabs, punch-outs, and damaged new shingles shall be allowed in the mixture. Post-consumer shingles or used shingles shall not be permitted in the mixture and all shingles shall be free of all foreign material and moisture. Fiberglass-backed and organic felt-backed shingles shall be kept separately and both materials shall not be used in the same mixture at the same time. The shingles shall be broken down in the mixing process with 100% passing the  $\frac{1}{2}$  in (12.5 mm) sieve. Shipping, handling, and shredding costs are incidental to the price of Superpave item.

#### **Mineral Aggregate:**

The mineral aggregate employed in the target gradation of the job mix formula (JMF) shall conform to Section 805 and the following criteria. These criteria apply to the combined aggregate blend.

DESIGN ESAL'S	COARSE AGGREGATE ANGULARITY <sup>1</sup> (% MIN)		ANGULARITY <sup>1</sup> ANGULARITY <sup>2</sup>		CLAY CONTENT <sup>3</sup>	FLAT AND ELONGATED <sup>4</sup>
(MILLIONS)	≤ 100 MM	> 100 MM	≤ 100 MM > 100 MM		(% - MIN)	(% - MAX)
< 0.3	55/-	-/-	-	-	40	-
0.3 to < 3	75/-	50/-	40	40	40	
3 to <10	85/80 <sup>5</sup>	60/-	45	40	45	
10 < 30	95/90	80/75	45	40	45	10
≥30	100/100	100/100	45	45	50	

<sup>&</sup>lt;sup>1</sup>Coarse Aggregate Angularity is tested according to ASTM D5821.

The following source properties apply to the individual aggregates in the aggregate blend for the proposed JMF.

TEST METHOD	SPECIFICATION LIMITS
Toughness, AASHTO T96 Percent Loss, Maximum	40
Soundness, AASHTO T104 Percent Loss, Maximum for five cycles	20
Deleterious Materials, AASHTO T112 Percent, Maximum	10
Moisture Sensitivity, AASHTO T283 Percent, Minimum	80

For any roadway with a minimum average daily traffic volume (ADT) of 8000 vehicles and a posted speed of 35 mph (60 kph) or greater, the polish value of the composite aggregate blend shall be greater than 8.0 when tested according to Maryland State Highway Administration MSMT 411 – "Laboratory Method of Predicting Frictional Resistance of Polished Aggregates and Pavement Surfaces." RAP shall be assigned a value of 4.0. The Contractor shall supply all polish values to the Engineer upon request.

#### **Mineral Filler:**

The mineral filler shall conform to AASHTO M17.

#### **Mixture Requirements:**

**Mix Design.** Develop and submit a job mix formula for each mixture according to AASHTO R35. Each mix design shall be capable of being produced, placed, and compacted as specified.

**Gradation:** The FHWA Superpave 0.45 Power Chart with the recommended restricted zone shall be used to define permissible gradations for the specified mixture. Type C shall be either a No.4 (4.75 mm), 3/8" (9.5 mm), or 1/2" (12.5 mm) Nominal Maximum Aggregate Size Hot-Mix. Unless otherwise noted in the Plans, the Type C shall meet the 3/8" (9.5 mm) Nominal Maximum Aggregate Size. Type B Hot-Mix shall be the 3/4" (19.0 mm) Nominal Maximum Aggregate Size and the Bituminous Concrete Base Course (BCBC) shall

<sup>&</sup>lt;sup>2</sup>Fine Aggregate Angularity is tested according to AASHTO TP-33.

<sup>&</sup>lt;sup>3</sup>Clay Content is tested according to AASHTO T176.

<sup>&</sup>lt;sup>4</sup>Flat and Elongated is tested according to ASTM 4791 with a 5:1 aspect ratio.

<sup>&</sup>lt;sup>5</sup> 85/80 denotes that 85% of the coarse aggregate has one fractured face and 80% has two or more fractured faces.

be the 1" (25.0 mm) Nominal Maximum Aggregate Size. Target values for percent passing each standard sieve for the design aggregate structure shall comply with the Superpave control points and should avoid the restricted zone. Percentages shall be based on the washed gradation of the aggregate according to AASHTO T11.

In addition to the results of the material requirements specified above, the following material properties shall be provided by the contractor: bulk specific gravity  $G_{sb}$ , apparent specific gravity  $G_{sa}$ , and the absorption of the individual aggregate stockpiles to be used, tested according to AASHTO T84 and AASHTO T85 and reported to three decimal places along with the specific gravity of the mineral filler to be used, tested according to AASHTO T100 and reported to three decimal places.

#### **Superpave Gyratory Compactive (SGC) Effort:**

The Superpave Gyratory Compaction effort employed throughout mixture design, field quality control, or field quality assurance shall be as indicated below. All mixture specimens tested in the SGC shall be compacted to  $N_{\rm M}$  Height data provided by the SGC shall be employed to calculate volumetric properties at  $N_{\rm L}$ ,  $N_{\rm D}$ , and  $N_{\rm M}$ 

#### **Superpave Gyratory Compactive (SGC) Effort:**

DESIGN TRAFFIC LEVEL (MILLION ESAL'S)	N <sub>INITIAL</sub>	$N_{ m DESIGN}$	N <sub>MAXIMUM</sub>
0.3 to < 3	7	75	115
3 to < 30	8	100	160
≥30	9	125	205

**Volumetric Design Parameters.** The design aggregate structure at the target asphalt cement content shall satisfy the volumetric criteria below:

DESIGN ESAL'S	(% Ol MAX	UIRED DEN F THEORE' IMUM SPE GRAVITY)	ΓICAL CIFIC		VOIDS-IN-MINERAL AGGREGATE (% - MINIMUM)  NOMINAL MAX. AGGREGATE (MM)				VOIDS FILLED WITH ASPHALT
(MILLION)	N <sub>INITIAL</sub>	$N_{ m DESIGN}$	N <sub>MAX</sub>	25.0	19.0	9.5	12.5	4.75	(% - MINIMUM)
0.3  to < 3	≤ 90.5								65.0 - 78.0
3 to < 10		96.0	≤ 98.0	12.5	13.5	15.5	14.5	16.5	
10 < 30	≤ 89.0	70.0	≥ 70.0	12.3	12.3	13.3	14.5	65.0 - 75.0 <sup>1</sup>	
≥ 30									

Air voids ( $V_a$ ) at  $N_{design}$  shall be 4.0% for all ESAL designs. Air voids ( $V_a$ ) at  $N_{max}$  shall be a minimum of 2.0% for all ESAL designs

The dust to binder ratio for the mix having aggregate gradations above the Primary Control Sieve (PCS) Control Points shall be 0.6-1.2. For aggregate gradations below the PCS Control Points, the dust to binder ratio shall be 0.8-1.6. For the No. 4 (4.75 mm) mix, the dust to binder ratio shall be 0.9-2.0 whether above or below the PCS Control Points.

For 3/8" (9.5 mm) Nominal Maximum Aggregate Size mixtures, the specified VFA range shall be 73.0% to 76.0% and for 4.75 mm Nominal Maximum Size mixtures, the range shall be 75 % to 78% for design traffic levels  $\geq 3$  million ESALs.

#### **Gradation Control Points:**

The combined aggregates shall conform to the gradation requirement specified in the following table when tested according to T-11 and T-27.

Nomina	Nominal Maximum Aggregates Size Control Points, Percent Passing									
	25.0	MM	19.0 MM		12.5 MM		9.5 MM		4.75 MM	
SIEVE SIZE	MIN	MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN	MAX
37.5 MM	100	-	-	-	-	-	-	-	-	-
25.0 MM	90	100	100	-	-	-	-	-	-	-
19.0 MM	-	90	90	100	100	-	-	-	-	-
12.5 MM	-	-	-	90	90	100	100	-	100	-
9.5 MM	-	-	-	-	-	90	90	100	95	100
4.75 MM	-	-	-	-	-	-	-	90	90	100
2.36 MM	19	45	23	49	28	58	32	67	-	-
1.18 MM	-	-	-	-	-	-	-	-	30	60
0.075 MM	1	7	2	8	2	10	2	10	6	12

Note: The aggregate's gradation for each sieve must fall within the minimum and maximum limits.

#### **Gradation Classification:**

The Primary Control Sieve (PCS) defines the break point of fine and coarse mixtures. The combined aggregates shall be classified as coarse graded when it passes below the Primary Control Sieve (PCS) control point as defined below. All other gradations shall be classified as fine graded.

PCS CONTROL POINT FOR MIXTURE NOMINAL MAXIMUM AGGREGATES SIZE (% PASSING)						
Nominal maximum Aggregates Size	25.0 mm	19.0 mm	12.5 mm	9.5 mm	4.5 mm	
Primary Control Sieve	4.75 mm	4.75 mm	2.36 mm	2.36 mm	1.18 mm	
PCS Control Point	40	47	39	47	30-60	

#### **Plant Production Tolerances:**

Volumeric Property	Superpave Criteria
Air Voids (V <sub>a</sub> ) at (%) N <sub>m</sub> Air Voids (V <sub>a</sub> ) at N <sub>design</sub> (%)	2.0 (min) 5.5 (max)
Voids in Mineral Aggregate (VMA) at N <sub>design</sub> 25.0 mm Bituminous Concrete Base Course 19.0 mm Type B Hot-Mix 12.5 mm Type C Hot-Mix 9.5 mm Type C Hot-Mix 4.5 mm Type C Hot-Mix	-1.2 +2.0

#### **Design Evaluation:**

The contractor shall furnish a Job Mix Formula (JMF) for review and approval. The Engineer may elect to evaluate the proposed JMF and suitability of all materials. All materials requested by the Engineer shall be provided at the contractor's expense to the Central Laboratory in Dover in a timely manner upon

#### Contract No. T201106304.01

request. To verify the complete mixture design and evaluate the suitability of all materials, the following approximate quantities are required:

5.25 gal (20 liters) of the asphalt binder;

0.13 gal (0.5 liters) sample of liquid heat-stable anti-strip additive;

254 lb. (115 kg) of each coarse aggregate;

154 lb. (70 kg) of each intermediate and fine aggregate;

22 lb. (10 kg) of mineral filler; and

254 lb. (115 kg) of RAP, when applicable.

#### The proposed JMF shall include the following:

Plot of the design aggregate structure on the FHWA Superpave 0.45 power chart showing the maximum density line, Superpave control points, and recommended restricted zone.

Plot of the three trial asphalt binder contents at +/- 0.5% gyratory compaction curves where the percent of maximum specific gravity (% of  $G_{mm}$ ) is plotted against the log base ten of the number of gyrations (log (N)) showing the applicable criteria for  $N_i$ ,  $N_d$ , and  $N_m$ .

Plot of the percent asphalt binder by total weight of the mix (P<sub>b</sub>) versus the following:

% of  $G_{mm}$  at  $N_d$ , VMA at  $N_d$ , VFA at  $N_d$ , Fines to effective asphalt binder ( $P_{be}$ ) ratio, and unit weight (kg/m²) at both  $N_d$  and  $N_m$ .

Summary of the consensus property standards test results for the design aggregate structure, summary of the source property standards test results for the individual aggregates in the design aggregate structure, target value of the asphalt binder content, and a table of  $G_{\text{mm}}$  of the asphalt mixture for the four trial asphalt binder contents determined according to AASHTO T209.

The JMF shall also include the NCAT Ignition Oven calibration for the specific materials utilized for this mix.

#### Construction.

**Weather Limitations.** Place mix only on dry, unfrozen surfaces and only when weather conditions allow for proper production, placement, handling, and compacting.

#### **Compaction:**

Compaction shall be tested and paid per Item 401699 - Quality Control/Quality Assurance of Bituminous Concrete .05 (b) Pavement Construction - Tests and Evaluations.

#### Method of Measurement and Basis of Payment:

Method of Measurement and Basis of Payment will be in accordance with Subsections 401.14 and 401.15 of the Standard Specifications.

The item 401699, will define adjustment factor to be applied to the bituminous concrete payments for bonus or penalty.

1/06/2010

#### 401696 - ENTRANCE, DRIVEWAY AND INTERSECTING STREET PAVING SURCHARGE

#### **Description:**

This item will only be considered for areas adjacent to the roadway paving that cannot be completed as part of the mainline roadway and auxiliary lane operation. The limits shall be from the outermost roadway element to the point of tie-in of the entrance, driveway, or intersecting street as directed by the Engineer.

It is the intent of this item to compensate the Contractor for the extra work involved when it is necessary for the paving operation to return to complete tie-in's to entrances, driveways and intersecting streets when such work cannot be completed as part of the mainline (roadway, auxiliary lane, shoulder) paving.

When the tie-in to an entrance or driveway is limited to within 3 feet (0.9 meters) of the outermost roadway element, the Contractor shall be expected to complete the tie-in as part of the normal paving operation with paver extensions. No surcharge will be considered.

When the tie-in is greater than 3 feet (0.9 meters) pave extensions will not be used during the mainline paving. The dimensions of the surcharge area will be from the edge of the roadway to the tie-in point. The contractor is to pave this entire area using the paver. The minimum length of the tie-in for side streets will be to the radius point unless otherwise noted on the Plans or directed by the Engineer.

No surcharge will be paid for paving auxiliary lanes and crossovers in the median of divided highways.

#### **Method of Measurement:**

The quantity of entrance, driveway and intersecting street paving for surcharge payment will be actual number of tons (metric tons) of hot-mix placed in entrances, driveways and intersecting streets as described in this item.

#### **Basis of Payment:**

The quantity of entrance, driveway and intersecting street paving, for surcharge payment will be paid for the Contract unit price per ton (metric ton). Price and payment will constitute full compensation for the additional labor and equipment costs involved with the reduced production caused by such work.

#### **Note:**

This item is intended for use on Pave & Rehab Contracts, CTF Contracts and South CTF (numbered road) Contracts only.

1/21/08

#### 401699 - OUALITY CONTROL/OUALITY ASSURANCE OF BITUMINOUS CONCRETE

#### .01 Description.

This item shall govern the Quality Control/Quality Assurance Testing for supplying hot-mix asphalt plant materials and constructing hot-mix asphalt pavements.

The Contractor shall be responsible for providing the quality level of materials and construction incorporated into the Contract that will meet the requirements of the Contract. The Contractor shall perform all necessary quality control inspection, sampling, and testing. The Engineer will evaluate all materials and construction for acceptance. The procedures for Quality Control and Acceptance are described in this Section.

#### .02 Definitions.

- Acceptable Quality Level (AQL): That level of percent within limits (PWL) to which the Engineer will consider the work completely acceptable.
- Acceptance Plan: Factors that comprise the Engineer's determination of the degree of compliance
  with contract requirements and value of the product. These factors include the Engineer's sampling,
  testing, and inspection.
- **Delaware Asphalt Pavement Association (DAPA):** The organization representing the interests of hot-mix asphalt producers and Contractors. The Engineer has a copy of the DAPA officers' names and point(s) of contact.
- **Dispute Resolution:** The procedure used to resolve conflicts resulting from discrepancies between the Engineer's and the Contractor's results of sufficient magnitude to impact payment. The testing will take place at a location and time mutually agreeable by both the Engineer and the Contractor.
- **Full Depth Construction** Construction of an adequate pavement box on a subgrade and subbase prepared by the contractor
- **Independent Assurance:** An unbiased and independent verification of the Quality Assurance system used, and the reliability of the test results obtained in regular sampling and testing activities. The results of Independent Assurance are not to be directly used as a basis of material acceptance.
- **Job Mix Formula (JMF)/Mixture Identification (ID):** The target values for individual aggregate size gradation percentages and the asphalt percentage, the sources of each of the component materials, the proposed proportions of component materials to be used to meet those target values, the asphalt proportion, and the mixing temperature. The Engineer will assign uniquely individual mixture identification for each JMF submitted and approved.
- **Lower Quality Index (QL):** The index reflecting the statistic related to the lower boundary to which a sample (or sample statistic) may deviate from the target value and still be considered acceptable.
- **Mean:** A statistical measure of the central tendency the average value.
- **Operational Day:** A day in which the Engineer has approved a lane closure for the Contractor to perform work within an approved MOT plan.
- **Percent Within Limits (PWL):** That amount of material or workmanship that has been determined, by statistical method, to be within the pre-established characteristic boundary(ies).
- **Qualified Laboratory:** A laboratory mutually agreed upon by both DAPA and the Engineer as having proper test equipment that has been calibrated in accordance to AASHTO.
- Qualified Technician: Personnel mutually agreed upon by both DAPA and the Engineer as having adequate training, experience, and abilities to perform the necessary testing. The minimum qualifications are either a recognized nationally accredited or certified Superpave testing certificate or been working in hot-mix asphalt testing for at least one year.
- **Quality Assurance (QA):** All those planned and systematic actions necessary to provide adequate confidence that a product or service will satisfy given requirements for quality.
- Quality Control (QC): The sum total of the activities performed by the Contractor in order to assure that the product meets contract requirements.
- Quality Control (QC) Plan: The detailed description of the type and frequency of inspection, sampling, and testing deemed necessary to measure and control the various properties governed by the Specifications. The QC Plan must address the actions needed to keep the process in control, detect when the process is going out of control, and responses to correct the situation(s).

- **Quality Level Analysis:** A statistical procedure that provides a method for estimating the percentage of each lot or sublot of material, product, item of construction, or completed construction that may be expected to be within specified tolerances.
- **Standard Deviation:** A term used in statistics to indicate the value calculated from the square root of the difference between the individual measurements in a group and their average. Standard deviation is calculated by taking the square root of the sum of the squares of the differences of each of n values and the mean value, this sum first divided by (n-1).
- **Target Value:** The acceptable value for a controlling characteristic of a product. The JMF will establish each of these values for the material.
- **Test Methods:** Shall be AASHTO test methods. Copies of these test methods shall be available at each qualified laboratory.
- Upper Quality Index (QU): The index reflecting the statistic related to the upper boundary to which a sample (or sample statistic) may deviate from the target value and still be considered acceptable.
- **Volumetric Properties:** Air voids, voids in mineral aggregates (VMA), voids filled with asphalt (VFA), and dust to effective asphalt.

#### .03 Equipment.

#### (a) Material Production Test Equipment.

The Contractor shall establish, maintain, and operate a qualified testing laboratory at the production plant site of sufficient size and layout that will accommodate the testing operations of both the Contractor and the Engineer. The Contractor shall maintain all the equipment used for handling, preparing, and testing materials in proper operating condition. For any laboratory equipment malfunction, the Contractor shall remedy the situation within one working day or the Engineer may reject production. In the case of an equipment malfunction, and while waiting for repairs to equipment, the Engineer may elect to test the material at either another production facility or the Engineer's laboratory to obtain payment factors.

The following shall be the minimum calibrations for the referenced equipment:

- SUPERPAVE<sup>R</sup> Gyratory Compactor: once every year; verified once every month by the Engineer.
- Ovens: once every three months, verified once every month.
- Vacuum Container and Gauge (Rice Bowls): once every three months, verified once every month.
- Balances and Scales: once every year, verified once every month.
- Thermometers: once a year; verified once every month.
- Gyratory Compactor molds and base plates: once every year
- Mechanical Shakers: once every year
- Sieve Verifications: once every year

All calibrations shall be documented and on file for review by the Engineer at any time.

#### (b) Pavement Construction Test Equipment.

The Contractor shall furnish and use in-place density gauges, or coring equipment, or both, as necessary to meet the requirements of these Specifications.

#### .04 Quality Control (QC) Plan.

#### (a) Material Production QC.

#### (1) Job Mix Formula – Material Production.

The Contractor shall submit for approval to the Engineer the job mix formula (JMF) design of the component materials and target characteristic values for each mixture proposed for use. Once the JMF is submitted to the Engineer, the Engineer will have up to three weeks to review the submitted information. However, a provision for a more timely approval is available to the Contractor; first, the Contractor shall submit the proper documentation on Pinepave mixture design software for the Engineer's approval. After that approval from the Engineer, the Contractor shall produce the new mixture for a non-Department project. The Engineer will test the material, by taking three series per the specifications. If the Engineer's test results are within the specifications, then the mixture will be approved by the Engineer for Department projects.

The component materials design shall include designating the source and the expected proportion (within 1 percent for the aggregate components, and within 0.1 percent for the other components) of each component to be used in order to produce workable hot-mix asphalt having the specified properties. For plant component feed adjustments, RAP can be considered in the same manner as an individual aggregate component. The JMF target characteristic values include the mixing temperature range, core temperature range for gyration, the percentage of the asphalt cement component (both total and virgin), and the percentages of the aggregate amounts retained on the sieves to be addressed by the JMF as shown in Table 1.

The Contractor shall provide an ignition oven correction number for each JMF. The Contractor shall also supply to the Engineer weighed material of each JMF so correction numbers can be established for the Engineer's equipment for Dispute Resolution samples.

Prior to starting production of a new mixture, the Contractor shall submit a JMF. For any mixture that has a 20% or greater failure rate on any combined volumetric criteria, the JMF will not be approved for use on Department contracts. In order to be approved, a re-design of the mixture will have to be completed by the Contractor for review and approval by the Engineer. The Contractor shall uniquely title each JMF. The Contractor shall submit test data with each JMF and tests performed by a Qualified Laboratory on representative materials, verifying the adequacy of the design. Refer to the specifications for each mix type in order to determine the design requirements. The JMF sieve percentage values shall conform to the ranges shown in Table 1.

If there is a change in the source of any of the component materials, other than asphalt, if there is a change in the proportions of the aggregate components or the percent passing for each sieve by more than 5 percent from the submitted JMF, or if there is a change in the percentage of the asphalt cement component by 0.2 percent or more, which causes the volumetrics to change from the originally submitted JMF, a new JMF is required. Also, if the asphalt cement target percentage is lowered, all volumetric criteria must still be achieved.

According to the Contractor's QC Plan, the Contractor shall inform the Engineer of any proposed changes to an existing JMF. The Contractor shall notify the Engineer by electronic mail of the proposed changes. The Engineer will reply to the proposed changes within one operational day and notify the Contractor of the effective date of the changes.

Although a new JMF is not required, the Contractor must notify the Engineer of any change in the proportions of the components. This notification shall include the total change made from the approved JMF proportions, and the effective time of the change.

All submitted JMF's shall correspond to the Pinepave mixture design software. The Engineer, for evaluation of the submitted JMF, will use the first three test samples. These test results acquired during production shall be within the following range compared to the submitted JMF on the Pinepave mixture design software:  $G_{mm}$ : + / -0.030 and  $G_{mb}$ : + / - 0.040

Table 1 - Aggregate Gradation - JMF and Control Point Information											
Sieves to be addressed by JMF/Range values are percentages passing by weight											
Sieve Size mm (inch)	4.75 mm	4.75mm Range	9.5 mm	9.5mm Range	12.5 mm	12.5mm Range	19.0 mm	19.0mm Range	25.0 mm	25.0mm Range	
37.5(1.5)	No		No		No		No		Yes	100	
25.0(1.0)	No		No		No		Yes	100	Yes	90-100	
19.0 (3/4)	No		No		Yes	100	Yes	90-100	Yes	20-90	
12.5(1/2)	Yes	100	Yes	100	Yes	90-100	Yes	23-90	Yes		
9.5 (3/8)	Yes	95-100	Yes	90-100	Yes	28-90	Yes		Yes		
4.75(#4)	Yes	90-100	Yes	32-90	Yes		Yes		Yes		
2.36(#8)	Yes		Yes	32-67	Yes	28-58	Yes	23-49	Yes	19-45	

Table 1 - Aggregate Gradation - JMF and Control Point Information											
Sieves to be addressed by JMF/Range values are percentages passing by weight											
Sieve Size mm (inch)	4.75 mm	4.75mm Range	9.5 mm	9.5mm Range	12.5 mm	12.5mm Range	19.0 mm	19.0mm Range	25.0 mm	25.0mm Range	
(#16)	Yes	30-60	Yes		Yes		Yes		Yes		
(#30)	Yes		Yes		Yes		Yes		Yes		
(#50)	Yes		Yes		Yes		Yes		Yes		
(#100)	Yes		Yes		Yes		Yes		Yes		
.075(#200)	Yes	6-12	Yes	2-10	Yes	2-10	Yes	2-8	Yes	1-7	

#### (2) Process Control - Material Production.

The Contractor shall submit in writing (letter or electronic mail) a QC Plan from each proposed production plant to the Engineer; no hot-mix asphalt material will be accepted until the Engineer approves the QC Plan. This plan must be submitted to the Engineer on an annual basis for review and approval prior to material production. The Engineer will send a signed copy back to the Contractor stating that it is approved. The approved QC Plan shall govern contractor operations.

The following are considered significant violations to the Contractor's QC Plan:

- Using testing equipment that is knowingly out of calibration or is not working properly.
- Reporting false information such as test data, JMF information, or any info requested by DelDOT
- When the Contractor fails to comply to their approved QC Plan in reference to materials testing
- Substantial deviations to AASHTO or DelDOT procedures when running tests, sampling stockpiles, or testing hot mix.
- The use of any material not listed in the JMF.
- The use of the wrong PG graded asphalt.
- If samples fall within the Contractors action points in the QC Plan but the Contractor fails to take the corrective action in the approved QC Plan

If a Contractor is found in violation of any of these items, they will receive a written warning for their first violation. If the Contractor is found in violation a second time on any of the criteria, they will forfeit any bonus from that day's production. If the Contractor is found in violation a third time on any of the criteria, they will receive a five percent (5%) deduction for that day's production. If the Contractor is found in violation a fourth time, the plant will not be approved for production until such time that the Contractor addresses the violation of the QC plan to the satisfaction of the Engineer. If the Engineer approves the changes in advance, the Contractor may make changes to the QC Plan. All changes shall be submitted and approved in writing by the Engineer.

The QC Plan shall include actions that will assure all materials and products will conform to the specifications, whether manufactured or processed by the Contractor, or procured from suppliers, subcontractors, or vendors. The Contractor shall perform the inspection and tests required to substantiate product conformance to contract requirements. The Contractor shall document QC inspections and tests, and provide copies to the Engineer when requested. The Contractor shall maintain records of all inspections and tests for at least one year. The records shall include the date, time, and nature of deficiency or deficiencies found; the quantities of material involved until the deficiency was corrected; and the date, time, and nature of corrective actions taken.

In the QC Plan, the Contractor shall detail the type and frequency of inspection, sampling, and testing deemed necessary to measure and control the various properties of material and construction governed by the Specifications. The QC Plan shall include the following elements as a minimum:

- Production Plant make, type, capacity, and location.
- Production Plant Calibration components and schedule; address documentation.
- Personnel include name and telephone number for the following individuals:
  - Person responsible for quality control.
  - Qualified technician(s) responsible for performing the inspection, sampling, and testing.
  - Person who has the authority to make corrective actions on behalf of the Contractor.
- Testing Laboratory state the frequency of accuracy checks and calibrations of the equipment used for testing; address documentation.
- Locations where samples will be obtained and the sampling techniques for each test
- Load number of QC samples (1-10 if QA sample is not within trucks 1-10)
- Tests to be performed and their normal frequency; the following, at a minimum, shall be conducted:
  - Mixture Temperature: each of the first five trucks, and each load that is sampled for QC or acceptance testing.
  - Gradation analysis of aggregate (and RAP) stockpiles one washed gradations per week for each aggregate stockpile; RAP: five gradations and asphalt cement contents for dedicated stockpiles where new material is not being added; one gradation and asphalt cement content test per week for stockpiles where material is continually being added to the stockpile.
  - Gradation analysis of non-payment sieves
  - Dust to effective asphalt calculation
  - Moisture content analysis of aggregates daily.
  - Gradation analysis of the combined aggregate cold feed one per year per mixture.
  - Bulk specific gravity and absorption of blended material one per year per mixture.
  - Ignition Oven calibration one per year per mixture.
  - Hot-Bins: one per year per mixture.
  - Others, as appropriate.
- Procedures for reporting the results of inspection and tests (include schedule).
- Procedures for dealing with non-compliant material or work.
- Presentation of control charts. The Contractor shall plot the results of testing on individual control charts for each characteristic. The control charts shall be updated within one working day as test results for each sublot become available. The control charts shall be easily and readily accessible at the plant laboratory. The following parameters shall be plotted from the testing:
  - Asphalt cement content.
  - Volumetrics (air voids, voids in mineral aggregates [VMA])
  - Gradation values for the following sieves:
    - 4.75 mm (#4).
    - 2.36 mm (#8).
    - 0.075 mm (#200).
- Operational guidelines (trigger points) to address times when the following actions would be considered:
  - Increased frequency of sampling and testing.
  - Plant control/settings/operations change.
  - JMF adjustment.
  - JMF change (See Section .04(a)(1)).
  - Change in the source of the component materials.
  - Calibration of material production equipment (asphalt pump, belt feeders, etc.).
  - Rejection of material.

When any point of non-compliance with the QC plan, or material not meeting the Specifications, comes to the attention of either the Contractor or the Engineer, the other party shall be notified immediately, and the Contractor shall take appropriate corrective actions. Failure to take corrective actions immediately shall be cause for rejection of material or work by the Engineer.

#### (b) Pavement Construction - Process Control.

The Contractor shall perform Quality Control of pavement compaction by testing in-place pavement with a density gauge or by testing cores extracted from the pavement. The use of the nuclear density gauge

shall conform to ASTM D2950; the use of other density gauges shall be as per the manufacturer's recommendations and approved by the Engineer. The Contractor may use any method to select locations for the Quality Control.

#### .05 Acceptance Plan.

#### (a) Material Production - Tests and Evaluations.

The Engineer will conduct acceptance tests. The Engineer will directly base acceptance on the acceptance test results, the asphalt cement quality, the Contractor's QC Plan work, and the comparisons of the acceptance test results to the QC test results. The Engineer may elect to utilize test results of the Contractor in some situations toward judging acceptance. All acceptance tests shall be performed by qualified technicians at qualified laboratories following AASHTO or DelDOT procedures, and shall be evaluated using Quality Level Analysis.

The Contractor shall supply, capture, and mark samples, as directed, from delivery trucks before the trucks leave the production plant. The sample shall represent the material produced by the Contractor, and shall be of sufficient size to allow the Engineer to complete all required acceptance tests. The Engineer will direct the Contractor when to capture these samples, on a statistically random, unbiased basis, established before production begins each day based upon the anticipated production tonnage. The captured sample shall be from the Engineer specified delivery truck; if the Contractor visually observes the specified delivery truck sample and does not want this sample to be sampled and tested for acceptance, that delivery truck will not be sent to a Department project. The next visually acceptable delivery truck to the Contractor shall be sampled for acceptance testing.

The first sample of the production day will be randomly generated by the Engineer between loads 0 and 12 (0-250 tons). Subsequent samples will be randomly generated by the Engineer on 500-ton sub-lots for the production day. Unacceptable samples may be a basis for rejection of material if the QC plan is not followed as approved for sample retrieval. If the Contractor wishes to perform parallel tests with the Engineer, or to capture samples to be retained for possible Dispute Resolution, each of the samples for these purposes shall be obtained at the same time and location as the acceptance test sample. Either splitting a large sample or getting multiple samples that equally represent the material is acceptable. The Engineer will perform all splitting and handling of samples after they are obtained by the Contractor.

The Engineer will evaluate and accept the material on a lot basis. All the material within a lot shall have the same JMF (mixture ID). The lot size shall be targeted for 2000 tons or a maximum period of three days, whichever is reached first. If the 2000<sup>th</sup> ton target lot size is achieved during a production day, the lot size shall extend to the end of that production day. The Contractor may interrupt the production of one JMF in order to produce different material; this type of interruption will not alter the determination of the size or limits of material represented by a lot. The Engineer will evaluate each lot on a sublot basis. The size for each sublot shall be 100 to 500 tons and testing for the sub lots will be completed on a daily basis. For each sublot, the Engineer will evaluate one sample.

The target size of sub-lots within each lot, except for the first sample of the production day, is equal-sized 500 ton sub lots and will be based upon anticipated production, however, more or fewer sublots, with differing sizes, may result due to the production schedule and conditions. If the actual production is less than anticipated, and it's determined a sample will not be obtained (based upon the anticipated tonnage), a new sample location will be determined on a statistically random, unbiased basis based upon the new actual production. If the actual production is going to be 50 tons or greater over the anticipated sub lot production, a new sample location will be determined on a statistically random, unbiased basis based upon the new actual production. The Engineer will combine the evaluation and test results for all of the applicable sublots in order to evaluate each individual lot.

If the Engineer is present, and the quantity exceeds 25 tons, a statistically random sample will be used for analysis. When the anticipated production is less than 100 tons and greater than 25 tons, and the Engineer is not present, the contractor shall randomly select a sample using the Engineer's random location program. The captured sample shall be placed in a suitable box, marked to the attention of the Engineer, and submitted to the Engineer for testing. A box sample shall also be obtained by the contractor at the same time and will be used as the Dispute Resolution sample if requested by the Engineer. The contractor shall also obtain one liquid asphalt sample (1 pint) per grade of asphalt used per day and properly label it with all pertinent information.

The Engineer will conduct the following tests in order to characterize the material for the pavement compaction quality, and to judge acceptance and the pay adjustment for the material:

- AASHTO T312 Preparing a mixture samples using a gyratory compactor.
- AASHTO T166, Method C (Rapid Method) Bulk specific gravity of compacted samples.
- AASHTO T308 Asphalt cement content.
- AASHTO T30 Aggregate gradations, using samples from the asphalt cement content test.
- AASHTO T209 Theoretical maximum specific gravity.
- ASTM Provisional Test Method Rapid Drying of Compacted and Loose Bituminous Asphalt Specimens using Vacuum Drying Method

#### (b) Pavement Construction – Tests and Evaluations.

The Engineer will directly base acceptance on the compaction acceptance test results, and on the inspection of the construction, the Contractor's QC Plan work, ride smoothness as referenced in the contract documents, lift thickness as referenced in the contract documents, joint quality as referenced in the contract documents, surface texture as referenced in the contract documents, and possibly the comparisons of the acceptance test results to the independent test results. For the compaction acceptance testing, the Engineer will sample the work on a statistically random basis, and will test and evaluate the work using lots.

Prior to paving a road segment, the Contractor shall notify the Engineer of any locations within that road segment that may not be suitable to achieve minimum (93%) compaction due to existing conditions. The Contractor shall schedule and hold a meeting in the field with the Engineer in order to discuss all areas that may potentially be applicable to Table 5a before paving starts. Areas that will be considered for Table 5a will be investigated in accordance to the method described in Appendix B. If this meeting is not held prior to paving, no areas will be considered for Table 5a. Areas of allowable exemptions that will not be cored include the following: partial-depth patch areas, driveway entrances, paving locations of less than 100 tons, areas around manholes and driveway entrances, and areas of paving that are under 400 feet in continuous total length and/or 5 feet in width.

The exempt areas around manholes will be a maximum of 4 feet transversely on either side from the center of the manhole, and 20 feet longitudinally on either side from the center of the manhole. The exempt areas around driveway entrances shall be the entire width of the driveway, and 3 feet from the edge of the longitudinal joint next to the driveway. Areas of exemption that will be cored for informational purposes only shall include: areas where the mat thickness is less than three times the nominal maximum aggregate size as directed by the Engineer, violations of Section 401.08 in the Standard Specifications as directed by the Engineer, and areas shown to contain questionable subgrade properties as proven by substantial yielding under a fully legally loaded truck. Failure to obtain core samples in these areas will result in zero payment for compaction regardless of the exempt status.

The Engineer will evaluate and accept the compaction work on a daily basis. Payment for the compaction will be calculated by using the material production lots as referenced in .05 Acceptance Plan (a) Material Production – Tests and Evaluation and analyzing the compaction results over the individual days covered in the material production lot. The compaction results will be combined with the material results to obtain a payment for this item.

The minimum size of a compaction lot shall be 100 tons. If the compaction lot is between 101 and 1000 tons, the Engineer shall randomly determine four compaction acceptance test locations. If the compaction lot is between 1001 and 1500 tons, the Engineer shall randomly determine six compaction acceptance test locations. If the compaction lot is between 1501 and 2000 tons, the Engineer shall randomly determine eight compaction acceptance test locations. If the compaction lot is greater than 2000 tons, the Engineer shall randomly determine two compaction acceptance test locations per 500 tons.

If a randomly selected area falls within an Engineer approved exemption area, the Engineer will select one more randomly generated location to be tested per the requirements of this Specification. If that cannot be accomplished, or if an entire location has been declared exempt, the compaction testing shall be performed as per these Specifications but a note will be added to the results that the location was an Engineer approved exempt location.

Testing locations will be a minimum of 1.5 feet from the newly placed longitudinal joint and 50 feet from a new transverse joint. If the Contractor chooses to cut companion cores, they shall be located within

one foot of the Engineers cores along the longitudinal direction and in-line with the Engineers cores in the longitudinal plane.

Exactly at the locations marked by the Engineer, the Contractor shall cut a core, 6 inches in diameter, through the full lift depth. Cores submitted that are not from the location designated by the Engineer will not be tested and will be paid at zero pay.

The Contractor shall notify the Engineer prior to starting paving operations with approximations of the tonnage to be placed. The Contractor is then responsible for notifying the appropriate Engineer test personnel within 12 hours of material placement. The Engineer will then have 24 hours to mark the core locations. After determination of locations, the Contractor shall complete testing within two operational days of the locations being marked. If the cores are not cut within two operational days, the area in question will be paid at zero pay for compaction testing.

The Contractor shall provide any traffic control required for the structural number investigation, sampling, and testing work at no additional cost to the Department.

The Contractor shall cut each core with care in order to prevent damaging the core. The pavement shall have a maximum temperature of 140°F when cores are cut from it. Immediately upon removal of a core from the roadway, the Contractor shall adequately label it. The Contractor shall protect the core by supplying a 6-inch plastic concrete cylinder mold, or an approved substitute, and placing the core in it. If more than one core is in the same mold, the Contractor shall place paper between them. The Contractor shall attach a completed QC test record for the representative area to the corresponding core. The Engineer will also complete a test record for areas tested for the QA report and provide to Materials & Research. At the end of every production day, the Contractor shall deliver the cores to the Engineer for testing, processing, and report distribution.

The Contractor shall repair the core hole per Appendix A, Repairing Core Holes in Hot-Mix Asphalt Pavements. Core holes shall be filled immediately. Failure to repair core holes at the time of coring will result in zero pay for compaction testing for the area in question.

The Engineer will conduct the following tests on the applicable portion of the cores in order to evaluate their quality:

- AASHTO T166, Method C (Rapid Method) to determine the bulk specific gravity of the cores.
- AASHTO T209 to calculate the theoretical maximum specific gravity and the density of the non-compacted mixtures.
- ASTM Provisional Test Method Rapid Drying of Compacted and Loose Bituminous Asphalt Specimens using Vacuum Drying Method.

The Engineer will use the average of the last five test values of the same JMF (mixture ID) material at the production plant in order to calculate the average theoretical maximum specific gravity of the cores. The average will be based on the production days test results and as many test results needed from previous days production to have an average of five samples. If there are less than five values available, the Engineer will use the JMF design value in addition to the available values to calculate the average theoretical maximum specific gravity.

#### .06 Payment and Pay Adjustment Factors.

The Contractor shall include the costs for all materials, labor, equipment, tools, and incidentals necessary to meet the requirements of this specification in the bid price per ton for the hot-mix asphalt. Payment to the Contractor for the hot-mix asphalt item(s) will be based on the Contract price per ton and the pay adjustments described in this specification. The Engineer will determine pay adjustments for the hot-mix asphalt item(s) based on the Acceptance Plan. The Engineer will determine both a pay adjustment for the material and a pay adjustment for the pavement construction. Note that the material portion of the total pay adjustment is 70 percent and the pavement construction portion is 30 percent. For replaced material or work, the Engineer will not apply the Pay Adjustment applicable to the material or work replaced; a new Pay Adjustment will be calculated based on the qualities of the new material. Even if one portion of the pay

adjustment (material or construction) is not applied, the Engineer may apply the pay adjustment to the other portion. All adjustments (bonus or penalty) shall be paid under this item number in the contract.

# (a) Material Production - Pay Adjustment.

The Engineer will determine the material pay adjustment by evaluating the production material based on the following parameters:

- Gradation of the 2.36 mm (#8) sieve.
- Gradation of the 0.075 mm (#200) sieve.
- Asphalt cement content.
- Air void content

Using the JMF target value, the single test tolerance (from Table 3), and the test values, the Engineer will use the following steps to determine the material pay adjustment factor for each lot of material:

- 1. For each parameter, calculate the mean value and the standard deviation of the test values for the lot to the nearest 0.1 unit.
- 2. For each parameter, calculate the Upper Quality Index (QU): QU = ((JMF target) + (single test tolerance) (mean value)) / (standard deviation).
- 3. For each parameter, calculate the Lower Quality Index (QL):
  QL = ((mean value) (JMF target) + (single test tolerance)) / (standard deviation).
- 4. For each parameter, locate the values for the Upper Payment Limit (PU) and the Lower Payment Limit (PL) from Table 2 Quality Level Analysis by the Standard Deviation Method. (Use the column for "n" representing the number of sublots in the lot. Use the closest value on the table when the exact value is not listed).
- 5. Calculate the PWL for each parameter from the values located in the previous step: PWL = PU + PL 100.
- 6. Calculate each parameter's contribution to the payment adjustment by multiplying its PWL by the weight factor shown in Table 3 for that parameter.
- 7. Add the calculated adjustments of all the parameters together to determine the Composite PWL for the lot.
- 8. From Table 4, locate the value of the Pay Adjustment Factor corresponding to the calculated PWL.
- 9. For each lot, determine the final material price adjustment:

# Final Pay Adjustment =

(Lot Quantity) x (Item Bid Price) x (Pay Adjustment Factor) x 70%. This final pay calculation will be paid to the tenth of a percent.

In lieu of being assessed a pay adjustment penalty, the Contractor may choose to remove and replace the material at no additional cost to the Department. If the PWL of any single material characteristic is below 60, the Engineer may require the removal and replacement of the material at no additional cost to the Department.

The test results from the Engineer on production that is less than 100 tons will be combined with the two most recently completed Engineer tests with the same Mixture ID to calculate payment for the lot encompassing the single test. If that cannot be accomplished, the approved JMF will be used to calculate payment for the lot encompassing the single test. Payment for previously closed lots will not be affected by the analysis.

When a sample is out of the acceptable tolerance for any Materials pay criteria, that sample will be isolated. For payment purposes, the test result of the out of acceptable tolerance sample will be combined with the two previous acceptable samples of the same JMF and analyzed per this specification. The material that is considered out of the acceptable tolerance will only include the material within the represented sub-lot (i.e., a maximum of 500 tons). If the previous acceptable test result is from the previous production day, only the material produced on the second production day will be considered out of tolerance. All future sub lots will not include the isolated test.

If, during production, a QA sample test result does not meet the acceptable tolerances and the Contractors QC sample duplicates the QA sample test result, the Contractor can make an appropriate change

to the mixture (within the JMF boundaries), and request to have that sample further isolated. If this request is approved, and the Contractor has made a change, the third load after the change will be tested. If that sample test result shows compliance with the specifications, the material that is considered out of the acceptable tolerance will include the material from the previous acceptable test result to the third load after the initially sampled and tested sample. If the sample does not meet the specification requirements, the Engineer will no longer accept material. Production may resume when changes have been made and an acceptable sample and test result is obtained.

Table 2 – Quality Level Analysis by the Standard Deviation Method							
DII DI		Q	U and QL	for "n"	Samples		
PU or PL	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9
100	1.16	1.50	1.79	2.03	2.23	2.39	2.53
99		1.47	1.67	1.80	1.89	1.95	2.00
98	1.15	1.44	1.60	1.70	1.76	1.81	1.84
97		1.41	1.54	1.62	1.67	1.70	1.72
96	1.14	1.38	1.49	1.55	1.59	1.61	1.63
95		1.35	1.44	1.49	1.52	1.54	1.55
94	1.13	1.32	1.39	1.43	1.46	1.47	1.48
93		1.29	1.35	1.38	1.40	1.41	1.42
92	1.12	1.26	1.31	1.33	1.35	1.36	1.36
91	1.11	1.23	1.27	1.29	1.30	1.30	1.31
90	1.10	1.20	1.23	1.24	1.25	1.25	1.26
89	1.09	1.17	1.19	1.20	1.20	1.21	1.21
88	1.07	1.14	1.15	1.16	1.16	1.16	1.17
87	1.06	1.11	1.12	1.12	1.12	1.12	1.12
86	1.04	1.08	1.08	1.08	1.08	1.08	1.08
85	1.03	1.05	1.05	1.04	1.04	1.04	1.04
84	1.01	1.02	1.01	1.01	1.00	1.00	1.00
83	1.00	0.99	0.98	0.97	0.97	0.96	0.96
82	0.97	0.96	0.95	0.94	0.93	0.93	0.93
81	0.96	0.93	0.91	0.90	0.90	0.89	0.89
80	0.93	0.90	0.88	0.87	0.86	0.86	0.86
79	0.91	0.87	0.85	0.84	0.83	0.82	0.82
78	0.89	0.84	0.82	0.80	0.80	0.79	0.79
77	0.87	0.81	0.78	0.77	0.76	0.76	0.76
76	0.84	0.78	0.75	0.74	0.73	0.73	0.72
75	0.82	0.75	0.72	0.71	0.70	0.70	0.69
74	0.79	0.72	0.69	0.68	0.67	0.66	0.66
73	0.75	0.69	0.66	0.65	0.64	0.63	0.63
72	0.74	0.66	0.63	0.62	0.61	0.60	0.60

Contract No. T201106304.01

Tab	Table 2 – Quality Level Analysis by the Standard Deviation Method						
PU or PL		QU and QL for "n" Samples					
FUOTEL	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9
71	0.71	0.63	0.60	0.59	0.58	0.57	0.57
70	0.68	0.60	0.57	0.56	0.55	0.55	0.54
69	0.65	0.57	0.54	0.53	0.52	0.52	0.51
68	0.62	0.54	0.51	0.50	0.49	0.49	0.48
67	0.59	0.51	0.47	0.47	0.46	0.46	0.46
66	0.56	0.48	0.45	0.44	0.44	0.43	0.43
65	0.52	0.45	0.43	0.41	0.41	0.40	0.40
64	0.49	0.42	0.40	0.39	0.38	0.38	0.37
63	0.46	0.39	0.37	0.36	0.35	0.35	0.35
62	0.43	0.36	0.34	0.33	0.32	0.32	0.32
61	0.39	0.33	0.31	0.30	0.30	0.29	0.29
60	0.36	0.30	0.28	0.27	0.27	0.27	0.26
59	0.32	0.27	0.25	0.25	0.24	0.24	0.24

Table 3 - Material Parameter Weight Factors					
Material Parameter Single Test Tolerance (+/-) Weight Factor					
Asphalt Content	0.4	0.30			
#8 Sive (19 mm or >)	7.0	0.30			
#8 Sieve (12.5 mm or <)	5.0	0.30			
#200 Sieve (0.075 mm) Sieve	2.0	0.30			
Air Voids (4.0% Target)	1.5	0.10			

Table 4 - PWL Pay Adjustment Factors			
PWL	Pay Adjustment Factor (%)		
100	+5		
<100	(PWL - 100)		

# (b) Pavement Construction - Pay Adjustments.

The Engineer will determine the pavement construction pay adjustment by evaluating the construction of the pavement, based on the following parameter:

# • Degree of compaction of the in-place material

Using the test values for the cores, the Engineer will use the following steps to determine the pavement construction pay adjustment for each lot of work. Note that the material portion of the total pay adjustment is 70 percent and the pavement construction portion is 30 percent.

- 1. Calculate the average density values from the sublot tests values, to the nearest 0.1 unit.
- 2. Calculate the Degree of Compaction:
  Degree of Compaction =
  - ((Core Bulk Specific Gravity) / (Theoretical Maximum Specific Gravity)) x 100%.
- 3. The average compaction for the sublots shall be averaged together for the compaction level of the lot. The lots compaction test level shall be averaged to the whole percent.
- 4. Locate the value of the Payment Adjustment Factor corresponding to the calculated degree of compaction from Table 5 or Table 5a.
- 5. Determine the pavement construction price adjustment by using the following formula: Pay adjustment = (Lot Quantity) x (Bid Price) x (Pay Adjustment Factor) x 30%.

Table 5: Compaction Price Adjustment Highway Locations			
Degree of Compaction (%)	Pay Adjustment Factor (%)		
>97	-100*		
96	-3		
95	0		
94	0		
93	+5		
92	0		
91	-15		
90	-25		
89	-30		
<u>&lt;</u> 88	-100*		

<sup>\*</sup> or remove and replace it at Engineer's discretion

Table 5a: Compaction Price Adjustment Other <sup>1</sup> Locations			
Degree of Compaction (%)	Pay Adjustment Factor (%)		
>96	-100*		
95	-2		
94	0		
93	+3		
92	0		
91	0		
90	0		
89	-1		
88	-5		
87	-15		
86	-25		
85	-30		
84	-100*		

<sup>\*</sup> or remove and replace at Engineer's discretion

This chart is to be used for areas where the structural value of the area to be paved is less than 1.75 as determined by the Engineer. See Appendix B – Method for Obtaining Cores for

Determination of Roadway Structure. This chart is applicable to rehabilitation work only; full depth construction will not be considered for Table 5a.

# .07 Dispute Resolution.

Disputes or questions about any test result shall be immediately brought to the attention of the Contractor and the Engineer. When there is a significant alleged discrepancy regarding the Engineer's acceptance test results, the Contractor must claim a dispute within two operational days of the test date. The following dispute resolution procedures will be used.

The Engineer and the Contractor will review the sample quality, the test method, the laboratory equipment, and the laboratory technician. If these factors are not the cause of the dispute, a third party dispute resolution will be used.

For third party resolution testing, it can be either at another Contractor's laboratory, the Engineer's laboratory, or an independent accredited laboratory. Unless otherwise mutually agreed upon by DAPA and the Engineer, the Engineer's qualified laboratory in Dover and qualified personnel shall conduct the necessary testing for third party Dispute Resolution after the Engineer has provided reasonable notice to allow the Contractor to witness this testing.

When disputes over production testing occur, the samples used for Dispute Resolution testing will be those samples the Contractor properly captured, labeled, and stored, as described in the second paragraph of the section of these specifications titled .05 Acceptance Plan, (a) Material Production – Tests and Evaluations. If no samples are available, the original testing results will be used for payment calculations.

Dispute Resolution samples for air void content will be heated by a microwave oven.

If there is a discrepancy between the Engineer's acceptance test result and the Contractor's test result, the Contractor may ask for the Dispute Resolution sample to be tested. If the Dispute Resolution sample substantiates the original acceptance test result, the Contractor, after two such Dispute Resolution samples, will be charged a fee of \$125 for all further Dispute Resolution cores that substantiate the acceptance test result. If the Dispute Resolution sample substantiates the Contractor's test result, the Contractor will not be charged a fee.

When disputes over compaction core test results occur, the Engineer's acceptance core will be used for the dispute resolution sample. The Contractor will be advised on when the testing will occur as referenced above to witness the testing.

The results of the dispute resolution testing shall replace all of the applicable disputed test results for payment purposes.

5/26/11

# Appendix A - Repairing Core Holes in Hot-Mix Asphalt Pavement

# Description.

This appendix describes the procedure required to acceptably repair core holes in a bituminous concrete pavement.

# Materials and Equipment.

The following material shall be available to complete this work:

• Patch Material –A DelDOT approved High Performance Cold Patch material shall be used.

The following equipment shall be available to complete this work:

- Sponge or other absorbent material Used to extract water from the hole.
- Compaction Hammer Shall be mechanical, with a flat, circular tamping face smaller than 6 inches in diameter. The tamping head shall be connected to an electrical, pneumatic, or gasoline driven tamping device.

#### **Construction Method.**

After core removal from the hole, remove all excess water from within the hole, and prevent water from re-entering the hole.

Place the patch material in lifts no greater than 3 inches. If the hole is deeper than 3 inches, use two lifts of approximately equal depths so that optimum compaction is achieved. Make sure that the patch surface matches the grade of the existing roadway. Make every effort to achieve the greatest possible compaction

# Performance Requirements.

The Engineer will judge the patch on the following basis:

- The patch shall be well compacted
- The patch surface shall match the grade of the surrounding roadway surface.

# **Basis of Payment.**

No measurement or payment will be made for the patching work. The Contractor must gain the Engineer's acceptance of the patching work before the Engineer will accept the material represented by the core.

#### Appendix B - Method for Obtaining Cores for Determination of Roadway Structure

The Contractor is responsible for obtaining cores in areas that they propose are eligible for compaction price adjustments according to Table 5a in this specification. Table 5a is not applicable for new full-depth pavement box construction. Cores submitted for this process shall be obtained according to the following process.

- 1. Contact Materials & Research (M&R) personnel to determine if information about the area is already available. If M&R has already obtained cores in the location that is being investigated, the contractor may opt to use the laboratory information for the investigation and not core the area on their own.
- 2. If M&R does not have information concerning the section of the roadway, the contractor needs to contact M&R to arrange for verification of coring operations. Arrangements shall be made to allow for an individual from M&R to be on the site when the cores are obtained. Cores will be turned over to M&R for evaluation.
- 3. The contractor is responsible for providing all traffic control and repairing core holes in accordance to 401699 Appendix A Repairing Core Holes in Hot-Mix Asphalt Pavements.
- 4. Cores are to be taken throughout the entire project for the area in question. Cores will be spaced, from the start of the project in increments determined based on field and project specifics. Cores will be evenly distributed throughout the project location. The cores will be taken in the center of the lane in question.
- 5. Additional cores may be taken at other locations, if surface conditions indicate that there may be a substantial difference in the underlying section. The location of these cores should be documented and submitted to M&R.
- 6. Cores shall be full depth and include underlying materials. If there is a stone base included in the pavement section, at a minimum 1 core must have information concerning the thickness of the base. This is determined by augering to the subgrade surface.
- 7. The calculations used to determine the structural capacity of the roadway is as follows. If the contractor finds, upon starting the coring process, that the areas are of greater thickness than applicable to Table 5a, they may terminate the coring process on their own and retract the request.

#### **Structural Number Calculations**

Each pavement box material is assigned a structural coefficient based upon AASHTO design guides. The structural coefficient is used to determine the total strength of the pavement section.

Materials used in older pavement sections are assigned lower structural coefficients to compensate for aging of the materials. The coefficients used to determine the structural number of an existing pavement are:

Existing Material	Structural Coefficient
HMA	0.32
Asphalt Treated Base	0.26
Soil Cement	0.16
Surface Treatment (Tar & Chip)	0.10
GABC	0.14
Concrete	0 - 0.7*

The Structural Coefficient of Concrete is dependent upon the condition of the concrete. Compressive strengths & ASR analysis are used to determine condition – contact the Engineer if this situation arises.

Newly placed materials use a different set of structural coefficients. They are as follows:

New Material	Structural Coefficient
HMA	0.40
Asphalt Treated Base (BCBC)	0.32
Soil Cement	0.20
GABC	0.14

# **Example:**

Location includes placement of a 1.25" Type C overlay on 2.25" Type B. Existing roadway is cored and is shown to consist of 2" HMA on 7" GABC.

# Calculation:

For the Type B lift the calculation would be:

Existing HMA	2 * 0.32	=	0.64
GABC	7 * 0.14	=	0.98
			1.62

For the Type C lift the calculation would be:

Newly Placed B	2.25 * 0.4	=	0.90
Existing HMA	2 * 0.32	=	0.64
GABC	7 * 0.14	=	0.98
			2.52

# **401713 - EMULSIFIED ASPHALT**

# **Description:**

This item shall be used with item 401636 - COLD RECYCLED BITUMINOUS PAVEMENT or 304508 - BITUMINOUS STABILIZED FULL-DEPTH RECLAMATION.

#### **Materials:**

Recycling agents, such as CSS 1h emulsion, will be accepted under certification from the Contractor. All recycling agents delivered shall be sampled in the presence of the Engineer. The contractor shall place a representative sample in a clean plastic container, note the date of sample, load number, and gallons verified. The sample shall be provided to the Engineer for testing.

# **Method of Measurement and Basis of Payment:**

Measurement and Payment will be at the contract unit price per gallon of emulsified asphalt used and will be verified by the Engineer by delivery tickets and/or metering devices on the equipment. Each day, prior to the start of work, and at the end of the workday, all quantities will be verified, in writing, with the Engineer.

6/3/11

# 401752 - SAFETY EDGE FOR ROADWAY PAVEMENT

# **Description:**

This work consists of the construction of safety edge(s) along bituminous concrete pavement or P.C.C. pavement in accordance with the details and notes on the Plans and as directed by the Engineer.

# **Construction Methods:**

The safety edge shall not be constructed adjacent to curb or in front of guardrail sections.

In bituminous concrete pavement sections, prior to the construction of the safety edge, the fill or in situ material at the edge of pavement shall be compacted so that it is level with the top of the pavement, prior to the final surface overlay.

In bituminous concrete pavement sections, the contractor shall attach a device to the screed of the paver unit that confines the material at the end of the gate and extrudes the asphalt material in such a way that results in a compacted wedge shape pavement edge of 32 degrees (+/- 2 degrees). Contact shall be maintained between the device and the road shoulder surface. The device shall be manufactured so that it can be easily adjusted to transition at cross roads, driveways and obstructions without stopping the paver unit. The device's shape shall constrain the asphalt and cause compaction, as well as increase the density of the extruded profile.

In bituminous concrete pavement sections, the Transtech Shoulder Wedge Maker, Advant-Edge or an approved equal shall be used to produce the safety edge. Contact information for these wedge shape compaction devices is listed below:

Transtech Systems, Inc. 1594 State Street Schenectady, NY 12304 1-800-724-6306 www.transtechsys.com

or

Advant-Edge Paving Equipment, LLC 33 Old Niskayuna Road Loudonville, NY 12211 1-814-422-3343 www.advantedgepaving.com

or an approved equal.

In P.C.C. pavement sections, the paver screed shall be modified to provide a chamfer at the end of the P.C.C. pavement in accordance with the details and notes on the Plans, or as directed by the Engineer.

#### **Method of Measurement:**

Safety Edge will not be measured for payment.

#### **Basis of Payment:**

The cost associated with the construction of safety edge(s), including but not limited to the wedge device, preparation and compaction of the fill or in situ material, and placement of the safety edge in accordance with the Plans and Details shall be incidental to the bituminous concrete pavement or P.C.C. pavement item being placed.

1/21/2011

- 401800 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 64-22 (CARBONATE STONE)
- 401801 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)
- 401802 WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 64-22 (CARBONATE STONE)
- 401803 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 70-22 (CARBONATE STONE)
- 401804 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 70-22 (CARBONATE STONE) 401805 – WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 70-22 (CARBONATE STONE)
- 401806 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 76-22 (CARBONATE STONE)
- 401807 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22 (CARBONATE STONE)
- 401808 WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 76-22 (CARBONATE STONE)

  - 401809 WMA, SUPERPAVE, TYPE B, 115 GYRATIONS, PG 64-22 401810 WMA, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22 401811 WMA, SUPERPAVE, TYPE B, 205 GYRATIONS, PG 64-22
  - 401812 WMA, SUPERPAVE, TYPE B, 115 GYRATIONS, PG 70-22
  - 401813 WMA, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 70-22
  - 401814 WMA, SUPERPAVE, TYPE B, 205 GYRATIONS, PG 70-22
  - 401815 WMA, SUPERPAVE, TYPE B, 115 GYRATIONS, PG 76-22
  - 401816 WMA, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 76-22
  - 401817 WMA, SUPERPAVE, TYPE B, 205 GYRATIONS, PG 76-22
- 401818 WMA, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 115 GYRATIONS. PG 64-22
- 401819 WMA, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22
- 401820 WMA, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 205 GYRATIONS, PG 64-22
- 401821 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22, PATCHING 401822 – WMA, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22, PATCHING 401823 - WMA, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG-64-22, PATCHING
  - 401824 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG-64-22, WEDGE 401825 - WMA, SUPERPAVE, TYPE B, 160 GYRATIONS, PG-64-22, WEDGE
  - 401826 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
  - 401827 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
  - 401828 WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
  - 401829 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
  - 401830 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
  - 401831 WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
  - 401832 WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)
  - 401833 WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)
  - 401834 WMA, SUPERPAVE, TYPE C, 205 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)

- 401835 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 64-22 (CARBONATE STONE)
- 401836 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (CARBONATE STONE)
- 401837 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 70-22 (CARBONATE STONE)
- 401838 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 70-22 (CARBONATE STONE)
- 401839 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 76-22 (CARBONATE STONE)
- 401840 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22 (CARBONATE STONE)
  - 401841 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
  - 401842 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22, (NON-CARBONATE STONE)
  - 401843 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
  - 401844 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 70-22, (NON-CARBONATE STONE)
  - 401845 THIN WMA, SUPERPAVE, TYPE C, 115 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)
  - <u>401846 THIN WMA, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)</u>

# **Description:**

Warm mix asphalt (WMA) is the generic term used to describe the reduction in production, paving, and compaction temperatures achieved through the application of one or more of several WMA technologies.

The following Subsections of the Standard Specifications shall be applicable: 401.01, 401.03 - 401.10, 401.12, and 401.13. All other subsections have been modified herein.

The Contractor shall read and thoroughly understand the requirements of the QA/QC specification as defined in item 401699. It is the responsibility of the Contractor to determine all costs associated with meeting these requirements and to include them in the per ton bids for the various Superpave bituminous concrete items. The Contractor shall also be aware that the pay adjustment factors in item 401699 will be applied to the Superpave bituminous concrete payments to determine the bonus or penalty for the item.

#### **Materials:**

WMA may be produced by one or a combination of several technologies involving plant foaming processes and equipment, mineral additives, or chemicals that allow the reduction of mix production temperatures to within 185°F to 275°F.

Materials for hot-mix, hot-laid bituminous concrete shall conform to the requirements of Subsections 823.01, 823.05-823.17, and 823.25 - 823.28 of the Standard Specifications and the following.

# **Asphalt Binder:**

The asphalt binder shall meet the requirements of Superpave PG 64-22, PG 70-22, or PG 76-22 performance grade asphalt, as referenced in the Plans, according to M-320, Table 1 and tested according to AASHTO PP6 with the following test ranges:

TEST PROCEDURE	AASHTO REFERENCE	SPECIFICATION LIMITS
Temperature, °C	M-320	Per Grade
Original DSR, G*/sin (δ)	T-315	1.00 - 2.00 kPa
RTFO DSR, G*/sin (δ)	T-315	2.20 - 5.00 kPa
PAV DSR, G*/sin (δ)	T-315	1400 - 5000 kPa
BBR Creep Stiffness	T-313	90.0 - 300.0 kPa
BBR — value	T-313	0.300 - 0.440

Substitution of a higher temperature grade will require prior approval by the Engineer.

# **Recycled Materials:**

The percentage allowance of recycled materials (recycled asphalt pavement and/or shingles) shall be controlled through the use of the Materials & Research recycled mixture program available through the Materials & Research Section. The program can be used by the Contractor to determine which materials and combinations of materials can be used to meet the specified material on the contract.

If the Contractor proposes to use a combination of materials that are not covered by this program, the mix design shall be submitted and reviewed by the Engineer.

# **Mineral Aggregate:**

The mineral aggregate employed in the target gradation of the job mix formula (JMF) shall conform to Section 805 and the following criteria. These criteria apply to the combined aggregate blend.

DESIGN ESAL'S	COARSE AGGREGATE ANGULARITY <sup>1</sup> (% MIN)		FINE AGGREGATE ANGULARITY <sup>2</sup> (% MIN)		CLAY CONTENT <sup>3</sup>	FLAT AND ELONGATED <sup>4</sup>
(MILLIONS)	≤ 100 MM	> 100 MM	≤ 100 MM	> 100 MM	(% - MIN)	(% - MAX)
< 0.3	55/-	-/-	-	-	40	-
0.3 to < 3	75/-	50/-	40	40	40	
3 to <10	85/80 <sup>5</sup>	60/-	45	40	45	
10 < 30	95/90	80/75	45	40	45	10
≥30	100/100	100/100	45	45	50	

<sup>&</sup>lt;sup>1</sup>Coarse Aggregate Angularity is tested according to ASTM D5821.

The following source properties apply to the individual aggregates in the aggregate blend for the proposed JMF.

TEST METHOD	SPECIFICATION LIMITS
Toughness, AASHTO T96 Percent Loss, Maximum	40

<sup>&</sup>lt;sup>2</sup>Fine Aggregate Angularity is tested according to AASHTO TP-33.

<sup>&</sup>lt;sup>3</sup>Clay Content is tested according to AASHTO T176.

<sup>&</sup>lt;sup>4</sup>Flat and Elongated is tested according to ASTM 4791 with a 5:1 aspect ratio.

<sup>&</sup>lt;sup>5</sup> 85/80 denotes that 85% of the coarse aggregate has one fractured face and 80% has two or more fractured faces.

TEST METHOD	SPECIFICATION LIMITS
Soundness, AASHTO T104 Percent Loss, Maximum for five cycles	20
Deleterious Materials, AASHTO T112 Percent, Maximum	10
Moisture Sensitivity, AASHTO T283 Percent, Minimum	80

For any roadway with a minimum average daily traffic volume (ADT) of 8000 vehicles and a posted speed of 35 mph (60 kph) or greater, the polish value of the composite aggregate blend shall be greater than 8.0 when tested according to Maryland State Highway Administration MSMT 411 – "Laboratory Method of Predicting Frictional Resistance of Polished Aggregates and Pavement Surfaces." RAP shall be assigned a value of 4.0. The Contractor shall supply all polish values to the Engineer upon request.

# **Mineral Filler:**

The mineral filler shall conform to AASHTO M17.

#### **Mixture Requirements:**

**Mix Design.** Develop and submit a job mix formula for each mixture according to AASHTO R35. Each mix design shall be capable of being produced, placed, and compacted as specified. Apply all mix design requirements for Superpave to the development of the WMA mix design.

The contractor shall submit a written mix design formula for review and approval at least 30 calendar days before production. The following information shall be submitted:

- 1. WMA technology and/or additive information.
- 2. WMA technology manufacturer's recommendation for usage.
- 3. WMA technology manufacturer's established target rate for water and additives, the acceptable variation for production, and documentation showing the impact of excessive production variation.
- 4. WMA technology manufacturer's material safety data sheets (MSDS).
- 5. Documentation of past WMA technology field application including points of contact.
- 6. Temperature range for mixing and compacting.
- 7. Asphalt binder performance grade test data over the range of WMA additive percentages proposed for use.
- 8. Laboratory test data, samples and sources of all mix components, and asphalt binder viscosity-temperature relationships.

The contractor shall follow the manufacturer's recommendation for incorporating additives and WMA technologies into the mix. The contractor shall also comply with the manufacturer's recommendation regarding receiving, storage, and delivery of additives.

**Gradation:** The FHWA Superpave 0.45 Power Chart with the recommended restricted zone shall be used to define permissible gradations for the specified mixture. Type C shall be either a No.4 (4.75 mm), 3/8" (9.5 mm), or 1/2" (12.5 mm) Nominal Maximum Aggregate Size Hot-Mix. Unless otherwise noted in the Plans, the Type C shall meet the 3/8" (9.5 mm) Nominal Maximum Aggregate Size. Type B Hot-Mix shall be the 3/4" (19.0 mm) Nominal Maximum Aggregate Size and the Bituminous Concrete Base Course (BCBC) shall be the 1" (25.0 mm) Nominal Maximum Aggregate Size. Target values for percent passing each standard sieve for the design aggregate structure shall comply with the Superpave control points and should avoid the restricted zone. Percentages shall be based on the washed gradation of the aggregate according to AASHTO T11.

In addition to the results of the material requirements specified above, the following material properties shall be provided by the contractor: bulk specific gravity  $G_{sb}$ , apparent specific gravity  $G_{sa}$ , and the absorption of the individual aggregate stockpiles to be used, tested according to AASHTO T84 and AASHTO

T85 and reported to three decimal places along with the specific gravity of the mineral filler to be used, tested according to AASHTO T100 and reported to three decimal places.

# **Superpave Gyratory Compactive (SGC) Effort:**

The Superpave Gyratory Compaction effort employed throughout mixture design, field quality control, or field quality assurance shall be as indicated below. All mixture specimens tested in the SGC shall be compacted to  $N_{\rm M}$  Height data provided by the SGC shall be employed to calculate volumetric properties at  $N_{\rm L}$ ,  $N_{\rm D}$ , and  $N_{\rm M}$ 

#### **Superpave Gyratory Compactive (SGC) Effort:**

DESIGN TRAFFIC LEVEL (MILLION ESAL'S)	N <sub>INITIAL</sub>	$N_{ m DESIGN}$	N <sub>MAXIMUM</sub>
0.3 to < 3	7	75	115
3 to < 30	8	100	160
≥30	9	125	205

**Volumetric Design Parameters.** The design aggregate structure at the target asphalt cement content shall satisfy the volumetric criteria below:

DESIGN ESAL'S	(% Ol MAX	QUIRED DENSITY OF THEORETICAL XIMUM SPECIFIC GRAVITY)			(%	6 - MINIM	AGGREGA IUM) REGATE (		VOIDS FILLED WITH ASPHALT									
(MILLION)	N <sub>INITIAL</sub>	$N_{ m DESIGN}$	N <sub>MAX</sub>	25.0	19.0	9.5	12.5	4.75	(% - MINIMUM)									
0.3  to < 3	≤ 90.5								65.0 - 78.0									
3 to < 10		96.0	≤ 98.0	12.5	13.5	15.5	14.5	16.5										
10 < 30	≤ 89.0	70.0		_ ≤ 70.0	≥ 90.0	≥ 90.0	≥ 96.0	≥ 96.0	≤ 90.0	14.3	12.3	12.3	12.5	12.5	13.3	13.3	14.5	10.3
≥ 30																		

Air voids (V<sub>a</sub>) at  $N_{\text{design}}$  shall be 4.0% for all ESAL designs. Air voids (V<sub>a</sub>) at  $N_{\text{max}}$  shall be a minimum of 2.0% for all ESAL designs

The dust to binder ratio for the mix having aggregate gradations above the Primary Control Sieve (PCS) Control Points shall be 0.6-1.2. For aggregate gradations below the PCS Control Points, the dust to binder ratio shall be 0.8-1.6. For the No. 4 (4.75 mm) mix, the dust to binder ratio shall be 0.9-2.0 whether above or below the PCS Control Points.

For 3/8" (9.5 mm) Nominal Maximum Aggregate Size mixtures, the specified VFA range shall be 73.0% to 76.0% and for 4.75 mm Nominal Maximum Size mixtures, the range shall be 75 % to 78% for design traffic levels  $\geq 3$  million ESALs.

# **Gradation Control Points:**

The combined aggregates shall conform to the gradation requirement specified in the following table when tested according to T-11 and T-27.

Nomina	Nominal Maximum Aggregates Size Control Points, Percent Passing									
	25.0	MM	19.0	MM	12.5	MM	9.5	MM	4.75	MM
SIEVE SIZE	MIN	MAX	MIN	MAX	MIN	MAX	MIN	MAX	MIN	MAX
37.5 MM	100	-	-	-	-	-	-	-	-	-
25.0 MM	90	100	100	-	-	-	-	-	-	-
19.0 MM	-	90	90	100	100	-	-	-	-	-
12.5 MM	-	-	-	90	90	100	100	-	100	-
9.5 MM	-	-	-	-	-	90	90	100	95	100
4.75 MM	-	-	-	-	-	-	-	90	90	100
2.36 MM	19	45	23	49	28	58	32	67	-	-
1.18 MM	-	-	-	-	-	-	-	-	30	60
0.075 MM	1	7	2	8	2	10	2	10	6	12

Note: The aggregate's gradation for each sieve must fall within the minimum and maximum limits.

# **Gradation Classification:**

The Primary Control Sieve (PCS) defines the break point of fine and coarse mixtures. The combined aggregates shall be classified as coarse graded when it passes below the Primary Control Sieve (PCS) control point as defined below. All other gradations shall be classified as fine graded.

PCS CONTROL POINT FOR MIXTURE NOMINAL MAXIMUM AGGREGATES SIZE (% PASSING)					TES SIZE
Nominal maximum Aggregates Size	25.0 mm	19.0 mm	12.5 mm	9.5 mm	4.5 mm
Primary Control Sieve	4.75 mm	4.75 mm	2.36 mm	2.36 mm	1.18 mm
PCS Control Point	40	47	39	47	30-60

#### **Plant Production Tolerances:**

Volumeric Property	Superpave Criteria
Air Voids (V <sub>a</sub> ) at (%) N <sub>m</sub> Air Voids (V <sub>a</sub> ) at N <sub>design</sub> (%)	2.0 (min) 5.5 (max)
Voids in Mineral Aggregate (VMA) at N <sub>design</sub> 25.0 mm Bituminous Concrete Base Course 19.0 mm Type B Hot-Mix 12.5 mm Type C Hot-Mix 9.5 mm Type C Hot-Mix 4.5 mm Type C Hot-Mix	-1.2 +2.0

# **Design Evaluation:**

The contractor shall furnish a Job Mix Formula (JMF) for review and approval. The Engineer may elect to evaluate the proposed JMF and suitability of all materials. All materials requested by the Engineer shall be provided at the contractor's expense to the Central Laboratory in Dover in a timely manner upon request. To verify the complete mixture design and evaluate the suitability of all materials, the following approximate quantities are required:

5.25 gal (20 liters) of the asphalt binder;

0.13 gal (0.5 liters) sample of liquid heat-stable anti-strip additive;

254 lb. (115 kg) of each coarse aggregate;

154 lb. (70 kg) of each intermediate and fine aggregate;

22 lb. (10 kg) of mineral filler; and

254 lb. (115 kg) of RAP, when applicable.

# The proposed JMF shall include the following:

Plot of the design aggregate structure on the FHWA Superpave 0.45 power chart showing the maximum density line, Superpave control points, and recommended restricted zone.

Plot of the three trial asphalt binder contents at +/- 0.5% gyratory compaction curves where the percent of maximum specific gravity (% of  $G_{mm}$ ) is plotted against the log base ten of the number of gyrations (log (N)) showing the applicable criteria for  $N_i$ ,  $N_d$ , and  $N_m$ .

Plot of the percent asphalt binder by total weight of the mix (P<sub>b</sub>) versus the following:

% of  $G_{_{mm}}$  at  $N_{_{d}},$  VMA at  $N_{_{d}},$  VFA at  $N_{_{d}},$  Fines to effective asphalt binder  $(P_{_{be}})$  ratio, and unit weight  $(kg/m^2)$  at both  $N_{_{d}}$  and  $N_{_{m}}.$ 

Summary of the consensus property standards test results for the design aggregate structure, summary of the source property standards test results for the individual aggregates in the design aggregate structure, target value of the asphalt binder content, and a table of  $G_{\text{mm}}$  of the asphalt mixture for the four trial asphalt binder contents determined according to AASHTO T209.

The JMF shall also include the NCAT Ignition Oven calibration for the specific materials utilized for this mix.

# **Construction.**

**Production Plants.** The contractor shall modify their production plant as required by the manufacturer to introduce the WMA technology. Plant modifications may include additional plant instrumentation, the installation of asphalt binder foaming systems and/or WMA technology delivery systems, tuning the plant burner and adjusting the flights in order to operate at lower production temperatures and/or reduced tonnage

**Weather Limitations.** Place mix only on dry, unfrozen surfaces and only when weather conditions allow for proper production, placement, handling, and compacting. Even with WMA technologies, the ambient paving temperature shall be above freezing.

# **Compaction:**

Compaction shall be tested and paid per Item 401699 - Quality Control/Quality Assurance of Bituminous Concrete .05 (b) Pavement Construction - Tests and Evaluations.

#### **Method of Measurement and Basis of Payment:**

Method of Measurement and Basis of Payment will be in accordance with Subsections 401.14 and 401.15 of the Standard Specifications.

The item 401699, will define adjustment factor to be applied to the bituminous concrete payments for bonus or penalty.

1/06/2010

# 705509 - PATTERNED PORTLAND CEMENT CONCRETE SIDEWALK, 4" 705519 - PATTERNED PORTLAND CEMENT CONCRETE SIDEWALK, 6"

#### **Description:**

This work consists of furnishing all materials and constructing a patterned/imprinted Portland cement concrete sidewalk in accordance with notes and details on the Plans, their specifications and as directed by the Engineer.

# **Materials:**

Materials shall conform to Subsections 705.02, 705.03 and 705.04, and other as modified herewith. In case of a conflict, the requirements of the manufacturer shall govern.

The imprinted concrete shall be colored using ready to use dry-shake type hardener and shall be streak free integrands of pigments, include surface conditioning and dispersing agents. The color hardener shall have a sufficient history of use with proven durability and stability. All shake hardener shall be distributed evenly by mechanical spreader.

The dispersing/ releasing agent shall be clear liquid compatible with color hardener. This shall be specifically formulated to prevent bonding of texturing tools to the concrete surfaces. The powdered pigmented dispersing/-releasing agent can be allowed, if this is of the same color as hardener and recommended by the manufacturer.

The imprinted concrete shall be sealed with penetrating sealer of acrylic polymer in the organic solvent having sufficient resistant to discoloration, abrasion, acids and alkalis.

All materials including hardener, dispersing agent, sealer shall be compatible and preferably manufactured by the same manufacturing firm.

The colors shall be as depicted on the Plans. Modifications of color during the sample approval process shall not affect bid prices.

To assure a high quality imprinted/stamped concrete, work should be performed by experience contractor must have minimum 5-year experience dealing with stamped concrete and must be approved by the manufacturer. The contractor shall submit materials source of materials, previous successful history of work to Materials & Research for approval. A sample of minimum size of 3'x3' for each pattern of patterned concrete sidewalk for shall be submitted for color and design approval from the Engineer. Any necessary changes to the color will be directed by the Engineer.

#### **Construction Methods:**

Construction methods shall conform to the applicable requirements of Subsections 705.05 through 705.10, the recommendations of the manufacturer, and as modified herewith. In case of a conflict, the requirements of the manufacturer shall govern.

Special concrete mix shall be placed and screened to the proper grade and floated to a uniform surface in the normal manner. The depth of the concrete sidewalk shall be as noted on the Plans.

Color hardener shall be applied evenly to the concrete while in the plastic, stage of set by dry shake method using a minimum of 60 lbs per 100 sq-ft. It shall be applied in two or more shakes, floated after each and trowel led only after the final floating. The first shake shall consume two third of materials, one third being withheld for the second shake and final touch up. Release agent and sealer shall be applied in accordance with manufacturers instructions.

While concrete is still in plastic stage of set, the imprinting tools shall be applied to make the desired pattern and texture. The patterns shall be as noted on the Plans.

# **Method of Measurement and Basis of Payment:**

Method of Measurement and Basis of Payment shall be in accordance with Subsection 705.11 Method of Measurement and 705.12 Basis of Payment respectively.

12/5/06

```
735531 - SOIL RETENTION BLANKET MULCH, TYPE 1
735532 - SOIL RETENTION BLANKET MULCH, TYPE 2
735533 - SOIL RETENTION BLANKET MULCH, TYPE 3
735534 - SOIL RETENTION BLANKET MULCH, TYPE 4
735535 - SOIL RETENTION BLANKET MULCH, TYPE 6
735537 - SOIL RETENTION BLANKET MULCH, TYPE 7
```

# **Description:**

This work consists of furnishing, placing and anchoring soil retention blanket mulch over seeded areas in accordance with notes and details on the Plans, these specifications and direction of the Engineer.

# **Materials:**

The blanket mulch shall be one of the pre-approved products listed in the Approved Product List (APL) at the time of bid, for the type(s) of mulch required on the Plans.

Pre-approval procedures and the current APL may be obtained by writing to the Stormwater Engineer, Delaware Department of Transportation, P. O. Box 778, Dover, DE 19903 or calling (302) 760-2177 or viewing DelDOT's web page at **www.deldot.net/business**. The Contractor shall submit an 8" x 8" (200 mm x 200 mm) sample to the Stormwater Engineer to verify pre-approval. Also, the Contractor shall submit manufacturer's literature, including installation recommendations, to the Engineer.

The products on the APL have been used extensively on DelDOT projects with satisfactory results and/or have received satisfactory evaluations by the Texas Department of Transportation/Texas Transportation Institute (TxDOT/TTI).

Soil Retention Blanket Mulch, Types 1, 2, 3, 4 and 5, generally referred to as erosion control blankets (ECB), shall be composed entirely of 100% biodegradable material.

Soil Retention Blanket Mulch, Types 6 and 7, generally referred to as turf reinforcement mats (TRM), shall be composed of mostly non-degradable material.

In order for a product to be added to DelDOT's Approved Product List and be eligible for use in DelDOT's construction and maintenance works, the product must meet the above guidelines and receive a satisfactory evaluation by TxDOT/TTI. The Department will remove products from the APL when field performance is unsatisfactory.

#### **Types of Soil Retention Blanket Mulch Application**

- **Type 1.** Sandy soils on slopes steeper than 3H:1V
- **Type 2.** Sandy soils on slopes equal to or flatter than 3H:1V
- **Type 3.** Top-soiled slopes steeper than 3H:1V
- **Type 4.** Top-soiled slopes equal to or flatter than 3H:1V
- **Type 5.** Top-soiled grass swale at maximum design shear stress less than or equal to 2 pounds per square foot (96 Pascals)
- **Type 6.** Top-soiled grass swale at maximum design shear stress greater than 2 pounds per square foot (96 Pascals) and less than or equal to 6 pounds per square foot (287 Pascals)
- **Type 7.** Top-soiled grass swale at maximum design shear stress greater than 6 pounds per square foot (287 Pascals) and less than or equal to 8 pounds per square foot (383 Pascals)

**Construction Methods.** The soil retention blanket mulch, shall be placed immediately after seeding operations have been completed or as approved by the Engineer, but in no case shall this period exceed 24 hours from the completion of the seeding operation. Prior to seeding and mulching, the area to be mulched shall be tracked, free of ruts, rocks or clods over 1 1/2 inches (40 millimeters) in maximum dimension and all sticks or other foreign materials which will prevent the close contact of the blanket with the soil. If as a result of rain, the prepared bed becomes crusted or eroded or if any eroded areas, ruts or depressions exist for any reason, the Contractor shall retrack and reseed the eroded areas.

Except for sprayed blanket mulch installation and anchorage of the soil retention blanket mulch shall be in accordance with notes and details in the Plans and the following DelDOT Standard Construction Details:

Standard No. E-9 for rolled blankets under Types 1 through 5 Standard No. E-25 for blankets under Types 6 and 7

Should the installation requirements of the manufacturer be more stringent than the above, the manufacturer's requirements shall govern.

Sprayed blanket mulches shall be applied as per the manufacturer's instructions and recommended rate. No application shall be permitted if rain is anticipated within 24 hours as determined by the Engineer.

#### **Method of Measurement:**

The quantity of soil retention blanket mulch will be measured in square yards (meters) of each type soil retention blanket mulch installed and accepted. Measurements for calculating the number of square yards (meters) will be made along the surface of the area covered. Overlaps of materials of any kind will not be measured.

# **Basis of Payment:**

The quantity of soil retention blanket mulch will be paid for at the contract unit price per square yard (meter) per each type. Price and payment will constitute full compensation for furnishing and placing all materials; for all methods of anchorage and securement; for repairing any loose or raised pins or pegs or any loose, torn, or undermined fabric; and for all labor, equipment, tools, and incidentals required to complete the work.

01/24/01

## 746774 - SUPPLY AND INSTALLATION OF LOOP DETECTOR WIRE

# **Description:**

This work consists of sawing a cut in existing pavement, furnishing and installing loop detector wire in the saw cut and sealing the saw cut with an approved sealer, in accordance with the Standard Details, these specifications, or as directed by the Engineer.

#### **Materials:**

The loop detector wire shall be a shielded four-conductor controlled capacitance cable with conductors twisted 6 turns per foot and enclosed in an aluminized polyester shield within a polyethylene jacket, rated to 600 volts. The interior of the cable is filled with a water blocking material. The four conductors are AWG # 18 stranded copper with color-coded polypropylene insulation. Color rotation is black, red, white, and green. The loop detector wire shall have an UV stable high-density polyethylene outer cover that is chemical resistant and waterproof with a wall thickness of 0.032 inches (0.8 mm). The cable shall have a temperature tolerance range of -65 to +176 degrees Fahrenheit (-54 to +80 degrees Celsius). Outside diameter of the cable is 0.25 inches (6 mm).

Flexible embedding sealer shall be a cold poured, resilient type epoxy joint sealer, Bondo P-606 or Duracote - D115 for concrete or asphalt pavement or E-Poxy Industry 36-1 for concrete or E-Poxy Industry 11-1 for asphalt pavement, or approved equal.

A sealer accelerant or retarder may be added at the discretion of the Contractor.

3/8" (10 mm) closed cell foam backer rod

# **Construction Methods:**

The saw cut shall be 1/4" (6 mm) wide and 3" (76 mm) deep. It shall be cut in the directions and sizes specified on the Standard Details or as directed by the Engineer. Contractor shall remove sharp edges in the saw cut and round the corners.

The saw cut shall be blown out with compressed air to remove all dust, water and particles of loose material.

A 3/8" (10 mm) backer rod will be placed into the bottom of the saw cut. The loop detector wire will then be installed using blunt tools so as to prevent damage to the polyethylene outer cover. One end of a loop detector wire shall be tagged to indicate start ("S"). All loop detector wires shall be laid in saw cuts in a clockwise rotation beginning with "S". The Engineer may require a High Voltage Ground Test with a 500 VDC megger after the loop detector installation is complete and prior to sealing saw cuts. If the resistance to ground is less than 100 megohms, this work will be rejected. Loop detectors also should be checked for continuity between the four conductors with an ohm-meter. If there is any resistance between colors or there is an open flow from color to color, this work will be rejected.

A sealer and sealer accelerant or retarder (if necessary) shall be applied in accordance with the manufacturer's directions and protected from traffic until it has set. A minimum of 1 inch of sealer shall be installed on top of the loop detector wire.

Two loop detector wires shall be installed in a saw cut from the loop to the edge of the road. These two wires shall then extend from the end of the saw cut to a junction well (see Standard Details). Wires shall be parallel and taped every 12" (305 mm) to 18" (457 mm) from the end of the saw cut to a junction well. A conduit may need to be installed between the end of the saw cut and junction well as directed by the Engineer. In this case the loop detector wire shall be installed in the conduit.

The loop detector wire shall be continuous and without splices from the junction well, through the saw cuts and conduit (if any).

#### **Method of Measurement:**

The quantity of loop detector wire to be measured under this item shall be the number of linear feet (meters) of saw cut in which loop detector wire is installed, sealed, tested, and accepted.

The additional loop detector wire needed beyond the saw cut to reach the junction well and sealer accelerant or retarder shall be incidental to this item and there shall be no separate measurement or payment. Any required conduit will be paid under a separate item.

Supply and installation of the conduit from the end of the saw cut to the junction well shall be covered under other items of this Contract. Installation of the loop detector wire in this conduit shall be incidental to this item and there shall be no separate measurement or payment.

Splicing of the loop detector wire to a lead-in cable in a junction well shall not be covered under this item and shall be paid separately under another item of this Contract.

# **Basis of Payment:**

The quantity of detector wire supplied and installed will be paid for at the Contract unit price per linear foot (meter) of sawcut. Price and payment shall constitute full compensation for furnishing and placing all materials including loop detector wire, backer rod, sealer, labor, equipment, tools, and incidentals necessary to complete this item.

5/7/10

# 746776 - LOOP DETECTOR SPLICE

# **Description:**

This work consists of splicing a loop detector wire to a loop detector lead-in cable ("home run").

#### **Materials:**

Soldering iron Rosin core solder 3/16" (5 mm) heat shrink tubing Splicing kit Vinyl tape – black, white, red, green, yellow, and blue

#### **Construction Methods:**

Each conductor to be spliced shall have sufficient wire jacket removed, with wire strippers or other approved tool, to expose 1/2 inch (13 mm) of the copper conductor. The use of any tool that might nick the conductor or cut a strand of wire is specifically prohibited.

Each conductor not to be spliced shall be inspected and trimmed as necessary to ensure that the copper conductor does not extend beyond the insulation.

When splicing a loop detector wire to a lead-in cable, the two ends of the loop detector wire forming one loop shall be spliced first. The method of splicing the two ends of the loop detector wire forming one loop is described below:

Splice the green, red and black conductors of start end ("S" or "In") of the loop detector wire to the white, green and red conductors of the finish end ("F" or "Out") of the same wire as follows:

- Green of "S" to White of "F" Red of "S" to Green of "F"
- Black of "S" to Red of "F"

A maximum of two loops shall be spliced to one loop detector lead in cable. The method of splicing two loops (Loop 1 and Loop 2) to a loop detector lead in cable is described below:

- Splice Loop 1 "S" White to a lead in cable White and Loop 1 "F" Black to a lead in cable 1. Black.
- Splice Loop 2 "S" White to a lead in cable Green and Loop 2 "F" Black to a lead in cable 2.

Conductors to be soldered shall be placed side by side with the exposed copper aligned. The copper shall then be twisted clockwise with pliers until a good mechanical connection is effected. The splice shall be coated with flux, heated with a soldering iron, and soldered in a manner, which minimizes insulation damage. After each soldered connection is completed, it shall be properly insulated with heat shrink tubing.

After the electrical and mechanical connection is completed and before the splicing kit is applied, a test shall be made by the Contractor to ensure that all circuits are complete. A splicing kit shall be installed as per manufacturer's instructions. A communication test will be performed at the cabinet by the Department technician after the splicing kit is applied. The Department will be notified of the test results. If the communication test fails the Contractor shall remake the splice at his own expense.

Each loop detector lead-in cable shall be identified with a distinctive band(s) at each end of the run. Additionally the loop "number" will be identified. Based upon direction of travel, the loop will be identified from left to right, closest to stop bar to furthest away, by a distinctive number of colored bands. System loops will also have a white band AFTER the color band. The following colors will be used as the distinctive band to denote direction of travel:

North Bound --- RED
East Bound --- GREEN
South Bound --- YELLOW
West Bound --- BLUE

If a splice is found to be faulty within 90 calendar days of installation, it shall be the Contractor's responsibility to remake the splice at his own expense.

# **Method of Measurement:**

The quantity of splices shall be measured as the number of loop detectors connected to a lead-in cable in accordance with these specifications, complete in place, and accepted. Splicing the "S" end to the "F" end of the loop detector wire forming one loop shall not be considered a separate loop detector splice.

# **Basis of Payment:**

The quantity of splices installed will be paid for at the Contract unit price per each. Price and payment will constitute full compensation for all materials, labor, equipment, tools, and incidentals required to complete the work.

05/07/10

```
748506 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 4"
748507 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 6"
748508 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 8"
748509 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 12"
748510 - PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND, EPOXY RESIN PAINT
748535 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 4"
748536 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 6"
748538 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 10"
748549 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 16"
748549 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"
748557 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"
748557 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"
748559 - PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 3"
```

# **Description:**

This work consists of furnishing and applying white or yellow, epoxy reflectorized pavement markings or black epoxy contrast pavement markings at the locations and in accordance with the patterns indicated on the Plans, or as directed by the Engineer, and in accordance with these specifications.

The white/yellow epoxy marking material shall be hot-applied by spray methods onto bituminous and/or Portland cement concrete pavement surfaces as required by the Plans. Following an application of double drop glass beads of two sizes and upon curing, the resultant epoxy marking shall be an adherent reflectorized stripe of the specified thickness and width that is capable of resisting deformation by traffic. All marking materials shall be certified lead free and free of cadmium, mercury, hexvalent chromium, and other toxic heavy metals.

The black epoxy marking shall be a two-component, hot-spray applied epoxy resin pavement marking material to be used for pavement marking on Portland cement concrete pavement surfaces. Following an aggregate drop, and upon curing, it shall produce an adherent stripe of specified thickness and width capable of resisting wear from traffic. Black contrast pavement markings will be required on all Portland cement concrete pavements.

#### **Materials Requirements:**

# A. White and Yellow Reflectorized Epoxy

#### 1. Epoxy Composition Requirements:

The epoxy resin composition shall be specifically formulated for use as a pavement marking material and for hot-spray application at elevated temperatures. The type and amounts of epoxy resins and curing agents shall be at the option of the manufacturer, providing the other composition and physical requirements of this specification are met.

The epoxy marking material shall be a two-component (Part A and Part B), 100% solids type system formulated and designed to provide a simple volumetric mixing ratio (e.g. two volumes of Part A to one volume of Part B).

<u>Component A</u> of both white and yellow shall conform to the following requirements:

	% BY WEIGHT	
	WHITE:	YELLOW:
Pigments	Titanium Dioxide - 18% Min.	Organic Yellow - 6%-10%
	(ASTM D476, Type II)	
Epoxy Resin	75% Min., 82% Max.	70% Min., 77% Max.

The entire pigment composition shall consist of either titanium dioxide and/or organic yellow pigment. No extender pigments are permitted. The white pigment upon analysis, shall contain a minimum of 16.5% TiO<sub>2</sub> (100% purity).

Epoxy Content-WPE (Component A) - The epoxy content of the epoxy resin will be tested in accordance with ASTM D1652 and calculated as the weight per epoxy equivalent (WPE) for both white and yellow. The epoxy content will be determined on a pigment free basis. The epoxy content (WPE) shall meet a target value provided by the manufacturer and approved by the Department's Material and Research Section (from now on will be addressed as Department). A  $\pm$  50 tolerance will be applied to the target value to establish the acceptance range.

Amine Value (Component B) - The amine value of the curing agent shall be tested in accordance with ASTM D2074-66 to determine its total amine value. The total amine value shall meet a target value provided by the manufacturer and approved by the Department. A  $\pm 50$  tolerance will be applied to the target value to establish the acceptance range.

<u>Toxicity</u> - Upon heating to application temperature, the material shall not exude fumes which are toxic or injurious to persons or property.

<u>Viscosity</u> - Formulations of each component shall be such that the viscosity of both components shall coincide (within 10%) at a recommended spray application.

# 2. Physical Properties of Mixed Composition:

Unless otherwise noted, all samples are to be prepared and tested at an ambient temperature of  $73 \pm 5$ °F.  $(23 \pm 3$ °C).

a. <u>Color</u>. The white epoxy composition when applied at a minimum wet film thickness of 20±1 mils (500 μm) as applicable and allowed to dry, shall plot within the boundaries described by the four corner points listed in Tables 1 and 2 of ASTM D 6628-01 when measured in accordance with the test methods prescribed in Section 7 of ASTM D 6628-01.

The yellow epoxy composition when applied at a minimum wet film thickness of  $20\pm1$  mils ( $500~\mu m$ ) as applicable and allowed to dry, shall plot within the boundaries described by the four corner points listed in Tables 1 and 2 of ASTM D 6628-01 when measured in accordance with the test methods prescribed in Section 7 of ASTM D 6628-01.

b. <u>Directional Reflectance</u>. The white epoxy composition (without glass spheres) shall have a daylight directional reflectance of not less than 84% relative to a magnesium oxide standard when tested in accordance with Method 6121 of Federal Test Method Standard No. 141.

The yellow epoxy composition (without glass spheres) shall have a daylight directional reflectance of not less than 55% relative to a magnesium oxide standard when tested in accordance with Method 6121 of Federal Test Method Standard No. 141.

c. <u>Drying Time (Laboratory)</u>. The epoxy composition, when mixed in the proper ratio and applied at a 20±1 mils (500 µm) minimum wet film thickness, and immediately dressed with large reflective glass spheres (Federal Spec. Type 4)at a rate of 12 lb/gal (1.4 kg/l) of epoxy pavement marking materials, immediately followed by a second drop of AASHTO M-247 Type 1 glass spheres applied at a rate of 12 lb/gal (1.4 kg/L) of epoxy pavement marking material, shall exhibit a no-track condition in 15 minutes or less (ASTM D711). A Bird Applicator or any other doctor blade shall be used to produce a uniform film thickness.

d. <u>Drying Time (Field)</u>. When installed at a minimum wet film thickness of 20±1 mils (500 or 625 um) and reflectorized with glass spheres, the maximum drying times shall correspond to these temperatures:

80°F (27°C) 10 minutes 70°F (21°C) 10 minutes 60°F (16°C) 15 minutes 50°F (10°C) 25 minutes 40°F (4°C) 45 minutes 35°F (2°C) 60 minutes

The composition shall dry to "no-tracking" in approximately 10 minutes, and after thirty (30) minutes shall show no damaging effect from traffic. Dry to "no-tracking" shall be considered as the condition where no visual deposition of the epoxy marking to the pavement surface is observed when viewed from a distance of 100 feet (30 meters), after a passenger car is passed over the line. Regardless of the temperature at the time of installation, the installation contractor shall be responsible for protection of the markings material until dry to a non-tracking state.

- e. <u>Abrasion Resistance</u>. The wear index of the composition shall not exceed 82 when tested in accordance with ASTM C501 using a CS-17 wheel and under a load of 1000 grams for 1000 cycles.
- f. Tensile Strength. The tensile strength of the epoxy composition shall not be less than 6000 psi (41 MPa) when tested in accordance with ASTM D638 using a Type IV specimen  $[0.125'' \pm 0.010'' (3.18 \pm 0.25 \text{ mm}) \text{ thick}]$ . Tests shall be conducted at an ambient temperature of  $75 \pm 5^{\circ}\text{F}$  ( $24 \pm 3^{\circ}\text{C}$ ). The testing machine shall operate at a speed of 0.20'' (5.1 mm) per minute.

The total conditioning or drying period, from the time the epoxy composition is first mixed to the time of testing, shall not be less than 24 hours nor more than 96 hours.

Test specimens for tensile strength determination will be prepared as follows:

A 1/8 inch (3 mm) thick sheet of epoxy material is cast from a reservoir-type mold, fabricated from polyterrafluorethylene (PTFE), 1/8" deep x 10" x 10" (3 mm deep x 250 mm x 250 mm).

Prior to casting, the mold is sprayed with a suitable release agent. A sufficient amount of epoxy composition is mixed in the proper proportions (A:B) and poured level with the top of the mold. Care should be taken so as not to decrease or exceed the 1/8" (3 mm) thickness.

After a period of 1 to 4 hours, the material will have set into a semi-rigid sheet that is flexible enough to die-cut yet rigid enough to retain its shape. While the material is in this "plastic" state, five (5) specimens shall be die-cut and then placed on a flat, smooth, PTFE surface for the completion of the specified conditioning period.

g. <u>Compressive Strength</u>. The compressive strength of the epoxy composition shall not be less than 12,000 psi (83 MPa) when tested in accordance with ASTM D695 except that a compression tool shall not be necessary. The test specimen shall be a right cylinder [0.50 inch diameter by 1.0 inch length (12 mm diameter by 25 mm length)]. Tests shall be conducted at an ambient temperature of  $75 \pm 5^{\circ}$ F (24  $\pm 3^{\circ}$ C).

The total conditioning or drying period, from the time the epoxy composition is first mixed to the time of testing shall not be less than 24 hours nor more than 96 hours.

Test specimens for compressive strength determinations will be prepared as follows:

Five molds will be prepared from 1/2" (12 mm) I.D., 1/16" (1.5 mm) wall thickness acrylic tubing, cut in 1 1/2" (38 mm) lengths. After spraying the inside of the mold with a suitable release agent, (1) the cylindrical tubes are placed in a vertical position

on a PTFE sheet base. A sufficient amount of epoxy composition is thoroughly mixed in the proper proportions (A:B) and poured into the mold to a depth of approximately 1 1/4" (32 mm). After a minimum of 72 hours curing, the specimens are removed from the molds and machined to a length of 1"  $\pm$  0.002" (25 mm  $\pm$  0.05 mm).

h. <u>Hardness</u>. The epoxy composition when tested in accordance with ASTM D2240 shall have a Shore D hardness of between 75 and 100. Samples shall be allowed to dry for not less than 24 hours nor more than 96 hours prior to testing.

#### B. Reflective Glass Spheres/Beads

Reflective glass spheres for drop-on application shall conform to the following requirements:

The glass spheres shall be colorless; clean; transparent; free from milkiness or excessive air bubbles; and essentially clean from-surface scarring or scratching. They shall be spherical in shape and at least 80% of the glass beads shall be true spheres when tested in accordance with ASTM D1155. At least 80% of the Type IV beads shall be true spheres as measured by the visual method.

The refractive index of the spheres shall be a minimum of 1.50 as determined by the liquid immersion method at  $77^{\circ}F$  ( $25^{\circ}C$ ).

The silica content of the glass spheres shall not be less than 60%.

The crushing resistance of the spheres shall be as follows: A 40 lb. (18 kg) dead weight, for 20 to 30 (850  $\mu$ m to 600  $\mu$ m) mesh spheres shall be the average resistance when tested in accordance with ASTM D1213.

The glass spheres shall have the following grading when tested in accordance with ASTM D1214.

M247 AASHTO Type 1 Glass Spheres		
U.S. Standard Sieve	% Retained	% Passing
#20 (850µm)	0	100
#30 (600µm)	5-25	75-95
#50 (300µm)	40-65	15-35
$#100 (150 \mu m)$	15-35	0-5
Pan	0-5	

% Retained	% Passing
0	100
0-5	95-100
5-20	80-95
40-80	10-40
10-40	0-5
0-5	0-2
0-2	
	0 0-5 5-20 40-80 10-40 0-5

The AASHTO M247 Type 1 glass spheres shall be treated with a moisture-proof coating. They shall show no tendency to absorb moisture in storage and shall remain free of clusters and hard lumps. They shall flow freely from dispensing equipment at any time when surface and atmosphere conditions are satisfactory for marking operations. The moisture-resistance of the glass spheres shall be determined in accordance with AASHTO M247 test method 4.4.1.

Type IV glass spheres shall be treated with an adhesion coating. They shall show no tendency to absorb moisture in storage and shall remain free of clusters and hard lumps. They shall flow freely from dispensing equipment at any time when surface and atmosphere conditions are satisfactory for

marking operations. The adhesion coating property of the Type IV beads shall be tested in accordance with the dansyl-chloride test.

# C. Black Epoxy Contrast Markings

Epoxy Resin Requirements: The two-component, 100% solids, paint shall be formulated and designed to provide a simple volumetric mixing ratio (e.g. 2 part component A to 1 part component B) specifically for service as a hot-spray applied binder for black aggregate in such a manner as to produce maximum adhesion. The material shall be composed of epoxy resins and pigments only.

The paint shall be well mixed in the manufacturing process and shall be free from defects and imperfections that may adversely affect the serviceability of the finished product. The paint shall not thicken, curdle, gel, settle excessively, or otherwise display any objectionable properties after storage. Individual components shall not require mixing prior to use when stored for a maximum of 6 months.

The overall paint composition shall be left to the discretion of the manufacturer, but shall meet the following requirements:

Composition:

Carbon Black
(ASTM D476 Type III)

Talc
Epoxy Resin

Carbon Black
7±2 percent, by weight
14±2 percent, by weight
79±4 percent, by weight

#### D. Black Aggregate

The moisture resistant aggregate shall meet the gradation requirements (AASHTO T27) as follows:

Percent Retained
18-28%
60-80%
2-14%

The moisture resistant aggregate shall have a ceramic coating. The aggregate shall be angular with no dry dispensement pigment allowed.

Hardness: The black aggregate hardness shall be 6.5-7 on Moh's

Mineral Scale.

Porosity: The black aggregate porosity shall be less than two (2)

percent.

Moisture Content: The black aggregate moisture content shall be less than a

half (.5) percent.

# E. Packaging and Shipment

Epoxy pavement marking materials shall be shipped to the job site in strong substantial containers. Individual containers shall be plainly marked with the following information:

- a. Name of Product
- b. Lot Number
- c. Batch Number
- d. Test Number
- e. Date of Manufacture
- f. Date of expiration of acceptance (12 months from date of manufacture)
- g. The statement (as appropriate)
  - Part A Contains Pigment & Epoxy Resin

Part B - Contains Catalyst

- h. Quantity
- i. Mixing proportions, Application Temperature and Instructions

- j. k. Safety Information
- Manufacturer's Name and Address

Reflective glass spheres shall be shipped in moisture resistant bags. Each bag shall be marked with the name and address of the manufacturer and the name and net weight of the material.

F. The Department reserves the right to randomly take a one-quart sample of white, yellow and hardener, of the epoxy material or glass spheres without prior notice for testing to ensure the epoxy material meets specifications.

#### **Epoxy Application Equipment:**

Application equipment for the placement of epoxy reflectorized pavement markings shall be approved by the Department, prior to the start of work.

At any time throughout the duration of the project, the Contractor shall provide free access to his epoxy application equipment for inspection by the Engineer or his authorized representative.

In general, the application equipment shall be a mobile, truck mounted and self contained pavement marking machine, specifically designed to apply epoxy resin materials and reflective glass spheres in continuous and skip-line patterns. The application equipment shall be maneuverable to the extent that straight lines can be followed and normal curves can be made in a true arc. In addition, the truck mounted unit shall be provided with accessories to allow for the marking of legends, symbols, crosswalks, and other special patterns.

The Engineer may approve the use of a portable applicator in lieu of truck mounted accessories, for use in applying special markings only, provided such equipment can demonstrate satisfactory application of reflectorized epoxy markings in accordance with these specifications.

The applicator shall be capable of installing up to 20,000 lineal feet (6,100 lineal meters) of epoxy reflectorized pavement markings in an 8-hour day and shall include the following features:

- 1. The applicator shall provide individual material reservoirs, or space, for the storage of Part A and Part B of the epoxy resin composition; for the storage of water; and for the storage of reflective glass spheres.
- 2. The applicator shall be equipped with heating equipment of sufficient capacity to maintain the individual epoxy resin components at the manufacturer's recommended temperature for spray application and for heating water to a temperature of approximately 140°F (60°C).
- 3. The glass spheres shall be gravity dropped upon 20 mils (500 um) of epoxy pavement markings to produce a wet-night-reflective pavement marking. The large spheres (Federal Spec. Type 4) shall be applied at a rate of 12 pounds per gallon (1.4 kg/L) of epoxy pavement marking material, immediately followed by a second drop of AASHTO M-247 Type 1 glass spheres applied rate of 12 pounds per gallon (1.4 kg/L) of epoxy pavement marking material. This application rate and the following gradation shall conform to FHWA's FP-96: Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects (pages 757-761 Type 3 and Type 4 Beads).
- 4. The applicator shall be equipped with metering devices or pressure gauges, on the proportioning pumps. Metering devices or pressure gauges shall be visible to the Engineer.
- 5. The applicator shall be equipped with all the necessary spray equipment, mixers, compressors, and other appurtenances to allow for the placement of epoxy reflectorized pavement markings in a simultaneous sequence of operations as described below in Construction Details, D. Applications of Epoxy Reflectorized Pavement Markings of this Special Provisions.

#### **Construction Details.**

A. <u>General</u>: All pavement marking and patterns shall be placed as shown on the Plans or as directed by the Engineer.

Before any pavement markings work is begun, a schedule of operations shall be submitted for the approval of the Engineer. This schedule shall be submitted 2 weeks prior to the application of the striping.

At least five (5) days prior to starting striping the Contractor shall provide the Engineer with the epoxy manufacturer's written instructions for use. These instructions shall include but not be limited to: mixing ratios, application temperatures, and recommendations for use of water spray.

The application of pavement markings shall be done in the general direction of traffic. Striping against the direction of traffic flow shall not be allowed.

The Contractor shall be responsible for removing, to the satisfaction of the Engineer, tracking marks, spilled epoxy or epoxy markings applied in unauthorized areas.

The hot water spray shall not be used in conjunction with markings applications on any pavement surface, or on any existing durable type marking, unless specifically recommended by the manufacturer of the epoxy material.

- B. <u>Atmospheric Conditions</u>: Epoxy pavement markings shall only be applied during conditions of dry weather and on substantially dry pavement surfaces. At the time of installation the pavement surface temperature shall be a minimum of 35°F (2°C) and the ambient temperature shall be a minimum of 35°F (2°C) and rising. The Engineer shall be the sole determiner as to when atmospheric conditions and pavement surface conditions are such to produce satisfactory results.
- C. <u>Surface Preparations</u>: The Contractor shall clean the pavement or existing durable marking to the satisfaction of the Engineer.

Surface cleaning and preparation work shall be performed only in the area of the epoxy markings application.

At the time of application <u>all</u> pavement surfaces and existing durable markings shall be free of oil, dirt, dust, grease and similar foreign materials. The cost of cleaning these contaminants shall be included in the bid price of this item. Also, the item shall include the cost of removal of the curing component in the area of the epoxy markings application, if concrete curing compounds on new portland cement concrete surfaces have been used. Waterblasting will not be permitted for removal.

D. <u>Application of White/Yellow Epoxy Reflectorized Pavement Markings</u>: White/yellow epoxy reflectorized pavement markings shall be placed at the widths and patterns designated on the Contract Plans.

Markings operations shall not begin until applicable surface preparation work is completed, and approved by the Engineer.

White/yellow epoxy pavement markings shall be applied at a minimum uniform thickness of 20 mils  $(500\,\mu\text{m})$  on all Portland cement concrete and bituminous concrete pavement, including Stone Matrix Asphalt.

Large reflective glass spheres (Federal Spec. Type 4) shall be applied at the rate of 12 pounds per gallon (1.4 kg/L) of epoxy pavement marking material, immediately followed by a second drop of AASHTO M-247 Type 1 glass spheres applied at a rate of 12 pounds per gallon (1.4 kg/L) of epoxy pavement marking material. Glass spheres shall uniformly cover the length and width of the pavement marking.

E. <u>Application of Black Epoxy Contrast Pavement Markings</u>: Black epoxy contrast pavement markings shall be placed at the widths designated on the Contract Plans.

Markings operations shall not begin until applicable surface preparation work is completed, and approved by the Engineer.

Black epoxy contrast pavement markings shall be applied at a minimum uniform thickness of 20 mils  $(500 \ \mu m)$  on all Portland cement concrete surfaces followed by a single drop of graded black aggregate.

The width of black epoxy line shall be applied for the following situations:

<u>Center Skip Line</u> - On Portland cement concrete pavements a black contrast skip line shall be 10 feet (3 m) in length of the same width as the white epoxy reflectorized skip. It is to lead the white skip and stop at the beginning of the white skip. The black contrast skip is to have a single application of graded black aggregate.

Edge Lines - All edge lines on Portland cement concrete pavements shall have a base of black contrast markings which is 4 inches (100 mm) wider than the reflective white or yellow marking. The black contrast marking is to be applied first with a single drop of graded black aggregate. Once it has cured sufficiently so as not to track, the reflectorized white or yellow line is to be applied on top of it. The reflective line is to be centered along the black contrast line such that a minimum of 2 inches (50 mm) of black contrast marking is visible on either side of the reflective marking.

- F. <u>Defective Epoxy Pavement Markings</u>: Epoxy reflectorized pavement markings, which after application and curing are determined by the Engineer to be defective and not in conformance with this specification, shall be repaired. Repair of defective markings shall be the responsibility of the Contractor and shall be performed to the satisfaction of the Engineer as follows:
  - 1. Insufficient film thickness [(less than 20±1 mils (500 μm) as applicable] and line widths; insufficient glass bead coverage or inadequate glass bead retention.

<u>Repair Method</u>: Prepare the surface of the defective epoxy marking by shot blasting, sand blasting, or water blasting. No other cleaning methods will be allowed. Surface preparation shall be performed to the extent that a substantial amount of the reflective glass spheres are removed and a roughened epoxy marking surface remains.

Immediately after surface preparation remove loose particles and foreign debris by brooming or blasting with compressed air.

Repair shall be made by re-striping over the cleaned surface, in accordance with the requirements of this specification and at a full  $20\pm1$  mils (500 µm) minimum line thickness as applicable.

2. Uncured or discolored epoxy (brown patches); insufficient bond to pavement surface (or existing durable marking).

Uncured epoxy shall be defined as applied material that fails to cure (dry) in accordance with the requirements of this specification under <u>MATERIALS</u>, A, 2d. <u>DRYING TIME (FIELD)</u>; or applied material that fails to cure (dry) within a reasonable time period under actual field conditions, as defined by the Engineer.

Discoloration (brown patches) shall be defined as localized areas or patches of brown or grayish colored epoxy marking material. These areas often occur in a cyclic pattern and also, often are not visible until several days or weeks after markings are applied.

<u>Repair Method</u>: The defective epoxy marking shall be completely removed and cleaned to the underlying pavement surface to the satisfaction of the Engineer.

The extent of removal shall be the defective area plus any adjacent epoxy pavement marking material extending one foot (300 mm) any direction.

After surface preparation work is complete, repair shall be made by re-applying epoxy over the cleaned pavement surface in accordance with the requirements of this specification.

3. Reflectivity for epoxy resin paint.

After satisfactory completion of all striping work and written notification from the Contractor, the Department shall test the striping to ensure it has the minimum reflectivity. The testing will be completed within 30 calendar days from notification. The Contractor may request that tests be conducted on completed phases or portions of the work. Approval of such a request will be at the discretion of the Engineer. Testing will be done using a Delta LTL 2000 Retrometer (30 meter geometry). Five readings will be taken per line per mile (1.6 km). Projects less than 1 mile (1.6 km) in length will have a minimum of 5 readings per line. These readings will then be averaged for the overall project average.

The required average minimum initial reflectivity reading in millicandellas shall be:

White 450 Yellow 325

Any single reading shall not be less than 350 millicandellas for white and 250 millicandellas for yellow. Without exception, any pavement markings installed that does not meet the above average minimum initial reflectivity numbers shall be removed and replaced, at the installation contractor's expense.

Other defects not noted above, but determined by the Engineer to need repair, shall be repaired or replaced as directed by and to the satisfaction of the Engineer.

All work in conjunction with the repair or replacement of defective epoxy reflectorized pavement markings shall be performed by the Contractor at no additional cost to the State.

#### **Method of Measurement:**

The quantity of permanent pavement striping (white, yellow, or black epoxy resin paint) will be measured by the number of linear feet (meters) of pavement striping line and number of square feet (meter) of symbol installed on the pavement and accepted in accordance with the Plans.

#### **Basis of Payment:**

The quantity of permanent pavement striping (white, yellow, or black epoxy resin paint) payment will be paid for at the Contract unit price per linear foot (meter) for 4", 6", 8", 10", 12", 16" (100 mm, 150 mm, 200 mm, 250 mm, 300 mm, or 400 mm) line and the Contract unit price per square foot (meter) of symbol. The quantity of permanent pavement marking (white, yellow, or black epoxy resin paint) will be paid for at the Contract unit price per linear foot (meter) of line and the Contract unit price per square foot (meter) of symbol. Price and payment shall include cleaning and preparing the pavement surface, and placing all materials, for all labor, tools, equipment and incidentals necessary to complete the work.

#### **NOTE:**

For information only:

The following manufacturers are known to us which manufacturer Epoxy Resin Paint for Pavement Striping. The Department does not endorse or require the use of any of the manufacturers listed below. However, a bidder wishes to use another manufacturer's product, it shall be submitted for review and approval prior to submitting a bid proposal. Should the product be deemed unacceptable by the Department, the successful bidder will be required to use only an approved product.

- 1. POLY CARB, Inc. 33095 Bainbridge Road Solon, Ohio 44139 Tel. 1-800-CALLMIX
- 2. IPS Ennis Paint P.O. Box 13582 Research Triangle Park, North Carolina 27709 Tel. 1-877-477-7623

- 3. Epoplex One Park Avenue Maple Shade, NJ 08052 Tel. 1-800-822-6920
- 4. Or an approved equal.

4/22/2010

#### 760509 - RUMBLE STRIPS, FULL LANE WIDTH

#### **Description:**

This work consists of furnishing a pavement cutting machine and cutting rumble strips in bituminous concrete pavement in accordance with the details and notes on the Plans and as directed by the Engineer. In general, rumble strips shall be cut perpendicular to the centerline of the road and shall extend across the full width of the lane.

#### **Construction Method:**

The machine shall be one with a proven record for use in cutting strips in bituminous concrete pavement. The strips shall be cut in accordance with the dimensions as detailed on the Plans, and materials resulting from cutting the pavement shall be disposed of and the slots shall be properly cleaned.

#### **Method of Measurement:**

The quantity of rumble strips will be measured as the actual number of linear feet (meters) of rumble strip slot cut in the pavement and accepted. Measurement will be made along the slot.

#### **Basis of Payment:**

The quantity of rumble strips will be paid for at the Contract unit price per linear foot (meter). Price and payment will include full compensation for furnishing the machine and operator as described herein and cutting the strip slots, for disposing of the discarded materials and cleaning the rumble strip area, and for all labor, tools, equipment and necessary incidentals to complete the work.

10/12/00

#### 763502 - MAINTENANCE OF RAILROAD TRAFFIC (NORFOLK SOUTHERN)

#### 1. AUTHORITY OF RAILROAD ENGINEER AND STATE ENGINEER:

The authorized representative of the Railroad Company, hereinafter referred to as Railroad Engineer, shall have final authority in all matters affecting the safe maintenance of Railroad traffic of his/her Company including the adequacy of the foundations and structures supporting the Railroad tracks.

The authorized representative of the State, hereinafter referred to as the Engineer, shall have authority over all other matters as prescribed herein and in the Project Specifications.

#### 2. NOTICE OF STARTING WORK:

- A. The Contractor shall not commence any work on Railroad rights-of-way until he/she has complied with the following conditions:
  - a. Given the Railroad written notice, with copy to the Engineer who has been designated to be in charge of the work, at least ten days in advance of the date he/she proposes to begin work on Railroad rights-of-way.

#### **Crossing Surfaces**

#### Chief Engineer - D&C Norfolk Southern Corp. 175 Spring Street, SW Building Box 142 Atlanta, Georgia 30303

#### **Warning Devices**

Chief Engineer - S&C Norfolk Southern Corp. 99 Spring Street, SW Building Box 123 Atlanta, Georgia 30303

#### **Bridges & Structures**

Chief Engineer Bridges and Structures Norfolk Southern Corp. 99 Spring Street, SW Atlanta, Georgia 30303

- b. Obtained written authorization from the Railroad to begin work on Railroad rights-of-way, such authorization to include an outline of specific conditions with which he/she must comply.
- c. Obtained written approval from the Railroad of Railroad Protective Insurance Liability coverage as required by paragraph 14 herein.
- d. Furnished a schedule for all work within the Railroad rights-of-way as required by paragraph 7,B,1.
- B. The Railroad's written authorization to proceed with the work shall include the names, addresses, and telephone numbers of the Railroad's representatives who are to be notified as hereinafter required. Where more than one representative is designated, the area of responsibility of each representative shall be specified.

#### 3. INTERFERENCE WITH RAILROAD OPERATIONS:

A. The Contractor shall so arrange and conduct his/her work that there will be no interference with Railroad operations, including train, signal, telephone and telegraphic services, or damage to the property of the Railroad Company or to poles, wires, and other facilities of tenants on the rights-of-way of the Railroad Company. Whenever work is liable to affect the operations or safety of trains, the method of doing such work shall first be submitted to the Railroad Engineer for approval, but such approval shall not relieve the Contractor from liability. Any work to be performed by the Contractor which requires flagging service or

inspection service shall be deferred by the Contractor until the flagging service or inspection service required by the Railroad is available at the job site.

- B. Whenever work within Railroad rights-of-way is of such a nature that impediment to Railroad operations such as use of runaround tracks or necessity for reduced speed is unavoidable, the Contractor shall schedule and conduct his/her operations so that such impediment is reduced to the absolute minimum.
- C. Should conditions arising from, or in connection with the work, require that immediate and unusual provisions be made to protect operations and property of the Railroad, the Contractor shall make such provisions. If in the judgment of the Railroad Engineer, or in his/her absence, the Engineer, such provisions is insufficient, either may require or provide such provisions as he/she deems necessary. In any event, such unusual provisions shall be at the Contractor's expense and without cost to the Railroad or the State.

#### 4. TRACK CLEARANCES:

The minimum track clearances to be maintained by the Contractor during construction are shown on the Project Plans. However, before undertaking any work within Railroad right-of-way, or before placing any obstruction over any track, the Contractor shall:

- 1. Notify the Railroad's representative at least 72 hours in advance of the work.
- 2. Receive assurance from the Railroad's representative that arrangements have been made for flagging service as may be necessary.
- 3. Receive permission from the Railroad's representative to proceed with the work.
- 4. Ascertain that the Engineer has received copies of notice to the Railroad and of the Railroad's response thereto.

#### 5. CONSTRUCTION PROCEDURES:

#### A. General:

Construction work and operations by the Contractor on Railroad property shall be:

- 1. Subject to the inspection and approval of the Railroad.
- 2. In accord with the Railroad's written outline of specific conditions.
- 3. In accord with the Railroad's general rules, regulations and requirements including those relating to safety, fall protection and personal protective equipment.
- 4. In accord with these Special Provisions.

#### B. Excavation:

The subgrade of an operated track shall be maintained with edge of berm at least 10'-0" (3.05 m) from centerline of track and not more than 24" (600 mm) below top of rail. Contractor will not be required to make existing section meet this specification if substandard, in which case existing section will be maintained.

#### C. Excavation for Structures:

The Contractor will be required to take special precaution and care in connection with excavating and shoring pits, and in driving piles or sheeting for footings adjacent to tracks to provide adequate lateral support for the tracks and the loads which they carry, without disturbance of track alignment and surface, and to avoid obstructing track clearances with working equipment, tools or other material. The procedure for doing such work, including

need of and plans for shoring, shall first be approved by the Engineer and the Railroad Engineer, but such approval shall not relieve the Contractor from liability.

#### D. Blasting:

- 1. The Contractor shall obtain advance approval of the Railroad Engineer and the Engineer for use of explosives on or adjacent to Railroad property. The request for permission to use explosives shall include a detailed blasting plan. If permission for use of explosives is granted, the Contractor will be required to comply with the following:
- (a) Blasting shall be done with light charges under the direct supervision of a responsible officer or employee of the Contractor and a licensed blaster.
- (b) Electric detonating fuses shall not be used because of the possibility of premature explosions resulting from operation of two-way radios.
- (c) No blasting shall be done without the presence of an authorized representative of the Railroad. At least 72 hours advance notice to the person designated in the Railroad's notice of authorization to proceed (see Section 2. Notice of Starting Work) will be required to arrange for the presence of an authorized Railroad representative and such flagging as the Railroad may require.
- (d) Have at the job site adequate equipment, labor and materials and allow sufficient time to clean up debris resulting from the blasting without delay to trains, as well as correcting at his/her expense any track misalignment or other damage to Railroad property resulting from the blasting as directed by the Railway's authorized representative. If his/her actions result in delay of trains, the Contractor shall bear the entire cost thereof.

#### 2. The Railroad representative will:

- (a) Determine approximate location of trains and advise the Contractor the appropriate amount of time available for the blasting operation and cleanup.
- (b) Have the authority to order discontinuance of blasting if, in his/her opinion, blasting is too hazardous or is not in accord with these Special Provisions.

#### E. Maintenance of Railroad Facilities:

- 1. The Contractor will be required to maintain all ditches and drainage structures free of silt or other obstructions which may result from his/her operations and provide and maintain any erosion control measures as required. The Contractor will promptly repair eroded areas within Railroad rights-of-way and repair any other damage to the property of the Railroad or its tenants.
- 2. All such maintenance and repair of damages due to the Contractor's operations shall be done at the Contractor's expense.

#### F. <u>Storage of Materials and Equipment:</u>

Materials and equipment shall not be stored within 25' (7.6 m) of the centerline of Railroad's track or where they will interfere with Railroad operations, nor on the rights-of-way of the Railroad Company without first having obtained permission from the Railroad Engineer, and such permission will be with the understanding that the Railroad Company will not be liable for damage to such material and equipment from any cause and that the Railroad Engineer may move or require the Contractor to move, at the Contractor's expense, such material and equipment.

All grading or construction machinery that is left parked near the track unattended by a watchman shall be effectively immobilized so that it cannot be moved by unauthorized persons. The Contractor shall protect, defend, indemnify and save Railroad, and any associated, controlled or affiliated corporation, harmless from and against all losses, costs, expenses, claim or liability for loss or damage to property or the loss of life or personal injury, arising out of or incident to the Contractor's failure to immobilize grading or construction machinery.

#### G. Cleanup:

Upon completion of the work, the Contractor shall remove from within the limits of the Railroad rights-of-way, all machinery, equipment, surplus materials, falsework, rubbish or temporary buildings of the Contractor, and leave said rights-of-way in a neat condition satisfactory to the Chief Engineer of the Railroad or his/her authorized representative.

#### 6. DAMAGES:

- A. The Contractor shall assume all liability for any and all damages to his/her work, employees, servants, equipment and materials caused by Railroad traffic.
- B. Any cost incurred by the Railroad for repairing damages to its property or to property of its tenants, caused by or resulting from the operations of the Contractor, shall be paid directly to the Railroad by the Contractor.

#### 7. FLAGGING SERVICES:

#### A. When Required:

Under the terms of the agreement between the State and the Railroad, the Railroad has sole authority to determine the need for flagging required to protect its operations. In general, the requirements of such services will be whenever the Contractor's personnel or equipment are or are likely to be, working on the Railroad's right-of-way, or across, over, adjacent to, or under a track, or when such work has disturbed or is likely to disturb a Railroad structure or the Railroad roadbed or surface and alignment of any track to such extent that the movement of trains must be controlled by flagging.

Normally, the Railroad will assign one flagman to a project; but in some cases, more than one may be necessary, such as yard limits where three (3) flagmen may be required. However, if the Contractor works within distances that violate instructions given by the Railroad's authorized representative or performs work that has not been scheduled with the Railroad's authorized representative, a flagman or flagmen may be required full time until the project has been completed.

#### B. Scheduling and Notification:

- 1. Not later than the time that approval is initially requested to begin work on Railroad right-of-way, Contractor shall furnish to the Railroad and the State a schedule for all work required to complete the portion of the project within Railroad right-of-way and arrange for a job site meeting between the Contractor, the State, and the Railroad's authorized representative. Flagman or flagmen may not be provided until the job site meeting has been conducted and the Contractor's work scheduled.
- 2. The Contractor will be required to give the Railroad representative at least 10 working days of advance written notice of intent to begin work within Railroad right-of-way in accordance with this special provision. Once begun, when such work is then suspended at any time, or for any reason, the Contractor will be required to give the Railroad representative at least 3 working days of advance notice before resuming work on Railroad right-of-way. Such notices shall include sufficient details of the proposed work to enable the Railroad representative to determine if flagging will be required. If such notice is in writing, the Contractor shall furnish the Engineer a copy; if notice is given verbally, it shall be confirmed

#### Contract No. T201106304.01

in writing with copy to the Engineer. If flagging is required, no work shall be undertaken until the flagman, or flagmen is present at the job site. It may take up to 30 days to obtain flagging initially from the Railroad. When flagging begins, the flagman is usually assigned by the Railroad to work at the project site on a continual basis until no longer needed and cannot be called for on a spot basis. If flagging becomes unnecessary and is suspended, it may take up to 30 days to again obtain from the Railroad. Due to Railroad labor agreements, it is necessary to give 5 working days notice before flagging service may be discontinued and responsibility for payment stopped.

3. If, after the flagman is assigned to the project site, an emergency arises that requires the flagman's presence elsewhere, then the Contractor shall delay work on Railroad right-of-way until such time as the flagman is again available. Any additional costs resulting from such delay shall be borne by the Contractor and not the State or Railroad.

#### C. Payment:

- 1. The State will be responsible for paying the Railroad directly for any and all costs of flagging which may be required to accomplish the construction.
- 2. The charge to the State by the Railroad will be the actual cost based on the rate of pay for the Railroad's employees who are available for flagging service at the time the service is required.
- 3. Work by a flagman in excess of 8 hours per day or 40 hours per week, but not more than 12 hours a day will result in overtime pay at 1 and 1/2 times the appropriate rate. Work by a flagman in excess of 12 hours per day will result in overtime at 2 times the appropriate rate. If work is performed on a holiday, the flagging rate is 2 and 1/2 times the normal rate.
- 4. Railroad work involved in preparing and handling bills will also be charged to the State. Charges to the State by the Railroad shall be in accordance with applicable provisions of Subchapter B, Part 140, Subpart I and Subchapter G, Part 646, Subpart B of the Federal-Aid Policy Guide issued by the Federal Highway Administration on December 9, 1991, including all current amendments. Flagging costs are subject to change.

#### D. Verification:

1. The Contractor and State will review and sign the Railroad flagman's time sheet (Form 11123), attesting that the flagman was present during the time recorded. Flagmen may be removed by the Railroad if form is not signed. If flagman is removed, the Contractor will not be allowed to re-enter the Railroad right-of-way until the issue is resolved. Any complaints concerning flagman or flagmen must be resolved in a timely manner. If need for flagman or flagmen is questioned, please contact Railroad's Engineer, Grade Separation Structures (404)529-1641. All verbal complaints will be confirmed in writing by the Contractor within 5 working days with a copy to the Engineer. Address all written correspondence to:

#### **CROSSING SURFACES**

Office of Chief Engineer Bridges & Structures Norfolk Southern Corp. 99 Spring Street, SW Atlanta, Georgia 30303 Attn: T. D. Wyatt Engineer Grade Separation 2. The Railroad flagman assigned to the project will be responsible for notifying the Project Engineer upon arrival at the job site on the first day (or as soon thereafter as possible) that flagging services begin and on the last day that he/she performs such services for each separate period that services are provided. The Project Engineer will document such notification in the project records. When requested, the Project Engineer will also sign the flagman's diary showing daily time spent and activity at the project site.

#### 8. HAUL ACROSS RAILROAD:

- A. Where the Plans show or imply that materials of any nature must be hauled across a Railroad, unless the Plans clearly show that the State has included arrangements for such haul in its agreement with the Railroad, the Contractor will be required to make all necessary arrangements with the Railroad regarding means of transporting such materials across the Railroad. The Contractor will be required to bear all costs incidental to such crossings whether services are performed by his/her own forces or by Railroad personnel.
- B. No crossing may be established for use of the Contractor for transporting materials or equipment across the tracks of the Railroad Company unless specific authority for its installation, maintenance, necessary watching and flagging thereof and removal, until a private crossing agreement has been executed between the Contractor and Railroad.

#### 9. WORK FOR THE BENEFIT OF THE CONTRACTOR:

- A. All temporary or permanent changes in wire lines or other facilities which are considered necessary to the project are shown on the Plans; included in the force account agreement between the State and the Railroad or will be covered by appropriate revisions to same which will be initiated and approved by the State and/or the Railroad.
- B. Should the Contractor desire any changes in addition to the above, then he/she shall make separate arrangements with the Railroad for same to be accomplished at the Contractor's expense.

#### 10. COOPERATION AND DELAYS:

- A. It shall be the Contractor's responsibility to arrange a schedule with the Railroad for accomplishing stage construction involving work by the Railroad or tenants of the Railroad. In arranging his/her schedule he/she shall ascertain, from the Railroad, the lead time required for assembling crews and materials and shall make due allowance therefore.
- B. No charge or claim of the Contractor against either the State or the Railroad will be allowed for hindrance or delay on account of railway traffic; any work done by the Raiload or other delay incident to or necessary for safe maintenance of railway traffic or for any delays due to compliance with these special provisions.

#### 11. TRAINMAN'S WALKWAYS:

Along the outer side of each exterior track of multiple operated track, and on each side of single operated track, an unobstructed continuous space suitable for trainman's use in walking along trains, extending to a line not less than 10′ (3.05 m) from centerline of track, shall be maintained. Any temporary impediments to walkways and track drainage encroachments or obstructions allowed during work hours while Railroad's protective service is provided shall be removed before the close of each work day. If there is any excavation near the walkway, a handrail, with 10′ - 0″ (3.05 m) minimum clearance from centerline of track, shall be placed.

#### 12. GUIDELINES FOR PERSONNEL ON RAILROAD RIGHT-OF-WAY:

A. All persons shall wear hard hats. Appropriate eye and hearing protection must be used. Working in shorts is prohibited. Shirts must cover shoulders, back and abdomen. Working in tennis or jogging shoes, sandals, boots with high heels, cowboy and other slip-on type boots is prohibited. Hard-sole, lace-up footwear, zippered boots or boots cinched up with

#### Contract No. T201106304.01

- straps which fit snugly about the ankle are adequate. Safety boots are strongly recommended.
- B. No one is allowed within 25' (7.6 m) of the centerline of track without specific authorization from the flagman.
- C. All persons working near track while train is passing are to lookout for dragging bands, chains and protruding or shifted cargo.
- D. No one is allowed to cross tracks without specific authorization from the flagman.
- E. All welders and cutting torches working within 25' (7.6 m) of track must stop when train is passing.
- F. No steel tape or chain will be allowed to cross or touch rails without permission.

#### 13. GUIDELINES EQUIPMENT ON RAILROAD RIGHT-OF-WAY:

- A. No crane or boom equipment will be allowed to set up to work or park within boom distance plus 15' (4.6 m) of centerline of track without specific permission from Railroad official and flagman.
- B. No crane or boom equipment will be allowed to foul track or lift a load over the track without flag protection and track time.
- C. All employees will stay with their machines when crane or boom equipment is pointed toward track.
- D. All cranes and boom equipment under load will stop work while train is passing (including pile driving).
- E. Swinging loads must be secured to prevent movement while train is passing.
- F. No loads will be suspended above a moving train.
- G. No equipment will be allowed within 25' (7.6 m) of centerline of track without specific authorization of the flagman.
- H. Trucks, tractors or any equipment will not touch ballast line without specific permission from railroad official and flagman.
- I. No equipment or load movement within 25' (7.6 m) or above a standing train or railroad equipment without specific authorization of the flagman.
- J. All operating equipment within 25′ (7.6 m) of track must halt operations when a train is passing. All other operating equipment may be halted by the flagman if the flagman views the operation to be dangerous to the passing train.
- K. All equipment, loads and cables are prohibited from touching rails.
- L. While clearing and grubbing, no vegetation will be removed from Railroad embankment with heavy equipment without specific permission from the Railroad Engineer and flagman.
- M. No equipment or materials will be parked or stored on Railroad's property unless specific authorization is granted from the Railroad Engineer.
- N. All unattended equipment that is left parked on Railroad property shall be effectively immobilized so that it cannot be moved by unauthorized persons.
- O. All cranes and boom equipment will be turned away from track after each work day or whenever unattended by an operator.

#### 14. INSURANCE:

- A. In addition to any other forms of insurance or bonds required under the terms of the Contract and specifications, the Prime Contractor will be required to carry insurance of the following kinds and amounts:
  - 1. Commercial General Liability Insurance having a combined single limit of not less than \$2,000,000 per occurrence for all loss, damage, cost and expense, including attorneys' fees, arising out of bodily injury liability and property damage liability during the policy period. Said policy shall include "explosion, collapse, and underground harzard" ("XCU") coverage, shall be endorsed to name Railroad specified in item A.2.c. below as an additional insured, and shall include a severability of interests provision.
  - 2. Railroad Protective Liability Insurance having a combined single limit of not less than \$2,000,000 each occurrence and \$6,000,000 in the aggregate applying separately to each annual period. If the project involves track over which passenger trains operate, the insurance limits required are not less than a combined single limit of \$5,000,000 each occurrence and \$10,000,000 in the aggregate applying separately to each annual period. Said policy shall provide coverage for all loss, damage or expense arising from bodily injury and property damage liability, and physical damage to property attributed to acts or omissions at the job site.

The standards for the Railroad Protective Liability Insurance are as follows:

The insurer must be rated A - or better by A.M. Best Company, Inc.

The policy must be written using one of the following combinations of Insurance Services Office ("ISO") Railroad Protective Liability Insurance Form Numbers:

CG 00 35 01 96 and CG 28 31 10 93; or CG 00 35 07 98 and CG 28 31 07 98.

The named insured shall read:

[Name of railroad that owns the track]; and Norfolk Southern Railway Company Three Commercial Place Norfolk, Virginia 23510-2191 Attn: Mr. Chris Bremus, Risk Manager

The description of operations must appear on the Declarations, must match the project description in this agreement, and must include the appropriate Department project and contract identification numbers.

The job location must appear on the Declarations and must include the city, state, and appropriate highway name/number.

The name and address of the prime contractor must appear on the Declarations.

The name and address of the Department must be identified on the Declarations as the "Involved Governmental Authority or Other Contracting Party".

Other endorsements/forms that will be accepted are:

Broad Form Nuclear Exclusion - Form IL 00 21 30-day Advance Notice of Non-renewal or cancellation Required State Cancellation Endorsement Quick Reference or Index Form CL/IL 240

#### Contract No. T201106304.01

Endorsements/forms that are NOT acceptable are:

Any Pollution Exclusion Endorsement except CG 28 31
Any Punitive or Exemplary Damages Exclusion
Known injury or Damage Exclusion form CG 00 59
Any Common Policy Conditions form
Any other endorsement/form not specifically authorized in item no. 2.h. above.

- B. If any part of the work is sublet, similar insurance, and evidence thereof as specified in A.1 above, shall be provided by or on behalf of the subcontractor to cover its operations on Railroad's right of way.
- C. Prior to entry on Railroad right-of-way, the original Railroad Protective Liability Insurance Policy shall be submitted by the Prime Contractor to the Department at the address below for its review and transmittal to the Railroad. In addition, certificates of insurance evidencing the Prime Contractor's and any subcontractors' Commercial General Liability Insurance shall be issued to the Railroad and the Department at the addresses below, and forwarded to the Department for its review and transmittal to the Railroad. The certificates of insurance shall state that the insurance coverage will not be suspended, voided, cancelled, or reduced in coverage or limits without (30) days advance written notice to Railroad and the Department. No work will be permitted by Railroad on its right-of-way until it has reviewed and approved the evidence of insurance required herein.

<u>STATE</u> <u>RAILROAD</u>

Mr. James Hoagland Contract Services Administrator Delaware Department of Transportation 800 Bay Road, Box 778 Dover, DE 19903 Mr. Chris Bremus Risk Manager Norfolk Southern Corp. Three Commercial Place Norfolk, VA 23510-2191

#### 15. FAILURE TO COMPLY:

In the event the Contractor violates or fails to comply with any of the requirements of these Special Provisions:

- A. The Railroad Engineer may require that the Contractor vacate Railroad property.
- B. The Engineer may withhold all monies due the Contractor on monthly statements.

Any such orders shall remain in effect until the Contractor has remedied the situation to the satisfaction of the Railroad Engineer and the Engineer.

#### 16. PAYMENT FOR COST OF COMPLIANCE:

The payment for the item shall be made for at the Contract unit price per Lump Sum bid for "Maintenance of Railroad Traffic", which price and payment shall constitute full compensation for maintaining Railroad traffic during the life of the project; submission of drawings and procedures to the Railroad; for all incidental costs imposed by the Railroad on the Contractor in accordance with the terms and conditions set in these Specifications; meeting all insurance requirements as described herein; for any cost incidental to or arising from the need to meet any or all requirements outlined, herein; for all materials, labor, tools, equipment, and incidentals necessary to complete the work.

#### **NOTE:**

As stated above in this specification, the Department will pay the Railroad directly for protective services required for this project. Should the Contractor wish to use a method or sequence of construction requiring more Railroad protective services than the method and sequence of construction shown in the Plans, cost for such extra Railroad protective services will be deducted from monies due the Contractor.

#### Contract No. T201106304.01

Also, the Contractor's attention is drawn to the portion of the second paragraph in Section 7. Flagging Services that reads:

"However, if the Contractor works within distances that violate instructions given by the Railroad's authorized representative or performs work that has not been scheduled with the Railroad's authorized representative, a flagman or flagmen may be required full time until the project has been completed."

If such "full time" flagging requirements are imposed by the Railroad because of the Contractor's negligence or willful disregard of Railroad requirements, the Contractor will be held responsible for extra cost involved. Time charges for flagging services provided, but not need for legitimate pursuit of construction will be recorded and charges for such flagging time will be deducted from monies due the Contractor.

There is approximately <u>4</u> freight trains that use this line per day.

09/16/09

#### 763643 - MAINTENANCE OF TRAFFIC - ALL INCLUSIVE

#### **Description:**

This item shall consist of furnishing, installing, maintaining and/or relocating the necessary temporary traffic control devices used to maintain vehicular, bicycle and pedestrian traffic, including persons with disabilities in accordance with the Americans with Disabilities Act, as amended. All work shall be performed in a manner that will provide reasonably safe passage with the least practicable obstruction to all users, including vehicular, bicycle and pedestrian traffic.

All requirements of the Delaware Manual on Uniform Traffic Control Devices (MUTCD), Part 6, herein referred to as the Delaware MUTCD. (latest edition with all revisions made up to the date of Advertisement of this project) shall apply for all temporary traffic control devices. Any, and all, control, direction, management and maintenance of traffic shall be performed in accordance with the requirements of the Delaware MUTCD, notes on the Plans, this specification, and as directed by the Engineer.

The Contractor shall be aware that the Case Diagrams and safety measures outlined in the Delaware MUTCD are for common construction situations and modifications may be warranted based on the complexity of the job. The Contractor shall submit justification for modifications to the Temporary Traffic Control Plan (TTCP) to the Engineer for approval prior to implementation.

The Department reserves the right to impose additional restrictions, as needed, for the operational movement and safety of the traveling public. The Department reserves the right to suspend the Contractor's operations until compliance with the Engineer's directive for remedial action, based on but not limited to the following reasons:

- 1. The Contractor's operations are not in compliance with the Delaware MUTCD, the specifications or the Plans.
- 2. The Contractor's operations have been deemed unsafe by the Traffic Safety Engineer or District Safety Officer.

#### **Materials and Construction Methods:**

The Contractor shall submit a Temporary Traffic Control Plan (TTCP) or a Letter of Intent to use the Plan recommended Delaware MUTCD Case Diagram(s) at or prior to the pre-construction meeting. The Contractor shall submit the TTCP for all Contractor and subcontractor work to be performed on the project for the Department's approval before the start of work.

When specified by a note in the Plans, the Contractor shall be required to have an American Traffic Safety Services Association (ATSSA) certified Traffic Control Supervisor on the project. The authorized designee must be assigned adequate authority, by the Contractor, to ensure compliance with the requirements of the Delaware MUTCD and provide remedial action when deemed necessary by the Traffic Safety Engineer or the District Safety Officer. The ATSSA certified Traffic Control Supervisor's sole responsibility shall be the maintenance of traffic throughout the project. This responsibility shall include, but is not limited to, the installation, operations, maintenance and service of temporary traffic control devices. Also required is the daily maintenance of a log to record maintenance of traffic activities, i.e., number and location of temporary traffic control devices; and times of installation, changes and repairs to temporary traffic control devices. The ATTSA Traffic Control Supervisor shall serve as the liaison with the Engineer concerning the Contractor's maintenance of traffic. The name, contact number and certification for the designated Traffic Control Supervisor shall be submitted at or prior to the pre-construction meeting. The cost of the ATSSA certified Traffic Control Supervisor shall be incidental to this item.

Temporary traffic control devices shall be maintained in good condition in accordance with the brochure entitled "Quality Guidelines for Temporary Traffic Control Devices", published by the American Traffic Safety Services Association (ATSSA). Any temporary traffic control devices that do not meet the quality guidelines shall be removed and replaced with acceptable devices. Failure to comply will result in work stoppage with time charges continuing to be assessed.

#### Contract No. T201106304.01

Any existing signs that conflict with any temporary or permanent construction signs shall be covered as needed or as directed by the Engineer. The cost for temporarily covering conflicting signs shall be incidental to this item.

Access to all transit stops located within the project limits shall be maintained unless otherwise directed by the Plans or the Engineer. Maintaining access shall include maintaining an area for the transit vehicle and also an accessible path for pedestrians to safely access the transit stop.

The Contractor shall notify the Engineer, in writing, no less than fourteen (14) calendar days prior to the start of any detour(s) and road closures. The Engineer will notify the following entities:

- Local 911 Center
- Local School Districts
- Local Post Offices
- DelDOT's Transportation Management Center (TMC)
- Town Managers
- Local Police
- DelDOT's Public Relations
- Delaware Transit Corporation (DTC)

Immediately prior to the implementation of any lane or road closures, the Engineer shall notify the DelDOT TMC at (302) 659-4600. Notifications shall also be provided when the closures are lifted. The Engineer shall notify TMC and the District Safety Officer if any lane closures cannot be removed prior to the end of the allowable work hours.

The Contractor shall notify the local 911 center if access to a fire hydrant is temporarily restricted. The Contractor shall provide written confirmation to the Engineer that the local 911 center has been notified.

If a detour is required during any part or the entire period of this Contract, an approved detour plan shall be obtained from the Department's Traffic Safety Section. All signs, barricades and other temporary traffic control devices required as part of the approved detour plan shall be installed and maintained by the Contractor on the route that is closed and on the detour route. Road closures without an approved detour plan shall not be allowed. If a road is closed without an approved detour plan, the Contractor's operations shall be stopped immediately.

The Contractor shall provide and maintain ingress and egress for each property abutting the construction area and each property located between the diversion points of any detour and the actual construction site. Construction activities which may temporarily or otherwise interfere with property access shall be coordinated in advance with the affected property owners.

The Contractor shall conduct construction operations in a manner which will minimize delays to traffic, and shall meet the following requirements:

- 1. If work is being performed within 200 feet in any direction of an intersection that is controlled by a traffic signal, the flagger(s) shall direct the flow of traffic in concert with the traffic signals in construction areas to avoid queuing, unless active work prohibits such action. The flagger shall direct traffic to prevent traffic from queuing through an intersection (i.e., blocking an intersection). Only a Traffic Officer may direct traffic against the operation of a traffic signal and only until the operation occurring within the intersection is completed.
- 2. When a lane adjacent to an open lane is closed to travel, the temporary traffic control devices shall be set 2 feet (0.61 m) into the closed lane from the edge of the open lane, unless an uncured patch exists or actual work is being performed closer to the open lane with minimum restriction to traffic.
- 3. Except for "buffer lanes" on high volume and/or high speed roadways, lanes shall not be closed unless construction activity requiring lane closure is taking place, or will take place within the next hour. Lanes shall be reopened immediately upon completion of the work. Moving operations will require the lane closures be shortened as the work progresses and as traffic conditions warrant to minimize the length of the closure. The Contractor shall conduct construction operations in a manner so as to minimize disruption to traffic during

peak hours and periods of heavy flow. The Department reserves the right to stop or change the Contractor's operations, if in the opinion of the Engineer, such operations are unnecessary at that time or the operations are unnecessarily impeding traffic.

4. Work in the vicinity of traffic signals, shall be scheduled to minimize the time during which the signal is operated without detectors, and prior approval from the Engineer shall be required. TMC shall be notified in advance of cutting a loop detector, and be immediately notified once the loop detector has been reinstalled. The Contractor shall provide sufficient advance notice of the loop detector work with the Engineer to ensure the aforementioned requirements are met.

It is required that all temporary traffic control work and related items shall either be performed entirely by the Contractor's own organization, or totally subcontracted. Maintenance of equipment shall not be subject to this requirement.

Any deficiencies related to temporary traffic control that are reported to the Contractor in writing shall be corrected within 24 hours or as directed by the Engineer. Failure to comply will result in non-payment for those devices that are found to be deficient for the duration of the deficiency. Serious deficiencies that are not corrected immediately shall result in suspension of work until items identified are brought back into compliance.

At the end of each day's work, the Contractor shall correct all pavement edge drop-offs in accordance with Table 6G-1 in the Delaware MUTCD. This corrective work shall be accomplished with Temporary Roadway Material (TRM) unless an alternate method is specified in the Plans. All ruts and potholes shall be filled with TRM as soon as possible but no later than the end of each work day. Placement and Payment of TRM shall be completed in accordance with Section 402 of the Standard Specifications. If temporary elimination of a drop-off hazard cannot be accomplished, then the area should be properly marked and protected with temporary traffic control devices such as temporary barricades, warning signs, flashing lights, etc. as required by Section 6G.21 of the Delaware MUTCD.

All open trench excavation accessible by vehicular traffic must be backfilled prior to the end of each working day. Steel plates shall not be used except in emergency situations and only with prior written approval from the Engineer unless otherwise directed by the Plans.

The Contractor shall submit, at or prior to the preconstruction meeting, detailed drawings including but not limited to existing striping lengths, lane and shoulder widths, turn lane lengths, locations of stop bars, turn arrows, crosswalks and railroad crossings. The drawings shall depict the existing pavement markings for each project location. These drawings will be reviewed by the Department's Traffic Section to determine the need for modification(s) for compliance with the Delaware MUTCD. Temporary pavement markings, on the final pavement surface, shall match the Plan dimensions and layout or the approved drawings of the permanent markings in compliance with Section 3 of the Delaware MUTCD. All conflicting or errant striping shall be removed as directed by the Engineer in compliance with the specifications for Item 748530 (Removal of Pavement Striping).

At the end of each day's operation and before traffic is returned to unrestricted roadway use, temporary striping shall be utilized when the existing pavement is milled and hot mix will not be placed the same day or more than a single course of hot mix is to be placed or permanent roadway striping cannot be placed on the same day as the placement of the final course of hot mix. Placement of temporary striping shall receive prior approval from the Engineer and the contractor shall apply temporary pavement markings in accordance with the requirements of Section 748 of Delaware Standard specifications and the Delaware MUTCD. Payment for temporary pavement striping shall be made at the unit price bid for item 748 - Temporary Striping. Payment for final striping will be included in the applicable striping item.

The Contractor shall have temporary striping/delineating materials (such as raised markers, tape, and other approved materials) available at the job site for verification by the Department prior to starting the hotmix paving operation on roads to be immediately opened to traffic. These materials shall be used by the Contractor for temporary markings if he/she fails to apply temporary marking paint, etc., as required by the Delaware MUTCD. No paving operations on roads to be immediately opened to traffic will be allowed unless such verification has been made for the availability of the materials at the job site.

#### **Certification:**

Temporary traffic control devices used on all highways open to the public in this State shall conform to the Delaware MUTCD. All devices shall be crashworthy in accordance with the National Cooperative Highway Research Program (NCHRP) Report 350, the memorandum issued August 28, 1998 by The USDOT Federal Highway Administration, and/or in accordance with the latest edition of the Manual for Assessing Safety Hardware (MASH), published by the American Association of State Highway and Transportation Officials (AASHTO).

The Contractor shall submit certification for temporary traffic control devices or vendors used specifically on this project at or prior to the pre-construction meeting.

Certification of compliance with NCHRP report 350 and/or MASH is required for the following categories of temporary traffic control devices:

<u>Category I</u> contains small and lightweight channelizing and delineating control devices which includes cones, tubular markers, flexible delineator post and drums, all without any accessories or attachments.

<u>Category II</u> includes temporary traffic control devices that are not expected to produce significant vehicular velocity changes to impacting vehicles. These devices which shall weigh 45 kg or less, include Type I, II and III barricades, portable sign supports with signs, and intrusion alarms. Also included are drums, cones, and vertical panels with accessories or attachments.

<u>Category III</u> includes temporary traffic control devices that are expected to cause significant vehicular velocity changes to impacting vehicles. These devices which weigh more than 45 kg include temporary barrier, temporary impact attenuators, and truck-mounted attenuators.

<u>Category IV</u> includes portable or trailer-mounted devices such as arrow panels, variable message signs, temporary traffic signals and temporary area lighting.

For Category I devices, the manufacturer or Contractor may self-certify that the devices meet the NCHRP-350 and/or MASH criteria. The Contractor shall supply the Federal Highway Administration's NCHRP-350 and/or MASH acceptance letter for each type of device that falls under Category II and III devices.

#### **Basis of Payment:**

Payment will be made at the Lump Sum price for "Maintenance of Traffic", for which price and payment constitutes full compensation for all maintenance of traffic activities accepted by the Engineer, which shall include the cost of furnishing and relocating permanent and temporary traffic control signs, traffic cones or drums, submission of temporary traffic control plan(s), submission of existing pavement marking drawings, submission of all required certifications, labor, equipment and incidentals necessary to complete the item. Payment to furnish and maintain other temporary traffic control devices including but not limited to Portable P.C.C. Safety Barrier, Truck Mounted Attenuators, Portable Changeable Message Signs, Arrow Panels and Portable Light Assemblies will be made at the contract unit price for each item.

#### **NOTE**

If the Contractor does not complete the Contract work within the Contract <u>completion time</u> (including approved extension time), the Contractor shall be responsible for providing the necessary temporary traffic control devices that are required to complete any remaining work. The costs of such temporary traffic control shall be borne by the Contractor. No additional payment will be made to the Contractor to maintain traffic in accordance with the Delaware MUTCD, contract plans and specifications. Temporary traffic control items include, but not be limited to, warning lights, warning signs, barricades, plastic drums, P.C.C. safety barrier, flaggers, traffic officers, arrow panels, message boards, and portable impact attenuators.

A breakout sheet is attached to the Proposal that lists the locations for Maintenance of Traffic. The Contractor shall specify a cost for each location. The lump sum price for Item 763643 shall be the sum of the cost for all locations listed. The calendar days on the breakout sheet will only be used to determine the compensation for maintenance of traffic activities directly associated with new items of work at and/or

#### Contract No. T201106304.01

extended limits of the original Contract location(s); and/or quantity additions to the original Contract bid item(s) which have been added after the Contract is deemed substantially complete by the Engineer and the Contract time has been stopped in accordance with subsection 105.20 and then only if the Original Contract Duration, including all approved time extensions, has been fully exhausted. Repair or replacement of defective work will not be considered for any additional maintenance of traffic compensation. The completed breakout sheet shall be attached to the Bid Proposal. Failure to submit the breakout sheet with the Bid Proposal will result in it being declared non responsive and rejected.

The Department reserves the right to delete from the Contract one or more of the locations listed and the lump sum price to be paid will be reduced in accordance with the Contractor's cost listed for that/those location(s). There will be no extra compensation to the Contractor if such deletion is made.

1/19/2011



#### STATE OF DELAWARE

#### **DEPARTMENT OF TRANSPORTATION**

800 BAY ROAD
P.O. BOX 778
DOVER, DELAWARE 19903

CAROLANN WICKS, P.E. SECRETARY

#### UTILITY STATEMENT

STATE CONTRACT No. T201106304 F.A.P. No. ESTP-2011(08) Project I.D. No. 11-06304 Pavement & Rehabilitation, South II-IV, 2011

#### SUSSEX COUNTY

No utility relocation involvement is anticipated, should any conflicts be encountered during construction requiring adjustments and/or relocation of the aforementioned utilities' existing facilities, the necessary relocation work shall be accomplished by the respective agencies, as directed by the District Engineer.

Any adjustments and/or relocations of municipally owned sewer or water facilities shall be done by the State's contractor in accordance with the respective agencies' standard specifications as directed by the District Engineer.

#### **General Notes**

- 1. The Contractor's attention is directed to Section 105.09 <u>Utilities</u>, Delaware Standard Specifications, August 2001. The Contractor shall contact Miss Utility (1-800-282-8555) two working days prior to any excavation. The Contractor is responsible for the support and protection of all utilities when excavating. The Contractor is responsible for ensuring proper clearances, including safety clearances, from overhead utilities for construction equipment. The Contractor is advised to check the site for access purposes for his equipment and, if necessary, make arrangements directly with the utility companies for field adjustments for adequate clearances.
- 2. It is understood and agreed that the Contractor has considered in his bid all permanent and temporary utility appurtenances in their present and relocated positions as shown on the plans or described in the Utility Statement or are readily discernible and that no additional compensation will be allowed for any delays, inconvenience, or damage due to any interference from the utility facilities and appurtenances or the operation of moving them, except that the Contractor may be granted an equitable extension of time.



Page 2 State Contract No. 201106304 Pavement & Rehabilitation, South II-IV, 2011 Continued, General Notes

> 3. Coordination and cooperation among the Utility Companies and the State's Contractor are of prime importance. Therefore, the Contractor is directed to contact the following Utility Company representatives with any questions regarding this work prior to submitting bids and work schedules. Proposed work schedules should reflect the Utility Companies' proposed relocations. The Utility Companies do not work on weekends or legal holidays.

#### DIVISION OF TRANSPORTATION SOLUTIONS

#### STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION PO BOX 778 DOVER, DELAWARE 19903

#### **CERTIFICATE OF RIGHT-OF-WAY STATUS**

#### STATE PROJECT NO. T201106304

F.A.P. No. N/A for R/W

#### PAVE AND REHABILITATION, SOUTH II-IV, 2011 TOWNS OF BRIDGEVILLE, DELMAR, LAUREL, MILLSBORO

#### SUSSEX COUNTY

**Certificate of Right-of-Way Status – 100%** 

As required by 23CFR Part 635, all necessary right-of-way has been acquired in accordance with current State/Federal rules and regulations covering the acquisition of real property.

This is to certify that all project right-of-way is currently available in accordance with the project right-of-way plans.

It is further certified that there were no individuals or families displaced by this project. Therefore the provisions of 49 CFR Part 24 is not applicable to the project.

There are no improvements to be removed or demolished as part of this project.

REAL ESTATE SECTION

/s/

Carol V. O'Donoghue Assistant Chief, Real Estate



#### STATE OF DELAWARE

#### DEPARTMENT OF TRANSPORTATION

800 BAY ROAD
P.O. BOX 778
DOVER, DELAWARE 19903

CAROLANN WICKS, P.E.
SECRETARY

March 17, 2011

#### **ENVIRONMENTAL REQUIREMENTS**

FOR

State Contract No. T201106304 Federal Aid No.: None

Contract Title: Pavement and Rehabilitation, South II-IV, 2011

In accordance with the procedural provisions for implementing the National Environmental Policy Act of 1969, as amended, the referenced project has been processed through the Department's Environmental Review Procedures and has been classified as a Level D/ Class II Action.

Due to the nature of the proposed construction activities, permits are not required for this project. However, the following construction requirements <u>and</u> special provisions have been developed to minimize and mitigate impact to the surrounding environs. These requirements by DelDOT not specified within the contract, but listed below, are the responsibility of the contractor and is subject to risk of shut down at the contractor's expense if not followed.

#### GENERAL REQUIREMENTS:

- 1. All construction debris, excavated material, brush, rocks, and refuse incidental to such work shall be placed either on shore above the influence of flood waters or on some suitable dumping ground.
- 2. That effort shall be made to keep construction debris from entering adjacent waterways or wetlands. Any debris that enters those areas shall be removed <u>immediately</u>.
- 3. The disposal of trees, brush, and other debris in any stream corridor, wetland, surface water, or drainage area is <u>prohibited</u>.



# CANNOT BE

**BID PROPOSAL FORMS** 

CONTRACT <u>T201106304.01</u>

BIDDDING

#### DELAWARE DEPARTMENT OF TRANSPORTATION PAGE: SCHEDULE OF ITEMS DATE:

CONTRACT ID: T201106304.01

PROJECT(S): T201106304

All figures must be typewritten.

INE	ITEM DESCRIPTION		APPROX.			BID AM	
NO I	DESCRIPTION	l Q	UANTITY   ND UNITS				
CTION	0001 Category 0001						
	02000 EXCAVATION AND MBANKMENT	    CY	834.000			     	
020   B	02005 GRADED AGGREGAT ASE COURSE, TYPE B		212.000				
3 030 S	04508 BITUMINOUS TABTLIZED FULL-DEPTH ECLAMATION	    SY	150203.000				2
040   P	01576 RECYCLED ASPHAI AVEMENT	T	1350.000				
050 B  B	01667 SUPERPAVE, ITUMINOUS CONCRETE ASECOURSE, 160 YRATIONS, PG 64-22	    TON	11.000				
I P	ATCHING						
060 D	01696 ENTRANCE, RIVEWAY AND NTERSECTINGSTREET AVING SURCHARGE	TON	562.000	1		K	
	01713 EMULSIFIED SPHALT	       GAL	422048.000			   	
080   T   P	01801 WMA, SUPERPAVE, YPE C, 160 GYRATIONS, G 64-22 (CARBONATE TONE)		17783.000		V		<b>I</b>

PAGE: DATE:

#### DELAWARE DEPARTMENT OF TRANSPORTATION SCHEDULE OF ITEMS

CONTRACT ID: T201106304.01 PROJECT(S): T201106304

All figures must be typewritten.

LINE NO	!	APPROX.   QUANTITY   AND UNITS	UNIT PRICE	BID AMOUNT 
0090	  406001 HOT-MIX PATCHING   		<u>-</u> I	
0100	705002 P.C.C. SIDEWALK,  6"	   567.000  SF	 	     
0110	705519 PATTERNED   PORTLAND CEMENT CONCRETE   SIDEWALK, 6"			     
0120	732004 TOPSOIL (TON)   	1730.000		R
	734013 PERMANENT GRASS  SEEDING, DRY GROUND	20929.000		
	735534 SOIL RETENTION  BLANKET MULCH, TYPE 4	   20929.000  SY		   
0150	743004 FURNISH AND  MAINTAIN PORTABLE  CHANGEABLE MESSAGE SIGN 	   42.000  EADY	H()	R
0160	743010 FURNISH AND  MAINTAIN TRUCK MOUNTED  ATTENUATOR, TYPE II	70.000  EADY		
	743052 FLAGGER, SUSSEX COUNTY, STATE	   2460.000  HOUR	42.00000	103320.0
	743064 FLAGGER, SUSSEX	   370.000	60.90000	22533.0

PAGE: DATE:

#### DELAWARE DEPARTMENT OF TRANSPORTATION SCHEDULE OF ITEMS

CONTRACT ID: T201106304.01

PROJECT(S): T201106304

All figures must be typewritten.

LINE			APPROX.	UNIT I	PRICE	BID AMC	UNT
NO	DESCRIPTION		UANTITY   ND UNITS	DOLLARS	CT	S   DOLLARS	CTS
190	746774 SUPPLY AND  INSTALLATION OF LOOP  DETECTOR WIRE	      LF	   115.000 			     	
	746776 LOOP DETECTOR SPLICE	    EACH	1.000			     	
210	748014 PERMANENT PAVEMENT STRIPING, ALKYD-THERMOPLASTIC, 4"	      LF	300.000				
0220	748015 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	      SF	545.000				3
0230	748017 PERMANENT PAVEMENT STRIPING, ALKYD-THERMOPLASTIC, 6"	    LF 	300.000  				
0240	748019 TEMPORARY MARKINGS, PAINT, 4"	    LF	305400.000				
250	748026 TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	  SF	1089.000				_
260	748506 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, 4"		152700.000  			   	
0270	758000 REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	  SY 	63.000				1

PAGE:

DATE:

SCHEDULE OF ITEMS

CONTRACT ID: T201106304.01

PROJECT(S): T201106304

All figures must be typewritten.

	ITEM	APPROX.		BID AMOUNT	
NO	DESCRIPTION	QUANTITY     AND UNITS	DOLLARS   CTS		
	60509 RUMBLE STRIPS, JLL LANE WIDTH	300.000		   	
76   76   0290	61001 BUTT JOINTS, HOT	5033.000		   	
76   76   0300	62001 SAW CUTTING, HOT	   1060.000  LF			
	52002 SAW CUTTING, DNCRETE, FULL DEPTH	190.000   LF		R	
76   320   -	63000 INITIAL EXPENSE	  LUMP 	LUMP		
	63502 MAINTENANCE OF AILROAD TRAFFIC	  LUMP 	LUMP		
	63643 MAINTENANCE OF RAFFIC, ALL INCLUSIVE	  LUMP	LÜMP	R	
	SECTION 0001 TOTAL				
	TOTAL BID	1			

## BIDDDING

## CANNOT BE

#### **BREAKOUT SHEETS**

THE FOLLOWING SHEETS MUST BE COMPLETED AND RETURNED WITH THE PROPOSAL AT THE TIME OF BID. FAILURE TO COMPLETE THE BREAKOUT SHEETS AS REQUIRED WILL RESULT IN THE BID BEING DECLARED NON-RESPONSIVE AND WILL NOT BE CONSIDERED. BREAKOUT SHEETS MUST BE COMPLETED REGARDLESS OF WHETHER BIDDING BY ELECTRONIC MEANS OR TYPEWRITTEN HARD COPY.

# BIDDDING

SECTION			ONTRACT NO	D.T201106304			
	ITEM 763643 - Maintenance of Traffic- All Inclusive						
Location No.	Location - Description	MOT Case Number	Unit of Measurement	Unit Price	Calendar Days		
1	EAST POPLAR STREET	6 - TRAVEL LANES	L.S.	\$			
		DETOUR	L.S.	\$			
2	DUBLIN HILL ROAD	6 - TRAVEL LANES	L.S.	\$			
		DETOUR	L.S.	\$			
3	WESLEY CHURCH ROAD	6 - TRAVEL LANES	L.S.	\$			
	TICED	DETOUR	L.S.	\$			
		H	IK				
4	OLD STAGE ROAD	6 - TRAVEL LANES	L.S.	\$			
		DETOUR	L.S.	\$			
5	DELAWARE AVENUE	6 - TRAVEL LANES	L.S.	\$			
	KIIIII	DETOUR	L.S.	\$			
			1 (				
	Total Lump Sum Bid for Item No. 763643 - Maintenance	e of Traffic - All Inclusive			Total Days*		
	(LS Bid Price for 763643)  *Total Days should equal original contract duration						

## "ATTENTION"

### TO BIDDERS

This Bid Proposal includes breakout sheets. The breakout sheets MUST ACCOMPANY the bid proposal at the time of bid. Failure to return completed breakout sheets WILL RESULT in the bid proposal being declared non-responsive and REJECTED as irregular.

#### SUBMISSIONS REQUIRED AT THE TIME OF BID

- 1. Copy(ies) of the American Traffic Safety Services Association (ATSSA) Certification(s) when listed in the applicable plan notes
- 2. Standard Specification Section 110.08 Site Reviewer requires that the name and DNREC certification number of each Site Reviewer if required shall be submitted to the Department at the time of bid. The level of certification and number required are listed in the applicable plan notes.
- 3. Proposed Trainee Plans as required. Number of required programs is listed in the Training Special Provisions within Contract General Notices. The program(s) must be submitted with 10 Calendar Days of notification of apparent low bidder status. Contract Award will not take place until acceptable On-the-Job (OJT) program plans are received by the Civil Rights Group of the Department.

Note: Items 1. and 2. above require copies of the current certifications for those individuals proposed for use on this Contract

Failure of the apparent low bidder to present copies of the required certifications and/or an acceptable OJT Trainee Programs within ten (10) calendar days after the bid opening shall create a rebuttable presumption that the bid is not responsive.

# CAN BIDDING

#### **CERTIFICATION**

Contract No. \_T201106304.01 \_

The undersigned bidder,			1.	1 1	whose a	ddress is _	
hereby certifies the fo	llowing:		and t	elepnone n	umber is		
I/We have carefully specifications, and will be boun in accordance with such award said plans and specifications shoof construction, and to do all the said contract within the time a Transportation, and at the unit	d, upon awa , a contract all be a par e work and and as requ	ard of this c t with nece t, to provid to furnish iired in acc	contract by the ssary surety e all necessa all the mater cordance wi	ne Departm bond, of vary maching rials necess th the requ	nent of Trans which contra ery, tools, la sary to perfor uirements of	portation, to proper this proper this proper the portage of the Department of the De	o execute posal and ner means nplete the
The foregoing quantitic comparison of bids. The Depart portion of the work as may be defor any item will not be regarded the time allowed for the complete the time allowed for the complete Accompanying this proof Transportation, for at least of forfeited as liquidated damages contract with necessary bond, a Transportation, under the condition the award of the contract as prodeposit is to be returned to the Title 30, of the Delaware Code	rtment of T eemed neced as a suffection of the oposal is a steen (10) per in case thing when requi- itions of this byided in the undersigned	cransportation of example continuous work, exception of example continuous proposal red, for the is proposal, the requirement of the continuous proposal continuous pr	on may increpedient. And for an inept as provided or a security for total amount is accepted, the performant, within tweenent and specific provided in the security of the performant, within tweenent and specific provided in the security of the security o	rease or decrease or deded in the decrease or decrease	crease the are crease or decerease or decerease in the contract.  dder assigned or opposal, who dersigned signed signed signed signed attacks thereto attacks.	nount of an crease in the che unit price and to the Denich deposition that I fail to the Department of official ched; other	e quantity es, nor in epartment t is to be execute a rtment of notice of
By submission of this p as to its own organization, under							
1. The prices in collusion, con bidder or with Unless requires have not been	sultation, of any compe d by law, th	communica titor for the ne prices wh	ation, or A e purpose of hich have be	greement restricting en quoted	with any or competition in this prope	ther n. osal	
the bidder, dire the opening of 3. No attempt has person, partner the purpose of	ectly or ind proposals. been made ship, or con	irectly, to a e or will be rporation to	any other bio made by the submit or r	dder or cor bidder to i	npetitor prion	or to	
I/We acknowledge rece	eipt and inc	corporation	of addenda	to this pro	posal as foll	ows:	
No. Date No.	Date	No.	Date	No.	Date	No.	Date
(FAILURE TO ACKNOWL BEING DECLARED NON-R			F ALL AD	DENDA '	WILL RES	ULT IN T	THE BID

	· · · · · · · · · · · · · · · · · · ·	day of	in the year of our Lord two thousand and	
	(20).			
			Name of Bidder (Organization)	
	Corporate	By:		
	Seal	·	Authorized Signature	
Attest				
			Title	
SWOR	N TO AND SUBSCRIBED	BEFORE ME this	day of, 20	
	Notary			
	Seal		Notary	

#### **BID BOND**

TO ACCOMPANY PROPOSAL (Not necessary if security is used)

KNOW ALL MEN BY THESE PRES	SENTS That:	
of	in the County of	and State of
as <b>Principal</b> , and		of in the
as Principal, and County of and State of	as <b>Surety</b> , legally a	uthorized to do business in the State of
Delaware (" <b>State</b> "), are held and firmly unto the	ne <b>State</b> in the sum of	
Dollars (\$	), or	percent not to exceed
	Dollars (\$	) of amount of bid on Contract
NoT201106304.01, to be paid to the <b>Stat</b>		
("DelDOT") for which payment well and truly		
executors, administrators, and successors, joint	ly and severally for and	a in the whole firmly by these presents.
NOW THE CONDITION OF THE O	DI ICATION IS SUC	II That if the above beauther Drivainal
NOW THE CONDITION OF THIS O who has submitted to the <b>DelDOT</b> a certain pr		
materiel and/or services within the <b>State</b> , shall		
truly enter into and execute this Contract as m		
the <b>DelDOT</b> , this Contract to be entered into w		
thereof in accordance with the terms of said		
remain in full force and virtue.	Toposui, inon unis con	
Sealed with seal and dated this	day of in	the year of our Lord two thousand and
(20).	•	-
SEALED, AND DELIVERED IN THE		
presence of		
'		2711
	Name	of Bidder (Organization)
Company	Dru	
Corporate Seal	By:	Authorized Signature
Seal	P	tutionzed Signature
Attest		
Titos.		Title
<b>K                                    </b>		
		Name of Surety
		-
Witness:	Ву:	

Title