



STATE OF DELAWARE  
**DEPARTMENT OF TRANSPORTATION**  
800 BAY ROAD  
P.O. Box 778  
DOVER, DELAWARE 19903

JENNIFER COHAN  
SECRETARY

**VIA OVERNIGHT DELIVERY**

June 27, 2018

Contract No. T201780102.01  
St. George's Maintenance Yard Entrance Improvements  
New Castle County

Ladies and Gentlemen:

Enclosed is Addendum No. 1 for the referenced contract consisting of the following:

1. The Bid Proposal Cover, revised, to be substituted for the same page in the Proposal.
2. One (1) page, Table of Contents, page iv, revised, to be substituted for the same page in the proposal.
3. Eight (8) pages, Special Provision 763501-Construction Engineering, has been added to the Proposal.
4. One (1) page, Special Provision 710500-Water Main and Accessories, page 18, revised, to be substituted for the same page in the Proposal.
5. One (1) page, Special Provision 711501-Sanitary Sewer System, page 28, revised, to be substituted for the same page in the Proposal.
6. Four (4) pages, Bid Proposal Form, pages 3, 4, 5 and 6 revised, to be substituted for the same pages in the Proposal. Item Number 763501-Construction Engineering has been added.
7. Expedite File Disc, Amendments No. 1.

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,

*~signature on file~*

Robert A. Kovacs  
Competitively Bid Contracts Coordinator  
Delaware Department of Transportation

STATE OF DELAWARE



DEPARTMENT OF TRANSPORTATION

BID PROPOSAL

for

CONTRACT T201780102.01

St. George's Maintenance Yard Entrance Improvements

New Castle County

ADVERTISEMENT DATE: June 11, 2018

COMPLETION TIME: 218 Calendar Days

SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION  
DELAWARE DEPARTMENT OF TRANSPORTATION  
AUGUST 2016

Bids will be received in the Bidder's Room at the Delaware Department of Transportation's Administration Building, 800 Bay Road, Dover, Delaware prior to 2:00 P.M. local time July 3, 2018

**TABLE OF CONTENTS**

**GENERAL DESCRIPTION..... i**  
LOCATION..... i  
DESCRIPTION..... i  
COMPLETION TIME..... i  
PROSPECTIVE BIDDERS NOTES..... i  
CONSTRUCTION ITEMS UNITS OF MEASURE..... iii

**GENERAL NOTICES..... 1**  
SPECIFICATIONS..... 1  
CLARIFICATIONS..... 1  
ATTESTING TO NON-COLLUSION..... 1  
QUANTITIES..... 1  
PREFERENCE FOR DELAWARE LABOR..... 1  
EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS..... 1  
TAX CLEARANCE..... 2  
LICENSE..... 2  
DIFFERING SITE CONDITIONS..... 2  
RIGHT TO AUDIT..... 3

**PREVAILING WAGES..... 4**  
STATE WAGE RATES..... 5  
STATE WAGE RATES..... 6

**SPECIAL PROVISIONS..... 7**  
401502 - ASPHALT CEMENT COST ADJUSTMENT..... 8  
710500 WATER MAIN AND ACCESSORIES..... 9  
711501 SANITARY SEWER SYSTEM..... 20  
**763501 - CONSTRUCTION ENGINEERING..... 28A**  
763508 - PROJECT CONTROL SYSTEM DEVELOPMENT PLAN..... 29  
763509 - CPM SCHEDULE UPDATES AND/OR REVISED UPDATES..... 29

**UTILITY STATEMENT..... 34**

**RIGHT OF WAY CERTIFICATE..... 39**

**ENVIRONMENTAL STATEMENT..... 40**

**RAILROAD STATEMENT..... 41**

**BID PROPOSAL FORMS..... 42**  
BREAKOUT SHEET..... 49

**DRUG TESTING AFFIDAVIT..... 53**

**CERTIFICATION..... 54**

**BID BOND..... 56**

## 763501 - CONSTRUCTION ENGINEERING

### **Description:**

This work consists of construction lay out including stakes, lines and grades as specified below as well as as-built plans. Subsection 105.10 Construction Stakes, Lines and Grades of the Standard Specifications is voided. Based on contract plans and information provided by the Engineer, the Contractor shall stake out right-of-way and easements lines, limits of construction and wetlands, slopes, profile grades, drainage system, centerline or offset lines, benchmarks, structure working points and any additional points to complete the project.

The Engineer will only establish the following:

- (a) Original and final cross-sections for borrow pits.
- (b) Final cross-sections: Top and bottom pay limit elevations for all excavation bid items that are not field measured by Construction inspection personnel. The Contractor shall notify the Engineer when these pay limit elevations are ready and allow for a minimum of two calendar days for the Engineer to obtain the information.
- (c) Line and grade for extra work added on to the project plans.

**Equipment.** The Contractor shall use adequate equipment/instruments in a good working order. He/she shall provide written certification that the equipment/instrument has been calibrated and is within manufacturer's tolerance. The certification shall be dated a maximum of 9 months before the start of construction. The Contractor shall renew the certification a minimum of every 9 months. The equipment/instrument shall have a minimum measuring accuracy of [3mm+2ppmxD] and an angle accuracy of up to 2.0 arc seconds or 0.6 milligons. If the Contractor chooses to use GPS technology in construction stakeout, the Contractor shall provide the Engineer with a GPS rover and Automatic Level for the duration of the contract. The GPS rover shall be in good working condition and of similar make and model used by the Contractor. The Contractor shall provide up to 8 hours of formal training on the Contractor's GPS system to a maximum of four Engineer's appointees (DELDOT Construction Inspectors). At the end of the contract, the Engineer will return the GPS rover to the Contractor. If any of the equipment/instruments are found to be out of adjustment or inadequate to perform its function, such instrument or equipment shall be immediately replaced by the Contractor to the satisfaction of the Engineer. Choosing to use GPS technology does not give the contractor authority to use machine control.- Construction Engineering (GPS) Machine Control Grading shall only be used if noted in the General Notes in the plan set outlining the available files that will be provided to the Contractor and "the Release for delivery of documents in electronic form to a contractor" are signed by all parties prior to delivery of any electronic files. Only files designated in the General Notes shall be provided to the contractor. If machine control grading is allowed on the project see the "machine control" section of this specification. GPS technology and machine control technology shall not be used in the construction of bridges.

**Engineering/Survey Staff.** The Contractor shall provide and have available for the project an adequate engineering staff that is competent and experienced to set lines and grades needed to construct the project. The engineering personnel required to perform the work outlined herein shall have experience and ability compatible with the magnitude and scope of the project. Additionally, the Contractor shall employ an engineer or surveyor licensed in the State of Delaware to be responsible for the quality and accuracy of the work done by the engineering staff. When individuals or firms other than the Contractor perform any professional services under this item, that work shall not be subject to the sub contracting requirements of Subsection 108.01 of the Standard Specifications. The Contractor shall assume full responsibility for any errors and/or omissions in the work of the engineering staff described herein. If construction errors are caused due to erroneous work done under Construction Engineering the Contractor accepts full responsibility, no matter when the error is discovered. Consideration will not be given for any extension of contract time or additional compensation due to delays, corrective work, or additional work that may result from faulty and erroneous construction stakeout, surveying, and engineering required by this specification.

**As-Builts:** The contractor is responsible for providing legible and clear as-built plans at the completion of the project, signifying any changes from the original plan. These plans will be reviewed by the Engineer.

**Construction Methods:**

**Performance Requirements:**

- (a) Construction Engineering shall include establishing the survey points and survey centerlines; finding, referencing, offsetting the project control points; running a horizontal and vertical circuit to verify the precision of given control points. Establishing plan coordinates and elevation marks for culverts, slopes, subbase, subsurface drains, paving, subgrade, retaining walls, and any other stakes required for control lines and grades; and setting vertical control elevations, such as footings, caps, bridge seats and deck screed. The Contractor shall be responsible for the preservation of the Department's project control points and benchmarks. The Contractor shall establish and preserve any temporary control points (traverse points or benchmarks) needed for construction. Any project control points (traverse points) or benchmarks conflicting with construction of the project shall be relocated by the Contractor. The Contractor as directed by the Engineer must replace any or all stakes that are destroyed at any time during the life of the contract. The Contractor shall re-establish centerline points and stationing prior to final cross-sections by the Engineer. The Vertical Control error of closure shall not exceed 0.035 ft times. The Horizontal Control precision ratio shall have a minimum precision of 1:20,000 feet of distance traversed prior to adjustment.
- (b) The Contractor shall perform construction centerline layout of all roadways, ramps and connections, etc. from project control points set by the Engineer. The Contractor using the profiles and typical sections provided in the plans shall calculate proposed grades at the edge of pavement or verify information shown on Grades and Geometric sheets.
- (c) The Contractor shall advise the Engineer of any horizontal or vertical alignment revisions needed to establish smooth transitions to existing facilities. The Contractor must immediately bring to the attention of the Engineer any potential drainage problem within the project limits. The Engineer must approve any proposed variation in profile, width or cross slope.
- (d) The Contractor shall establish the working points, centerlines of bearings on bridge abutments and on piers, mark the location of anchor bolts to be installed, check the elevation of bearing surfaces before and after they are ground and set anchor bolts at their exact elevation and alignment as per Contract Plans. Before completion of the fabrication of beams for bridge superstructures, the Contractor shall verify by accurate field measurements the locations both vertically and horizontally of all bearings and shall assume full responsibility for fabricated beams fitting and bearing as constructed. After beam erection and concurrently with the Department project surveyors or their designated representative, the Contractor shall survey top of beam elevations at a maximum of 10-ft stations and compute screed grades. These shall be submitted to the Engineer for review and approval before the stay in place forms are set. Construction stakes and other reference control marks shall be set at sufficiently frequent intervals to assure that all components of the structure are constructed in accordance with the lines and grades shown on the plans. The Contractor will be responsible for all structure alignment control, grade control and all necessary calculations to establish and set these controls.
- (e) The Contractor, using contract plans, shall investigate proposed construction for possible conflicts with existing and proposed utilities. The Contractor shall then report such conflicts to the Engineer for resolution. All stakes for utility relocations, which will be performed by others, after the Notice to Proceed has been given to the Contractor, shall be paid for under item 763597 - Utility Construction Engineering.
- (f) The Contractor shall be responsible for the staking of all sidewalk and curb ramp grades in accordance with the plans and the Departments Standard Construction Details. The Contractor shall review the stakeout with the Engineer prior to construction. The Engineer must approve any

deviation from plans, Department Standard Construction Details and Specifications in writing. The Contractor shall be responsible for any corrective actions resulting from problems created by adjustments if they fail to obtain such approval.

(g) If wetland areas are involved and specifically defined on the Plans the following shall apply:

- i. It is the intent of these provisions to alert the Contractor, that he/she shall not damage or destroy wetland areas, which exist beyond the construction limits. These provisions will be strictly enforced and the Contractor shall advise his/her personnel and those of any Subcontractor of the importance of these provisions.
- ii. All clearing operations and delineation of wetlands areas shall be performed in accordance with these Special Provisions. Before any clearing operation commences the Contractor shall demarcate wetlands at the Limits of Construction throughout the entire project as shown on the Plans labeled as Limits of Construction or Wetland Delineation to the satisfaction of the Engineer.
- iii. The material to be used for flagging the limits of construction shall be orange vinyl material with the wording "Wetland Boundary" printed thereon. In wooded areas, the flagging shall be tied on the trees, at approximate 20-foot intervals through wetland areas. In open field and yard areas that have been identified as wetlands, 6 foot posts shall be driven into the ground at approximate 50-foot intervals and tied with the flagging. The flagging shall extend approximately 12 inches in length beyond the post. Posts shall be oak with cross sectional dimensions of 1 ½ inches to 2 inches by 1 ½ inches to 2 inches or ¼ inch rebar.
- iv. If the flagging has been destroyed and the Engineer determines that its use is still required, the Contractor shall reflag the area at no cost to the Department. If the Contractor, after notification by the Engineer that replacement flagging is needed, does not replace the destroyed flagging within 48 hours, the Engineer may proceed to have the area reflagged. The cost of the reflagging by the Engineer will be charged to the Contractor and deducted from any monies due under the Contract.
- v. At the completion of construction, the Contractor shall remove all posts and flagging.
- vi. The Contractor shall be responsible for any damages to wetlands located beyond the construction limits, which occurs from his/her operations during the life of the Contract. The Contractor shall restore all temporarily disturbed wetland areas to their preconstruction conditions. This includes restoring bank elevations, streambed and wetland surface contours and wetlands vegetation disturbed or destroyed. The expense for this restoration shall be borne solely by the Contractor.

(h) Whenever the Engineer will be recording data for establishment of pay limits, the Contractor will be invited to obtain the data jointly with the Engineer's Survey Crew(s) in order to agree with the information. If the Contractor's representative is not able to obtain the same data, then the information obtained by the Engineer shall be considered the information to be used in computing the quantities in question.

**Submittals.** All computations necessary to establish the exact position of all work from the control points shall be made and preserved by the Contractor. All computations, survey notes, electronic files, and other records necessary to accomplish the work shall be made available to the Department in a neat and organized manner at any time as directed by the Engineer. The Engineer may check all or any portion of the stakeout survey work or notes made by the Contractor and any necessary correction to the work shall be made as soon as possible. The Contractor shall furnish the Engineer with such assistance as may be required for checking all lines, grades, and measurements established by the Contractor and necessary for the execution of the work. Such checking by the Engineer shall not relieve the Contractor of his/her responsibility for the accuracy or completeness of the work. Copies of all notes must be furnished to the engineer at the completion of the project.

The Contractor shall submit any of the following at the Engineer's request:

- (a) Proposed method of recording information in field books to ensure clarity and adequacy.

- (b) A printout of horizontal control verification, as well as coordinates, differences and error of closure for all reestablished or temporary Control Points.
- (c) A printout of vertical control verification, with benchmark location elevation and differences from plan elevation.
- (d) Sketch of location of newly referenced horizontal control, with text printout of coordinates, method of reference and field notes associated with referencing control - traverse closure report.
- (e) Description of newly established benchmarks with location, elevation and closed loop survey field notes - bench closure report
- (f) All updated electronic and manuscript survey records.
- (g) Stakeout plan for each structure and culvert.
- (h) Computations for buildups over beams, screed grades and overhang form elevations.
- (i) A report showing differences between supplied baseline coordinates and field obtained coordinates, including a list of preliminary input data.
- (j) Any proposed plan alteration to rectify a construction stakeout error, including design calculations, narrative and sealed drawings.
- (k) Baseline for each borrows pit location.
- (l) Detailed sketch of proposed overhead ground mounted signs or signals showing obstructions that may interfere with their installation.
- (m) Copies of cut sheets.

### Machine Control Grading

**This Section of the specification shall only be used if machine control is authorized for use on the project.**

#### **Description:**

This specification contains the requirements for grading operations utilizing Global Positioning Systems (GPS).

Use of this procedure and equipment is intended for grading the subgrade surface; it is not intended for the use in constructing final surface grades.

The Contractor may use any manufacturer's GPS machine control equipment and system that results in achieving the grading requirements outlined in section 202 of the standard specifications. The Contractor shall convert the electronic data provided by the Department into the format required by their system. The Department will only provide the information outlined in this document and no additional electronic data will be provided.

The Contractor shall perform at least one 500 foot test section with the selected GPS system to demonstrate that the Contractor has the capabilities, knowledge, equipment, and experience to properly operate the system and meet acceptable tolerances. The engineer will evaluate and make the determination as to whether additional 500 foot test sections are required. If the Contractor fails to demonstrate this ability to the satisfaction of the Department, the Contractor shall construct the project using conventional surveying and staking methods.

#### **Materials:**

All equipment required to perform GPS machine control grading, including equipment needed by DeIDOT to verify the work, shall be provided by the Contractor and shall be able to generate end results that are in accordance with the requirements of Division 200 - EARTHWORK of the Standard Specifications.

#### **Construction:**

##### **A. DeIDOT Responsibilities:**

1. The Department will set initial vertical and horizontal control points in the field for the project as indicated in the contract documents, (plans set). If the Contractor needs to establish new control points they shall be traversed from existing control points and verified to be accurate by conventional surveying techniques.
2. The Department will provide the project specific localized coordinate system.
3. The Department will provide data in an electronic format to the Contractor as indicated in the General Notes.
  - a. The information provided shall not be considered a representation of actual conditions to be encountered during construction. Furnishing this information does not relieve the Contractor from the responsibility of making an investigation of conditions to be encountered including, but not limited to site visits, and basing the bid on information obtained from these investigations, and the professional interpretations and judgments of the Contractor. The Contractor shall assume the risk of error if the information is used for any purpose for which the information is not intended.
  - b. Any assumption the Contractor makes from this electronic information shall be at their risk. If the Contractor chooses to develop their own digital terrain model the Contractor shall be fully responsible for all cost, liability, accuracy and delays.
  - c. The Department will develop and provide electronic data to the Contractor for their use as part of the contract documents in a format as indicated in the General Notes. The Contractor shall independently ensure that the electronic data will function in their machine control grading system.
4. The Files that are provided were originally created with the computer software applications MicroStation (CADD software) and INROADS (civil engineering software). The data files will be provided in the native formats and other software formats described below. The contractor shall perform necessary conversion of the files for their selected grade control equipment. The Department will furnish the Contractor with the following electronic files:
  - a. CAD files
    - i. Inroads -Existing digital terrain model (.DTM)
    - ii. Inroads -Proposed digital terrain model (.DTM)
    - iii. Microstation -Proposed surface elements - triangles
  - b. Alignment Data Files:
    - i. ASCII Format
5. The Engineer shall perform spot checks of the Contractor's machine control grading results, surveying calculations, records, field procedures, and actual staking. If the Engineer determines that the work is not being performed in a manner that will assure accurate results, the Engineer may order the Contractor to redo such work to the requirements of the contract documents, and in addition, may require the Contractor to use conventional surveying and staking, both at no additional cost to the Department.

## **B . Contractor's Responsibilities**

1. The Contractor shall provide the Engineer with a GPS rover and Automatic Level, for use during the duration of the contract. At the end of the contract, the GPS rover and Automatic Level will be returned to the Contractor. The Contractor shall provide a total of 8 hours of



formal training on the Contractor's GPS machine control system to the Engineer and up to three additional Department appointees per rover.

2. The Contractor shall review and apply the data provided by the Department to perform GPS machine control grading.
3. The Contractor shall bear all costs, including but not limited to the cost of actual reconstruction of work, that may be incurred due to application of GPS machine control grading techniques. Grade elevation errors and associated corrections including quantity adjustments resulting from the contractor's use of GPS machine control shall be at no cost to the Department.
4. The Contractor shall convert the electronic data provided by the Department into a format compatible with their system.
5. The Contractor's manipulation of the electronic data provided by the Department shall be performed at their own risk.
6. The Contractor shall check and if necessary, recalibrate their GPS machine control system at the beginning of each workday in accordance with the manufacturer's recommendations, or more frequently as needed to meet the requirements of the project.
7. The Contractor shall meet the accuracy requirements as detailed in the Standard Specifications.
8. The Contractor shall establish secondary control points at appropriate intervals and at locations along the length of the project. These points shall be outside the project limits and/or where work is performed. These points shall be at intervals not to exceed 1000 feet. The horizontal position of these points shall be determined by conventional survey traverse and adjustments from the original baseline control points. The conventional traverse shall meet or exceed the Department's Standards. The elevation of these control points shall be established using differential leveling from the project benchmarks, forming a closed loop. A copy of all new control point information including closure report shall be provided and approved by the Engineer prior to construction activities. The Contractor shall be responsible for all errors resulting from their efforts and shall correct deficiencies to the satisfaction of the Engineer and at no additional cost to the Department.
9. The Contractor shall provide stakes at all alignment control points, at every 500 foot stationing, and where required for coordination activities involving environmental agencies and utility companies at the Contractor's expense. Work that is done solely for utility companies and that is beyond the work performed under item 763501 - Construction shall follow and be paid for under item 763597 -Utility Construction Engineering.
10. The Contractor shall at a minimum set hubs at the top of finished grade at all hinge points on the cross section at 500 foot intervals on the main line and at least 4 cross sections on side roads and ramps as directed by the engineer or as shown on the plans. Placement of a minimum of 4 control points outside the limits of disturbance for the excavation of borrow pits, Stormwater Management Ponds, wetland mitigation sites etc. These control points shall be established using conventional survey methods for use by the Engineer to check the accuracy of the construction.
11. The Contractor shall preserve all reference points and monuments that are identified and established by the Engineer for the project. If the Contractor fails to preserve these items the Contractor shall reestablish them at no additional cost to the Department.

12. The Contractor shall provide control points and conventional grades stakes at critical points such as, but not limited to, PC's, PT's, superelevation points, and other critical points required for the construction of drainage and roadway structures.
13. No less than 2 weeks before the scheduled preconstruction meeting, the Contractor shall submit to the Engineer for review a written machine control grading work plan which shall include the equipment type, control software manufacturer and version, and proposed location of the local GPS base station used for broadcasting differential correction data to rover units.
14. The Contractor shall follow the guidelines set forth in the "Geometric Geodetic Accuracy Standards and Specifications for Using GPS Relative Positioning Techniques" and follow a minimum of Second Order Class 1, (2-I) classification standards.

Automated equipment operations have a high reliance on accurate control networks from which to take measurements, establish positions, and verify locations and features. Therefore, a strong contract control network in the field which is the same or is strongly integrated with the project control used during the design of the contract is essential to the successful use of this technology with the proposed Digital Terrain Model (DTM). Consistent and well designed site calibration for all machine control operations (as described below under Contract Control Plan) are required to ensure the quality of the contract deliverables. The Contract Control Plan is intended to document which horizontal and vertical control will be held for these operations. Continued incorporation of the Base Station(s) as identified in the Contract Control Plan is essential to maintaining the integrity of positional locations and elevations of features. The Contract Control Plan shall be submitted to the Department for review and approval by the Departments Survey Section 3 weeks prior to the start of any machine control work. The Contractor shall operate and maintain all elements of the Machine Grade Control continuously once the operations begin until otherwise approved by the Engineer.

#### **Contract Control Plan:**

The Contractor shall develop and submit a Contract Control Plan for all contracts which use Machine Control Grading. Contract control includes all primary and secondary horizontal and vertical control which will be used for the construction contract. Upon the Contractor's completion of the initial survey reconnaissance and control verification, but prior to beginning primary field operations, the Contractor shall submit a Contract Control Plan document (signed and sealed by the Delaware licensed Land Surveyor or Delaware Professional Engineer who oversees its preparation) for acceptance by the Engineer, which shall include the following:

1. A control network diagram of all existing horizontal and vertical control recovered in the field as contract control.
2. Include a summary of the calculated closures of the existing control network, and which control has been determined to have been disturbed or out of tolerance from its original positioning.
3. An explanation of which horizontal and vertical control points will be held for construction purposes. If necessary include all adjustments which may have been made to achieve required closures.
4. An explanation of what horizontal and vertical control (including base stations) was set to accomplish the required stakeout or automated machine operation. Include how the position of these new control points was determined.
5. Describe the proposed method and technique (technology and quality control) for utilizing the control to establish the existing and/or proposed feature location and to verify the completed feature location and/or measured quantity.

6. A listing of the horizontal and vertical datums to be used and the combined factor to be used to account for ellipsoidal reduction factor and grid scale factor.
7. If the Contractor chooses to use machine control as a method of measuring and controlling excavation, fill, material placement or grading operations as a method of measuring and controlling excavation, fill, material placement or grading operations, the Contractor Control Plan shall include the method by which the automated machine guidance system will initially be site calibrated to both the horizontal and vertical contract control, and shall describe the method and frequency of the calibration to ensure consistent positional results.
8. Issues with equipment including inconsistent satellite reception of signals to operate the GPS machine control system will not result in adjustment to the "Basis of Payment" for any construction items or be justification for granting contract time extension.

**Method of Measurement:**

The quantity of Construction Engineering will not be measured.

**Basis of Payment:**

Payment will be made at the Lump Sum price bid for the item "Construction Engineering". The price bid shall include the cost of furnishing all labor, equipment, instruments, stakes and other material necessary to satisfactorily complete the work as herein described under this item for all roads and structures that are a part of the contract. Adjustment in payment will be made for the deletion or addition of work not shown in the contract documents.

Monthly payment will be made under this item in proportion to the amount of work done as determined by the Engineer.

6/26/2018

Contract No. T201780102.01

- c. STERILIZATION OF WATERMAIN - The method to be used for sterilization shall comply with AWWA C 601-81, C 651, and Owner requirements, with the plugs used in the pressure test still installed in the pipe prior to placement into service. Extreme care is to be exercised in order to prevent the entrance of any contaminants into the main. All expenses and cost incurred in carrying out the specified sterilization work shall be borne by the Contractor at no extra cost to the Utility Owner or the State and shall be included in the contract unit price per linear foot bid for the Water Main Installation.
  - d. BACTERIA TESTING OF WATERMAIN - Provide an adequate blowoff for use in flushing of the main. Before the water is turned on for use by the consumer from the relocated mains, the Owner will conduct bacteriological tests on water samples taken from the blowoff. All expenses incurred in the performance of these tests by the Owner are borne by the Contractor. Upon final sanitary approval by the Owner, return water service for use by the consumer. Before the final connection is made, thoroughly clean all surfaces of the relocated line, including all gaskets and glands, and the existing water main that are to become part of the closing joint with a 5 percent solution of Sodium Hypochlorite. Exercise extreme care in order to prevent the entrance of any contaminants into the main. All expenses and cost incurred in carrying out the specified sterilization work is borne by the Contractor at no extra cost to the Owner or the State and is included in the Contract Unit Price per linear foot bid for the Item for the various sizes. Plug adjacent pipe openings as required in accordance with the Section 202.03.2.
12. AS-BUILT / FINAL LOCATION DRAWINGS - Within thirty (30) days after completion of required work, the Contractor shall submit an accurate print or prints showing the horizontal and vertical location of mains, bends and other appurtenances to the Engineer and the Utility Owner. Services, fittings, fire hydrants and all other reconnections to the replaced pipes shall be identified and marked in the construction drawings by the Contractor. The Contractor shall be responsible for marking the construction drawings in reference to at least two fixed and easily found points.

**Method of Measurement and Basis of Payment:**

Price and payment for water service Items includes furnishing, transporting and installing the Materials; adjusting, relocating or repairing the services, testing of the water main system; for repairing leaks and defects, including defects to settlement, connecting to existing water main systems and services; maintaining service as required; excavating; disposing of excess excavated Material; backfilling; furnishing Material for backfilling; furnishing and installing concrete thrust blocks, joint restraints, pipe bedding, sheeting and shoring, temporary support of existing Utilities, dewatering; abandoning existing pipes, cutting and capping new or existing lines and for all labor, Equipment, tools and necessary incidentals to achieve and accept an operational water main system. No separate payment shall be made for salvaging or abandoning or removing and disposing of existing water mains and cost for such required work shall be incidental to the respective sizes for installing water main.

A breakout sheet attached to the Proposal lists the different elements of work or materials involved in completing this item. The Contractor shall fill in a unit price for each item and the cost (unit price times the proposed quantity). The Lump Sum cost for Item 710500, shall be derived from the total sum of the cost of all items listed. ~~The breakout sheet shall be attached to the Bid Proposal. Failure to submit the breakout sheet with the Bid Proposal will result in the bid being declared non-responsive and rejected.~~ The Department reserves the right to delete from the Contract one or more items listed and the right to add or subtract from

**Method of Measurement and Basis of Payment:**

Price and payment for sanitary sewer system Items, including adjustment of sanitary sewer laterals, includes furnishing, transporting and installing the materials; the pumping station; testing of the sanitary sewer system; connecting to existing sanitary sewer systems and services; maintaining service as required; excavating; disposing of excess excavated material; backfilling; furnishing material for backfilling; furnishing and placing warning tape; furnishing and installing concrete thrust blocks, joint restraints, aggregate pipe bedding, sheeting and shoring, temporary support of existing Utilities, dewatering, furnishing and using tanker trucks for excess flow, disposing of excess flow at an approved location; abandoning existing pipes including filling such pipes with flowable fill, cutting and capping new or existing lines and for all labor, Equipment, tools and necessary incidentals to achieve and accept an operational sanitary sewer system.

All lump sum pay items will be prorated for each pay estimate. A percentage of the lump sum item will be paid, on a monthly basis, based upon the amount of work completed and accepted by the Engineer. A breakout sheet attached to the Proposal lists the different elements of work or materials involved in completing this item. The Contractor shall fill in a unit price for each item and the cost (unit price times the proposed quantity). The Lump Sum cost for Item 710501, shall be derived from the total sum of the cost of all items listed. ~~The breakout sheet shall be attached to the Bid Proposal. Failure to submit the breakout sheet with the Bid Proposal will result in the bid being declared non-responsive and rejected.~~ The Department reserves the right to delete from the Contract one or more items listed and the right to add or subtract from the quantity of each item. The total price to be paid will be adjusted in accordance with the Contractor's unit prices as required above. There will be no extra compensation or increase in unit prices in the breakout sheet if such additions and/or deletions are made to the quantities.

5/10/2018

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 3  
DATE:

CONTRACT ID: T201780102.01 PROJECT(S): T201780102.01

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	708003 GEOTEXTILES, RIPRAP	50.000 SY				
0210	710500 INSTALLATION OF WATERMAIN AND ACCESSORIES	LUMP	LUMP			
0220	711501 SANITARY SEWER SYSTEM	LUMP	LUMP			
0230	760010 PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT	17196.000 SYIN				
0240	762000 SAW CUTTING, BITUMINOUS CONCRETE	2203.000 LF				
0250	763000 INITIAL EXPENSE/DE-MOBILIZATION	LUMP	LUMP			
0260	763501 CONSTRUCTION ENGINEERING	LUMP	LUMP			
0270	763508 PROJECT CONTROL SYSTEM DEVELOPMENT PLAN	LUMP	LUMP			
0280	763509 CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	8.000 EAMO				
0290	801000 MAINTENANCE OF TRAFFIC	LUMP	LUMP			

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 4  
DATE:

CONTRACT ID: T201780102.01 PROJECT(S): T201780102.01

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	803001 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	 40.000 EADY				
0310	805001 PLASTIC DRUMS	 5166.000 EADY				
0320	808002 FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	 81.000 EADY				
0330	810001 TEMPORARY WARNING SIGNS AND PLAQUES	 1006.000 EADY				
0340	811001 FLAGGER, NEW CASTLE COUNTY STATE	 180.000 HOUR				
0350	811013 FLAGGER, NEW CASTLE COUNTY, STATE, OVERTIME	 36.000 HOUR				
0360	813001 TEMPORARY BARRICADES, TYPE III	 2.000 LFDY				
0370	817002 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND, ALKYD-THERMOPLASTIC	 275.000 SF				
0380	817003 TEMPORARY MARKINGS, PAINT, 4"	 13895.000 LF				
0390	817004 TEMPORARY MARKINGS, PAINT, SYMBOL/LEGEND	 230.000 SF				

DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 5  
DATE:

CONTRACT ID: T201780102.01 PROJECT(S): T201780102.01

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	817012 RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, SYMBOL/LEGEND	30.000 SF				
0410	817013 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	7715.000 LF				
0420	817014 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"	1630.000 LF				
0430	817015 PREFORMED RETROREFLECTIVE THERMOPLASTIC MARKINGS, BIKE SYMBOL	8.000 EACH				
0440	817018 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 3"	400.000 LF				
0450	817031 REMOVAL OF PAVEMENT STRIPING	12953.000 SF				
0460	819018 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	90.000 EACH				
0470	819019 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON MULTIPLE SIGN POSTS	96.000 SF				
0480	905001 SILT FENCE	594.000 LF				



DELAWARE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 6  
DATE:

CONTRACT ID: T201780102.01 PROJECT(S): T201780102.01

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0490	907017 COMPOST FILTER LOGS	60.000 LF				
0500	908004 TOPSOIL, 6" DEPTH	10363.000 SY				
0510	908014 PERMANENT GRASS SEEDING, DRY GROUND	10363.000 SY				
0520	908020 EROSION CONTROL BLANKET MULCH	3793.000 SY				
0530	908023 STABILIZED CONSTRUCTION ENTRANCE	98.000 TON				
	SECTION 0001 TOTAL					
	TOTAL BID					