

STATE OF DELAWARE

**This Copy is for information only.  
You must request a CD from  
DeIDOT in order to bid.**



DEPARTMENT OF TRANSPORTATION

BID PROPOSAL

for

CONTRACT T201880103.01

NORTH DISTRICT IMPROVEMENTS, PHASE 1

NEW CASTLE COUNTY

ADVERTISEMENT DATE: March 25, 2019

COMPLETION TIME: 376 Calendar Days

**THERE WILL BE A NON-MANDATORY PRE-BID MEETING IN THE BIDDERS ROOM  
AT THE DeIDOT ADMINISTRATION BUILDING, 800 BAY ROAD, DOVER, DE ON  
TUESDAY APRIL 9, 2019 AT 10:30 A.M.**

SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION  
DELAWARE DEPARTMENT OF TRANSPORTATION  
AUGUST 2016

Bids will be received in the Bidder's Room at the Delaware Department of Transportation's Administration Building, 800 Bay Road, Dover, Delaware prior to 2:00 P.M. local time April 30, 2019

**Contract No.T201880103.01**

**NORTH DISTRICT IMPROVEMENTS, PHASE 1  
NEW CASTLE COUNTY**

**GENERAL DESCRIPTION**

LOCATION

These improvements are located in NEW CASTLE County more specifically shown on the Location Map(s) of the enclosed Plans.

DESCRIPTION

The improvements consist of furnishing all labor and materials for NORTH DISTRICT IMPROVEMENTS, PHASE 1 consisting of site work, crew operations building, material storage pad, paving and electrical upgrades, and other incidental construction in accordance with the location, notes and details shown on the plans and as directed by the Engineer.

COMPLETION TIME

All work on this contract must be complete within 376 Calendar Days. The Contract Time includes an allowance for 60 Weather Days. It is the Department's intent to issue a Notice to Proceed such that work starts on or about June 10, 2019.

PROSPECTIVE BIDDERS NOTES:

1. BIDDERS MUST BE REGISTERED with DelDOT and request a cd of the official plans and specifications in order to submit a bid. Contact DelDOT at [dot-ask@state.de.us](mailto:dot-ask@state.de.us), or (302) 760-2031. Bids will be received in the Bidder's Room at the Delaware Department of Transportation's Administration Building, 800 Bay Road, Dover, Delaware prior to 2:00 P.M. local time April 30, 2019 unless changed via addendum.
2. QUESTIONS regarding this project are to be e-mailed to [dot-ask@state.de.us](mailto:dot-ask@state.de.us) no less than six business days prior to the bid opening date in order to receive a response. Please include T201880103.01 in the subject line. Responses to inquiries are posted on-line at <http://www.bids.delaware.gov>.
3. PREQUALIFICATION REQUIREMENT - 29 Del.C. §6962 (12)(a) requires DelDOT to include a performance-based rating system for contractors. The Performance Rating for each Contractor shall be **NEW** used as a prequalification to bid at the time of bid. Refer to Contract '**General Notices**' for details.
4. THE BID PROPOSAL incorporates a cd containing **Expedite, version 5.9a** and its installation file. Bidders are to use the cd provided to enter their bid amounts into the Expedite file. The Expedite bid file must be printed and submitted in paper form along with the cd and other required documents prior to the Bid due date and time.
5. SURETY BOND - Each proposal must be accompanied by a deposit of either surety bond or security for a sum equal to at least 10% of the bid.
6. DRUG TESTING - Regulation 4104; The state Office of Management and Budget has developed regulations that require Contractors and Subcontractors to implement a program of mandatory drug testing for Employees who work on Large Public Works Contracts funded all or in part with public funds pursuant to 29 Del.C. §6908(a)(6). **Refer to the full REVISED requirements at the following link: <http://regulations.delaware.gov/register/december2017/final/21 DE Reg 503 12-01-17.htm>**  
Note a few of the requirements;
  - \* At bid submission - Each bidder must submit with the bid a single signed affidavit certifying that the bidder and its subcontractors has in place or will implement during the entire term of the contract a Mandatory Drug Testing Program that complies with the regulation, *the form is attached*;
  - \* At least two business days prior to contract execution - The awarded Contractor shall provide to DelDOT copies of the Employee Drug Testing Program for the Contractor, and any other listed Subcontractors;

\* Subcontractors - Contractors that employ Subcontractors on the job site may do so only after submitting a copy of the Subcontractor's Employee Drug Testing Program along with the standard required subcontractor information. A Subcontractor shall not commence work until **DelDOT** has approved the subcontractor in writing;

\* Penalties for non-compliance are specified in the regulation.

7. No RETAINAGE will be withheld on this contract unless through the Prequalification Requirements.
8. EXTERNAL COMPLAINT PROCEDURE can be viewed on DelDOT's Website [here](#), or you may request a copy by calling (302) 760-2555.
9. REMINDER; A copy of your firm's Delaware Business License must be submitted with your bid.
10. AUGUST 2016 STANDARD SPECIFICATIONS apply to this contract. The Contractor shall make himself aware of any revisions and corrections (Supplemental Specifications, if any) and apply them to the applicable item(s) of this contract. The 2016 Standard Specifications can be [viewed here](#).
11. FLATWORK CONCRETE TECHNICIAN CERTIFICATION TRAINING:  
Section 501.03, 503.03, 505.03, 610.03, 701.03 and 702.03 of the 2016 Standard Specifications require contractor's to provide an American Concrete Institute (ACI) or National Ready Mix Concrete Association (NRMCA) certified concrete flatwork technician to supervise all finishing of flatwork concrete. Concrete flatwork certification will be effective starting on June 1, 2018.
12. **BREAKOUT SHEETS** MUST be submitted either with your bid documents; or within seven (7) calendar days following the bid due date by the lowest apparent bidder. Refer to instructions adjacent to the Breakout Sheets in this document.
13. This project incorporates **Appendix A TECHNICAL SPECIFICATIONS**, which is a part of this contract. Appendix A contains additional specifications required for this project.
14. In accordance with 29 Del. C. §6962(d)(10), a **Pre-Bid Meeting** will be held to select the subcontractor categories to be included in the bids for performing the work required for this contract. A penalty of \$2,000.00 will be withheld from the successful bidder for each occurrence for the failure to utilize any or all of the Subcontractors submitted with the bid.

The Pre-Bid Meeting will be held Tuesday April 9, 2019 at 10:30 a.m. in the DelDOT Administration Building, 800 Bay Road, Dover, Delaware, 19901, unless changed via Addendum.

**STATE OF DELAWARE  
CONSTRUCTION ITEMS UNITS OF MEASURE**

<b>English Code</b>	<b>English Description</b>	<b>Multiply By</b>	<b>Metric Code</b>	<b>Metric Description</b>	<b>Suggested CEC Metric Code</b>
ACRE	Acre	0.4047	ha	Hectare	HECTARE
BAG	Bag	N/A	Bag	Bag	BAG
C.F.	Cubic Foot	0.02832	m <sup>3</sup>	Cubic Meter	M3
C.Y.	Cubic Yard	0.7646	m <sup>3</sup>	Cubic Meter	M3
EA-DY	Each Day	N/A	EA-DY	Each Day	EA-DY
EA-MO	Each Month	N/A	EA-MO	Each Month	EA-MO
EA/NT	Each Night	N/A	EA-NT	Each Night	EA/NT
EACH	Each	N/A	EA	Each	EACH
GAL	Gallon	3.785	L	Liter	L
HOUR	Hour	N/A	h	Hour	HOUR
INCH	Inch	25.4	mm	Millimeter	MM
L.F.	Linear Foot	0.3048	m	Linear Meter	L.M.
L.S.	Lump Sum	N/A	L.S.	Lump Sum	L.S.
LA-MI	Lane Mile	1.609	LA-km	Lane-Kilometer	LA-KM
LB	Pound	0.4536	kg	Kilogram	KG
MFBM	Thousand Feet of Board Measure	2.3597	m <sup>3</sup>	Cubic Meter	M3
MGAL	Thousand Gallons	3.785	kL	Kiloliter	KL
MILE	Mile	1.609	km	Kilometer	KM
S.F.	Square Foot	0.0929	m <sup>2</sup>	Square Meter	M2
S.Y.	Square Yard	0.8361	m <sup>2</sup>	Square Meter	M2
SY-IN	Square Yard-Inch	0.8495	m <sup>2</sup> -25 mm	Square Meter-25 Millimeter	M2-25 MM
TON	Ton	.9072	t	Metric Ton (1000kg)	TON
N.A.*	Kip	4.448	kN	Kilonewton	N.A.*
N.A.*	Thousand Pounds per Square Inch	6.895	MPa	Megapascal	N.A.*

\*Not used for units of measurement for payment.

**TABLE OF CONTENTS**

<b>GENERAL DESCRIPTION.....</b>	<b><u>i</u></b>
LOCATION.....	<u>i</u>
DESCRIPTION.....	<u>i</u>
COMPLETION TIME.....	<u>i</u>
PROSPECTIVE BIDDERS NOTES.....	<u>i</u>
CONSTRUCTION ITEMS UNITS OF MEASURE.....	<u>iii</u>
<b>GENERAL NOTICES.....</b>	<b><u>1</u></b>
SPECIFICATIONS.....	<u>1</u>
CLARIFICATIONS.....	<u>1</u>
ATTESTING TO NON-COLLUSION.....	<u>1</u>
QUANTITIES.....	<u>1</u>
PREQUALIFICATION REQUIREMENT.....	<u>1</u>
PREFERENCE FOR DELAWARE LABOR.....	<u>1</u>
EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS.....	<u>2</u>
TAX CLEARANCE.....	<u>2</u>
LICENSE.....	<u>2</u>
DIFFERING SITE CONDITIONS.....	<u>2</u>
RIGHT TO AUDIT.....	<u>3</u>
<b>PREVAILING WAGES.....</b>	<b><u>3</u></b>
STATE WAGE RATES.....	<u>5</u>
<b>SUPPLEMENTAL SPECIFICATIONS.....</b>	<b><u>6</u></b>
<b>SPECIAL PROVISIONS.....</b>	<b><u>7</u></b>
CONSTRUCTION ITEM NUMBERS.....	<u>8</u>
401502 - ASPHALT CEMENT COST ADJUSTMENT.....	<u>9</u>
401699 - QUALITY CONTROL/QUALITY ASSURANCE OF BITUMINOUS CONCRETE.....	<u>10</u>
701505 - PORTLAND CEMENT CONCRETE PARKING BUMPER.....	<u>25</u>
710500 - INSTALLATION OF WATER MAIN AND ACCESSORIES.....	<u>26</u>
720556 - BOLLARD.....	<u>29</u>
763501 - CONSTRUCTION ENGINEERING.....	<u>30</u>
763508 - PROJECT CONTROL SYSTEM DEVELOPMENT PLAN.....	<u>40</u>
763509 - CPM SCHEDULE UPDATES AND/OR REVISED UPDATES.....	<u>40</u>
763511 - MAINTENANCE BUILDINGS.....	<u>45</u>
763598 - FIELD OFFICE, SPECIAL I.....	<u>47</u>
911500 - PLANTINGS, TUBELINGS.....	<u>53</u>
911502 - DECORATIVE STONE MULCH.....	<u>54</u>
<b>UTILITY STATEMENT.....</b>	<b><u>57</u></b>
<b>RIGHT OF WAY CERTIFICATE.....</b>	<b><u>59</u></b>
<b>ENVIRONMENTAL STATEMENT.....</b>	<b><u>61</u></b>
<b>RAILROAD STATEMENT.....</b>	<b><u>63</u></b>
<b>BID PROPOSAL FORMS.....</b>	<b><u>64</u></b>
BREAKOUT SHEET.....	<u>81</u>
<b>DRUG TESTING AFFIDAVIT.....</b>	<b><u>84</u></b>
<b>LIST OF BUILDING SUBCONTRACTORS.....</b>	<b><u>85</u></b>
<b>CERTIFICATION.....</b>	<b><u>86</u></b>
<b>BID BOND.....</b>	<b><u>89</u></b>

## GENERAL NOTICES

### SPECIFICATIONS:

The specifications entitled "Standard Specifications for Road and Bridge Construction, August, 2016", hereinafter referred to as the Standard Specifications, and Supplemental Specifications, the Special Provisions, notes on the Plans, this Bid Proposal, and any addenda thereto shall govern the work to be performed under this contract. The Specifications and Supplemental Specifications can be [viewed here](#).

### CLARIFICATIONS:

Under any Section or Item included in the Contract, the Contractor shall be aware that when requirements, responsibilities, and furnishing of materials are outlined in the details and notes on the Plans and in the paragraphs preceding the "Basis of Payment" paragraph in the Standard Specifications or Special Provisions, no interpretation shall be made that such stipulations are excluded because reiteration is not made in the "Basis of Payment" paragraph.

### ATTESTING TO NON-COLLUSION:

The Department requires as a condition precedent to acceptance of bids a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with such contract. The form for this sworn statement is included in the proposal and must be properly executed in order to have the bid considered.

### QUANTITIES:

The quantities shown are for comparison of bids only. The Department may increase or decrease any quantity or quantities without penalty or change in the bid price.

### PREQUALIFICATION REQUIREMENT

29 Del.C. §6962 (12)a requires a Department of Transportation project, excluding a Community <sup>NEW</sup> Transportation Fund or municipal street aid contract, to include a performance-based rating system. At the time of bid, the Performance Rating for each Contractor shall be used as a prequalification to bid.

Bidders with Performance Rating scores equal to or greater than 85% shall be permitted to bid. Bidders with scores of less than 85% who comply with the retainage requirements of 29 Del.C. §6962 shall be permitted to bid provided the *Agreement to Accept Retainage* (located on the Certification Page) is executed and submitted with the bid. Lack of an executed *Agreement to Accept Retainage* will result in the rejection of the bid by the Department. Successful bidders awarded Department contracts who have no performance history within the last five (5) years will be assigned a provisional Performance Rating of 85% at the date of advertisement.

Notification of Performance Rating. The Department shall post publicly the Performance Rating for all Contractors on the Department's [website](#). DelDOT will complete performance-based evaluations on the construction company contracted by the Department to build the project (the "Contractor"). Provisions to appeal Performance Ratings are described in the regulations. The regulations are set forth in Section 2408 of Title 2, Delaware Administrative Code, found [here](#).

### PREFERENCE FOR DELAWARE LABOR:

Delaware Code, Title 29, Chapter 69, Section 6962, Paragraph (d), Subsection (4)b:

"In the construction of all public works for the State or any political subdivision thereof, or by firms contracting with the State or any political subdivision thereof, preference in employment of laborers, workmen or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State. Each public works contract for the construction of public works for the State or any political subdivision thereof shall contain a stipulation that any person, company or corporation who violates this section shall pay a penalty to the Secretary of Finance equal to the amount of compensation paid to any person in violation of this section."

EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS:

Delaware Code, Title 29, Chapter 69, Section 6962, Paragraph (d), Subsection (7) states;

- a. As a condition of the awarding of any contract for public works financed in whole or in part by State appropriation, such contracts shall include the following provisions:

During the performance of this contract, the contractor agrees as follows:

1. The contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex, sexual orientation, gender identity or national origin. The contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, color, sex, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
2. The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex, sexual orientation, gender identity or national origin.
3. The contractor will ensure employees receive equal pay for equal work, without regard to sex. Employee pay differential is acceptable if pursuant to a seniority system, a merit system, a system which measures earnings by quantity or quality of production, or if the differential is based on any other factor other than sex.

TAX CLEARANCE:

As payments to each vendor or contractor aggregate \$2,000, the Division of Accounting will report such vendor or contractor to the Division of Revenue, who will then check the vendor or contractor's compliance with tax requirements and take such further action as may be necessary to insure compliance.

LICENSE:

A person desiring to engage in business in this State as a contractor shall obtain a license upon making application to the Division of Revenue.

CONTRACTOR / SUBCONTRACTOR LICENSE: 29 DEL. C. §6967:

(b) No agency shall accept a proposal for a public works contract unless such contractor has provided a proper and current copy of its occupational and/or business license, as required by Title 30, to such agency.

(c) Any contractor that enters a public works contract must provide to the agency to which it is contracting, within 30 days of entering such public works contract, copies of all occupational and business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the contractor entered the public works contract the occupational or business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

DIFFERING SITE CONDITIONS,

SUSPENSIONS OF WORK and SIGNIFICANT CHANGES IN THE CHARACTER OF WORK:

Differing site conditions: During the progress of the work, if subsurface or latent physical conditions are encountered at the site differing materially from those indicated in the contract or if unknown physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract are encountered at the site, the party discovering such conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

Upon written notification, the engineer will investigate the conditions, and if he/she determines that the conditions materially differ and cause an increase or decrease in the cost or time required for the performance of any work under the contract, an adjustment, excluding loss of anticipated profits, will be made and the contract modified in writing accordingly. The engineer will notify the contractor of his/her determination whether or not an adjustment of the contract is warranted.

No contract adjustment which results in a benefit to the contractor will be allowed unless the contractor has provided the required written notice.

No contract adjustment will be allowed under their clause for any effects caused on unchanged work.

Suspensions of work ordered by the engineer: If the performance of all or any portion of the work is suspended or delayed by the engineer in writing for an unreasonable period of time (not originally anticipated, customary or inherent to the construction industry) and the contractor believes that additional compensation and/or contract time is due as a result of such suspension or delay, the contractor shall submit to the engineer in writing a request for adjustment within 7 calendar days of receipt of the notice to resume work. The request shall set forth the reasons and support for such adjustment.

Upon receipt, the engineer will evaluate the contractor's request. If the engineer agrees that the cost and/or time required for the performance of the contract has increased as a result of such suspension and the suspension was caused by conditions beyond the control of and not the fault of the contractor, its suppliers, or subcontractors at any approved tier, and not caused by weather, the engineer will make an adjustment (excluding profit) and modify the contract in writing accordingly. The engineer will notify the contractor of his/her determination whether or not an adjustment of the contract is warranted.

No contract adjustment will be allowed unless the contractor has submitted the request for adjustment within the time prescribed.

No contract adjustment will be allowed under this clause to the extent that performance would have been suspended or delayed by any other cause, or for which an adjustment is provided for or excluded under any other term or condition of this contract.

Significant changes in the character of work: The engineer reserves the right to make, in writing, at any time during the work, such changes in quantities and such alterations in the work as are necessary to satisfactorily complete the project. Such changes in quantities and alterations shall not invalidate the contract nor release the surety, and the contractor agrees to perform the work as altered.

If the alterations or changes in quantities significantly change the character of the work under the contract, whether or not changed by any such different quantities or alterations, an adjustment, excluding loss of anticipated profits, will be made to the contract. The basis for the adjustment shall be agreed upon prior to the performance of the work. If a basis cannot be agreed upon, then an adjustment will be made either for or against the contractor in such amount as the engineer may determine to be fair and equitable.

The term "significant change" shall be construed to apply only to the following circumstances:

- (A) When the character of the work as altered differs materially in kind or nature from that involved or included in the original proposed construction or
- (B) When a major item of work, as defined elsewhere in the contract, is increased in excess of 125 percent or decreased below 75 percent of the original contract quantity. Any allowance for an increase in quantity shall apply only to that portion in excess of 125 percent of original contract item quantity, or in case of a decrease below 75 percent, to the actual amount of work performed.

#### RIGHT TO AUDIT

The Department shall have the right to audit the books and records of the contractor or any subcontractor under this contract or subcontract to the extent that the books and records relate to the performance of the contract or subcontract. The books and records shall be maintained by the contractor for a period of 3 years from the date of final payment under the prime contract and by the subcontractor for a period of 3 years from the date of final payment under the subcontract (29 Del.C. §6930)

#### PREVAILING WAGES

Included in this proposal are the minimum wages to be paid various classes of laborers and mechanics as determined by the Department of Labor of the State of Delaware in accordance with Title 29 Del.C. §6960, relating to wages and the regulations implementing that Section.

REQUIREMENT BY DEPARTMENT OF LABOR FOR SWORN PAYROLL INFORMATION

Title 29 Del.C. §6960 stipulates;

(b) Every contract based upon these specifications shall contain a stipulation that the employer shall pay all mechanics and laborers employed directly upon the site of the work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics. The specifications shall further stipulate that the scale of wages to be paid shall be posted by the employer in a prominent and easily accessible place at the site of the work, and that there may be withheld from the employer so much of accrued payments as may be considered necessary by the Department of Labor to pay to laborers and mechanics employed by the employer the difference between the rates of wages required by the contract to be paid laborers and mechanics on the work and rates of wages received by such laborers and mechanics to be remitted to the Department of Labor for distribution upon resolution of any claims.

(c) Every contract based upon these specifications shall contain a stipulation that sworn payroll information, as required by the Department of Labor, be furnished weekly. The Department of Labor shall keep and maintain the sworn payroll information for a period of 6 months from the last day of the work week covered by the payroll.

Bidders are specifically directed to note the Department of Labor's prevailing wage regulations implementing §6960 relating to the effective date of the wage rates, at Section 6.3, which in relevant part states:

"Public agencies (covered by the provisions of 29 Del.C. §6960) are required to use the rates which are in effect on the date of the publication of specifications for a given project. In the event that a contract is not executed within one hundred twenty (120) days from the date the specifications were published, the rates in effect at the time of the execution of the contract shall be the applicable rates for the project."

Contractor may contact:

Department of Labor, Division of Industrial Affairs, 4425 N. Market Street, Wilmington, DE 19802  
Telephone (302) 761-8200

STATE OF DELAWARE  
DEPARTMENT OF LABOR  
DIVISION OF INDUSTRIAL AFFAIRS  
OFFICE OF LABOR LAW ENFORCEMENT  
PHONE: (302) 761-8200

Mailing Address:  
4425 North Market Street  
3rd Floor  
Wilmington, DE 19802

Located at:  
4425 North Market Street  
3rd Floor  
Wilmington, DE 19802

PREVAILING WAGES FOR BUILDING CONSTRUCTION EFFECTIVE MARCH 15, 2019

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
ASBESTOS WORKERS	23.92	29.46	42.87
BOILERMAKERS	71.61	36.33	53.41
BRICKLAYERS	55.89	55.89	55.89
CARPENTERS	55.63	55.63	44.22
CEMENT FINISHERS	75.54	52.62	23.19
ELECTRICAL LINE WORKERS	47.57	40.79	31.10
ELECTRICIANS	70.49	70.49	70.49
ELEVATOR CONSTRUCTORS	96.27	67.47	33.42
GLAZIERS	75.65	75.65	59.28
INSULATORS	57.88	57.88	57.88
IRON WORKERS	65.57	65.57	65.57
LABORERS	47.70	47.70	47.70
MILLWRIGHTS	74.23	74.23	59.84
PAINTERS	52.47	52.47	52.47
PILEDRIVERS	78.02	41.17	33.30
PLASTERERS	31.22	31.22	23.14
PLUMBERS/PIPEFITTERS/STEAMFITTERS	70.05	55.29	60.31
POWER EQUIPMENT OPERATORS	71.29	71.29	71.29
ROOFERS-COMPOSITION	25.12	24.79	22.64
ROOFERS-SHINGLE/SLATE/TILE	19.24	22.88	17.99
SHEET METAL WORKERS	72.53	72.53	72.53
SOFT FLOOR LAYERS	53.39	53.39	53.39
SPRINKLER FITTERS	60.04	60.04	60.04
TERRAZZO/MARBLE/TILE FNRS	64.45	64.45	64.45
TERRAZZO/MARBLE/TILE STRS	71.27	71.27	71.27
TRUCK DRIVERS	32.19	28.70	21.91

CERTIFIED: 03/27/2019

BY: [Signature] on behalf of Julie Petoff  
ADMINISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

**NOTE:** THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE 302-761-8200

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: T201880103.01 North District Improvements Phase 1, New Castle County

# **SUPPLEMENTAL SPECIFICATIONS TO THE STANDARD SPECIFICATIONS**

**EFFECTIVE AS OF THE ADVERTISEMENT  
DATE OF THIS PROPOSAL  
AND INCLUDED BY REFERENCE**

**The Supplemental Specifications can be viewed and printed from  
the Department's Website.**

To access the Website;

- in your internet browser, enter; <https://www.deldot.gov>
- under 'BUSINESS', Click; 'Publications'
- scroll down under 'MANUALS' and Click; "Standard Specifications"
- be sure and choose the correct Standard Specification year; 2001 or 2016
- choose the latest revision prior to the date of this advertisement

The full Website Link is;

[https://www.deldot.gov/Publications/manuals/standard\\_specifications/index.shtml](https://www.deldot.gov/Publications/manuals/standard_specifications/index.shtml)

Copies of the Supplemental Specifications can be printed from the Website.

**The Contractor shall make himself aware of these revisions and corrections (Supplemental Specifications), and apply them to the applicable item(s) of this contract.**

# **SPECIAL PROVISIONS**

**CONSTRUCTION ITEM NUMBERS**

All construction pay items are assigned a six (6) digit number, shown as Item Number on the Plans and/or in the Special Provisions, and shall be interpreted in accordance with the following:

**Standard Item Number:**

The first three digits of the construction item numbers indicates the Section number as described in the Standard Specifications, and all applicable requirements of the Section shall remain effective unless otherwise modified by the Special Provisions. The last three digits of the construction item identifies the item by sequential number under that Section. A comprehensive list of construction item numbers are listed in the Standard Specifications. Additions to this list will be made as required.

**Special Provisions Item Number:**

The first three digits of the construction items, covered under Special Provisions, indicates the applicable Section number of the Standard Specifications, and shall be governed fully by the requirements of the Special Provisions. The last three digit of the items covered under Special Provisions identifies the item by sequential number.

Examples

**Standard Item Number - 202000 Excavation and Embankment**

202 Indicates Section Number

000 Indicates Sequential Number

**Special Provision Item Number - 202500 Grading and Reshaping Roadway**

202 Indicates Section Number

500 Indicates Sequential Number

**401502 - ASPHALT CEMENT COST ADJUSTMENT**

For Sections 304, 401, 402, 403, 404, and 405, payments to the Contractor shall be adjusted to reflect increases or decreases in the Delaware Posted Asphalt Cement Price when compared to the Project Asphalt Cement Base Price, as defined in these Special Provisions.

The Delaware Posted Asphalt Cement Price will be issued monthly by the Department and will be the industry posted price for Asphalt Cement, F.O.B. Philadelphia, Pennsylvania. The link for the [posting is here](#).

The Project Asphalt Cement Base Price will be the Delaware Posted Asphalt Cement Price in effect on the date of advertisement.

All deviations of the Delaware Posted Asphalt Cement Price from the Project Asphalt Cement Base Price are eligible for cost adjustment. No minimum increases or decreases or corresponding percentages are required to qualify for cost adjustment.

Actual quantity of asphalt cement qualifying for any Asphalt Cement Cost Adjustment will be computed using the weight of eligible asphalt that is shown on the QA/QC pay sheets as a percentage for the delivered material.

If the mix was not inspected and no QA/QC pay sheet was generated, then the asphalt percentage will be obtained from the job mix formula for that mix ID.

The asphalt percentage eligible for cost adjustment shall only be the virgin asphalt cement added to the mix.

There shall be no separate payment per ton cost of asphalt cement. That cost shall be included in the various unit prices bid per ton for those bid items that contain asphalt cement (mentioned above).

The Asphalt cement cost adjustment will be calculated on grade PG 64-22 asphalt regardless of the actual grade of asphalt used. The Project Asphalt Cement Base Price per ton for the project will be the Delaware Posted Asphalt Cement Price in effect on the date of project advertisement.

If the Contractor exceeds the authorized allotted completion time, the price of asphalt cement on the last authorized allotted work day, shall be the prices used for cost adjustment during the time liquidated damages are assessed. However, if the industry posted price for asphalt cement goes down, the asphalt-cement cost shall be adjusted downward accordingly.

**NOTE:**

Application of Asphalt Cement Cost Adjustment requirements as indicated above shall apply only to those contracts involving items related to bituminous base and pavements, and with bitumen, having a total of 1,000 tons or more of hot-mix bid quantity in case of Sections 401, 402 and 403; and 15,000 gallons or more in case of Sections 304, 404 and 405.

5/05/15

**401699 - QUALITY CONTROL/QUALITY ASSURANCE OF BITUMINOUS CONCRETE**

**.01 Description**

This item shall govern the Quality Assurance Testing for supplying bituminous asphalt plant materials and constructing bituminous asphalt pavements and the calculation for incentives and disincentives for materials and construction. The Engineer will evaluate all materials and construction for acceptance. The procedures for acceptance are described in this Section. Include the costs for all materials, labor, equipment, tools, and incidentals necessary to meet the requirements of this specification in the bid price per ton for the bituminous asphalt. Payment to the Contractor for the bituminous asphalt item(s) will be based on the Contract price per ton and the pay adjustments described in this specification.

**.02 Bituminous Concrete Production – Quality Acceptance**

**(a) Material Production - Tests and Evaluations.**

All acceptance tests shall be performed by qualified technicians at qualified laboratories following AASHTO or DelDOT procedures, and shall be evaluated using Quality Level Analysis. The Engineer will conduct acceptance tests. The Engineer will directly base acceptance on the acceptance test results, the asphalt cement quality, the Contractor's QC Plan work, and the comparisons of the acceptance test results to the QC test results. The Engineer may elect to utilize test results of the Contractor in some situations toward judging acceptance.

Supply and capture samples, as directed by the Engineer under the purview of the Engineer from delivery trucks before the trucks leave the production plant. Hand samples to the Engineer to be marked accordingly. The sample shall represent the material produced by the Contractor, and shall be of sufficient size to allow the Engineer to complete all required acceptance tests. The Engineer will direct the Contractor when to capture these samples, on a statistically random, unbiased basis, established before production begins each day based upon the anticipated production tonnage. The captured sample shall be from the Engineer specified delivery truck. The Contractor may visually inspect the specified delivery load during sampling and elect to reject the load. If the contractor elects to reject the specified delivery truck, each subsequent load will be inspected until a visually acceptable load is produced for acceptance testing. All visually rejected loads shall not be sent to a Department project.

The first sample of the production day will be randomly generated by the Engineer between loads 0 and 12 (0-250 tons). Subsequent samples will be randomly generated by the Engineer on 500-ton sublots for the production day. Samples not retrieved in accordance with the Contractor's QC plan will be deemed unacceptable and may be a basis for rejection of material produced. Parallel tests or dispute resolution tests will only be performed on material captured at the same time and location as the acceptance test sample. Parallel test samples or Dispute Resolution samples will be created by splitting a large sample or obtaining multiple samples that equally represent the material. The Engineer will perform all splitting and handling of material after it is obtained by the Contractor.

The Contractor may retain dispute resolution samples or perform parallel tests with the Engineer on any acceptance sample.

The Engineer will evaluate and accept the material on a lot basis. All the material within a lot shall have the same JMF (mixture ID). The lot size shall be targeted for 2000 tons or a maximum period of three days, whichever is reached first. If the 2000<sup>th</sup> ton target lot size is achieved during a production day, the lot size shall extend to the end of that production day. The Contractor may interrupt the production of one JMF in order to produce different material; this type of interruption will not alter the determination of the size or limits of material represented by a lot. The Engineer will evaluate each lot on a subplot basis. The size for each subplot shall be 100 to 500 tons and testing for the sub lots will be completed on a daily basis. For each subplot, the Engineer will evaluate one sample.

The target size of sub-lots within each lot, except for the first sample of the production day, is equal-sized 500 ton sub lots and will be based upon anticipated production, however, more or fewer sublots, with differing sizes, may result due to the production schedule and conditions. If the actual production is less than anticipated, and it's determined a sample will not be obtained (based upon the anticipated

tonnage), a new sample location will be determined on a statistically random, unbiased basis based upon the new actual production. If the actual production is going to be 50 tons or greater over the anticipated sub lot production, a new sample location will be determined on a statistically random, unbiased basis based upon the new actual production. The Engineer will combine the evaluation and test results for all of the applicable sublots in order to evaluate each individual lot.

If the Engineer is present, and the quantity exceeds 25 tons, a statistically random sample will be used for analysis. When the anticipated production is less than 100 tons and greater than 25 tons, and the Engineer is not present, the contractor shall randomly select a sample using the Engineer's random location program. The captured sample shall be placed in a suitable box, marked to the attention of the Engineer, and submitted to the Engineer for testing. A box sample shall also be obtained by the contractor at the same time and will be used as the Dispute Resolution sample if requested by the Engineer. The Contractor shall also obtain one liquid asphalt sample (1 pint) per grade of asphalt used per day and properly label it with all pertinent information.

The Engineer will conduct the following tests in order to characterize the material for the pavement compaction quality and to judge acceptance and the pay adjustment for the material:

- AASHTO T312 - Preparing and Determining the Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyrotory Compactor
- AASHTO T166, Method C (Rapid Method) - Bulk Specific Gravity of Compacted Hot Mix Asphalt (HMA) Using Saturated Surface Dry Specimens
- AASHTO T308 - Determining the Asphalt Binder Content of Hot Mix Asphalt (HMA) by the Ignition Method
- AASHTO T30 - Mechanical Analysis of Extracted Aggregate
- AASHTO T209 - Theoretical Maximum Specific Gravity and Density of Hot Mix Asphalt (HMA)
- ASTM D7227 - Standard Practice for Rapid Drying of Compacted Asphalt Specimens using Vacuum Drying Apparatus

**(b) Pavement Construction - Tests and Evaluations.**

The Engineer will directly base acceptance on the compaction acceptance test results, and on the inspection of the construction, the Contractor's QC Plan work, ride smoothness as referenced in the contract documents, lift thickness as referenced in the contract documents, joint quality as referenced in the contract documents, surface texture as referenced in the contract documents, and possibly the comparisons of the acceptance test results to the independent test results. For the compaction acceptance testing, the Engineer will sample the work on a statistically random basis, and will test and evaluate the work based on daily production.

Notify the Engineer of any locations within that road segment that may not be suitable to achieve minimum (93%) compaction due to existing conditions prior to paving the road segment. Schedule and hold a meeting in the field with the Engineer in order to discuss all areas that may potentially be applicable to Table 5a before paving starts. Areas that will be considered for Table 5a will be investigated in accordance to the method described in Appendix B. If this meeting is not held prior to paving, no areas will be considered for Table 5a. Areas of allowable exemptions that will not be cored include the following: partial-depth patch areas, driveway entrances, paving locations of less than 100 tons, areas around manholes and driveway entrances, and areas of paving that are under 400 feet in continuous total length and/or 5 feet in width.

The exempt areas around manholes will be a maximum of 4 feet transversely on either side from the center of the manhole, and 20 feet longitudinally on either side from the center of the manhole. The exempt areas around driveway entrances shall be the entire width of the driveway, and 3 feet from the edge of the longitudinal joint next to the driveway. Areas of exemption that will be cored for informational purposes only include: areas where the mat thickness is less than three times the nominal maximum aggregate size as directed by the Engineer, violations of Section 401.08 in the Standard Specifications as directed by the Engineer, and areas shown to contain questionable subgrade properties as proven by substantial yielding under a fully legally loaded truck. Failure to obtain core samples in these areas will result in zero payment for compaction regardless of the exempt status.

The Engineer will evaluate and accept the compaction work on a daily basis. Payment for the compaction will be calculated by using the material production lots as referenced in **.02 Acceptance Plan (a) Material Production - B Tests and Evaluation** and analyzing the compaction results over the individual days covered in the material production lot. The compaction results will be combined with the material results to obtain a payment for this item.

The minimum size of a compaction lot shall be 100 tons. If the compaction lot is between 101 and 1000 tons, the Engineer shall randomly determine four compaction acceptance test locations. If the compaction lot is between 1001 and 1500 tons, the Engineer shall randomly determine six compaction acceptance test locations. If the compaction lot is between 1501 and 2000 tons, the Engineer shall randomly determine eight compaction acceptance test locations. If the compaction lot is greater than 2000 tons, the Engineer shall randomly determine two compaction acceptance test locations per 500 tons.

If a randomly selected area falls within an Engineer approved exemption area, the Engineer will select one more randomly generated location to be tested per the requirements of this Specification. If that cannot be accomplished, or if an entire location has been declared exempt, the compaction testing shall be performed as per these Specifications but a note will be added to the results that the location was an Engineer approved exempt location.

Testing locations will be a minimum of 1.0 feet from the newly placed longitudinal joint and 50 feet from a new transverse joint.

Cut one six (6) inch diameter core through the full lift depth at the exact location marked by the Engineer. Cores submitted that are not from the location designated by the Engineer will not be tested and will be paid at zero pay.

Notify the Engineer prior to starting paving operations with approximate tonnage to be placed. The Contractor is then responsible for notifying the appropriate Engineer test personnel within 12 hours of material placement. The Engineer will mark core locations within 24 hours of notification. After determination of locations, the Contractor shall complete testing within two operational days of the locations being marked. If the cores are not cut within two operational days, the area in question will be paid at zero pay for compaction testing.

Provide any traffic control required for the structural number investigation, sampling, and testing work at no additional cost to the Department.

Commence coring of the pavement after the pavement has cooled to a temperature of 140°F or less. Cut each core with care in order to prevent damaging the core. Damaged cores will not be tested. Label each core with contract number, date of construction, and number XX of XX upon removal from the roadway. Place cores in a 6-inch diameter plastic concrete cylinder mold or approved substitute for protection. Separate cores in the same cylinder mold with paper. Attach a completed QC test record for the represented area with the corresponding cores. The Engineer will also complete a test record for areas tested for the QA report and provide to Materials & Research. Deliver the cores to the Engineer for testing, processing, and report distribution at the end of each production day.

Repair core holes per Appendix A, Repairing Core Holes in Bituminous Asphalt Pavements. Core holes shall be filled immediately. Failure to repair core holes at the time of coring will result in zero pay for compaction testing for the area in question.

The Engineer will conduct the following tests on the applicable portion of the cores in order to evaluate their quality:

- AASHTO T166, Method C (Rapid Method) – Bulk Specific Gravity of Compacted Hot Mix Asphalt (HMA) Using Saturated Surface Dry Specimens
- AASHTO T209 - Theoretical Maximum Specific Gravity and Density of Hot Mix Asphalt
- ASTM D7227 - Standard Practice for Rapid Drying of Compacted Asphalt Specimens using Vacuum Drying Apparatus

The Engineer will use the average of the last five test values of the same JMF (mixture ID) material at the production plant in order to calculate the average theoretical maximum specific gravity of the cores.

The average will be based on the production days test results and as many test results needed from previous days production to have an average of five samples. If there are less than five values available, the Engineer will use the JMF design value in addition to the available values to calculate the average theoretical maximum specific gravity.

**.03 Payment and Pay Adjustment Factors.**

The Engineer will determine pay adjustments for the bituminous asphalt item(s) in accordance with this specification. The Engineer will determine a pay adjustment factor for the material produced and a pay adjustment factor for the pavement construction. Pay adjustments for material and construction will be calculated independently. When the pay adjustment calculation for either material or construction falls to zero payment per tables 4, 5, or 5a, the maximum pay adjustment for the other factor will not exceed 100.

Pay Adjustment factors will only be calculated on in place material. Removed material will not be used in payment adjustment calculations.

Material Production Pay Adjustments will be calculated based upon 70% of the contract unit price and calculated according to section .03(a) of this specification. Pavement construction Pay Adjustments will be calculated based upon 30% of the contract unit price and calculated according to section .03(b) of this specification.

**(a) Material Production - Pay Adjustment.**

Calculate the material pay adjustment by evaluating the production material based on the following parameters:

<b>Table 2 - Material Parameter Weight Factors</b>		
<b>Material Parameter</b>	<b>Single Test Tolerance (+/-)</b>	<b>Weight Factor</b>
Asphalt Content	0.4	0.30
#8 Sieve (>=19.0 mm)	7.0	0.30
#8 Sieve (<=12.5 mm)	5.0	0.30
#200 Sieve (0.075mm Sieve)	2.0	0.30
Air Voids (4.0% Target)	2.0	0.10

Using the JMF target value, the single test tolerance (from Table 2), and the test values, the Engineer will use the following steps to determine the material pay adjustment factor for each lot of material:

1. For each parameter, calculate the mean value and the standard deviation of the test values for the lot to the nearest 0.1 unit.
2. For each parameter, calculate the Upper Quality Index (QU):  
 $QU = ((JMF \text{ target}) + (\text{single test tolerance}) - (\text{mean value})) / (\text{standard deviation}).$
3. For each parameter, calculate the Lower Quality Index (QL):  
 $QL = (\text{mean value}) - (JMF \text{ target}) + (\text{single test tolerance}) / (\text{standard deviation}).$
4. For each parameter, locate the values for the Upper Payment Limit (PU) and the Lower Payment Limit (PL) from Table 3 - Quality Level Analysis by the Standard Deviation Method. (Use the column for “n” representing the number of sublots in the lot. Use the closest value on the table when the exact value is not listed).
5. Calculate the PWL for each parameter from the values located in the previous step:  
 $PWL = PU + PL - 100.$
6. Calculate each parameter’s contribution to the payment adjustment by multiplying its PWL by the weight factor shown in Table 2 for that parameter.
7. Add the calculated adjustments of all the parameters together to determine the Composite PWL for the lot.

8. From Table 4, locate the value of the Pay Adjustment Factor corresponding to the calculated PWL. When all properties of a single test are within the single test tolerance of Table 2, Pay Adjustment factors shall be determined by Column B. When any property of a single test is outside of the Single Test Tolerance parameters defined in Table 2, the Material Pay Adjustment factor shall be determined by Column C
9. For each lot, determine the final material price adjustment:

Final Material Pay Adjustment =  
 (Lot Quantity) x (Item Bid Price) x (Pay Adjustment Factor) x 70%. This final pay calculation will be paid to the cent.

In lieu of being assessed a pay adjustment penalty, the Contractor may choose to remove and replace the material at no additional cost to the Department. When the PWL of any material parameter in Table 2 is below 60, the Engineer may require the removal and replacement of the material at no additional cost to the Department. Test results on removed material shall not be used in calculation of future PWL calculations for Mixture ID.

The test results from the Engineer on production that is less than 100 tons will be combined with the two most recently completed Engineer tests with the same Mixture ID to calculate payment for the lot encompassing the single test. If that cannot be accomplished, the approved JMF will be used to calculate payment for the lot encompassing the single test. Payment for previously closed lots will not be affected by the analysis.

When a sample is outside of the allowable single test tolerance for any Materials criteria in Table 2, that sample will be isolated. For payment purposes, the test result of the out of acceptable tolerance sample will be combined with the two previous acceptable samples of the same JMF and analyzed per this specification. The material that is considered out of the acceptable tolerance will only include the material within the represented sub-lot (i.e., a maximum of 500 tons). If the previous acceptable test result is from the previous production day, only the material produced on the second production day will be considered out of tolerance. All future sub lots will not include the isolated test. The pay factors for the out of tolerance sample lot will be calculated using column C of table 4.

If, during production, a QA sample test result does not meet the acceptable tolerances and the Contractors QC sample duplicates the QA sample test result, the Contractor can make an appropriate change to the mixture (within the JMF boundaries), and request to have that sample further isolated. After the Contractor has made appropriate changes, the Contractor will visually inspect each produced load. The first visually acceptable load will be sampled and tested. If that sample test result shows compliance with the specifications, the material that is considered out of the acceptable tolerance will include the material from the previous acceptable test result to the third load after the initially sampled and tested sample. If the sample does not meet the specification requirements, the Engineer will no longer accept material. Production may resume when changes have been made and an acceptable sample and test result is obtained.

PU or PL	QU and QL for “n” Samples						
	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9
100	1.16	1.50	1.79	2.03	2.23	2.39	2.53
99	-	1.47	1.67	1.80	1.89	1.95	2.00
98	1.15	1.44	1.60	1.70	1.76	1.81	1.84
97	-	1.41	1.54	1.62	1.67	1.70	1.72
96	1.14	1.38	1.49	1.55	1.59	1.61	1.63
95	-	1.35	1.44	1.49	1.52	1.54	1.55
94	1.13	1.32	1.39	1.43	1.46	1.47	1.48
93	-	1.29	1.35	1.38	1.40	1.41	1.42
92	1.12	1.26	1.31	1.33	1.35	1.36	1.36
91	1.11	1.23	1.27	1.29	1.30	1.30	1.31

90	1.10	1.20	1.23	1.24	1.25	1.25	1.26
89	1.09	1.17	1.19	1.20	1.20	1.21	1.21
88	1.07	1.14	1.15	1.16	1.16	1.16	1.17
87	1.06	1.11	1.12	1.12	1.12	1.12	1.12
86	1.04	1.08	1.08	1.08	1.08	1.08	1.08
85	1.03	1.05	1.05	1.04	1.04	1.04	1.04
84	1.01	1.02	1.01	1.01	1.00	1.00	1.00
83	1.00	0.99	0.98	0.97	0.97	0.96	0.96
82	0.97	0.96	0.95	0.94	0.93	0.93	0.93
81	0.96	0.93	0.91	0.90	0.90	0.89	0.89
80	0.93	0.90	0.88	0.87	0.86	0.86	0.86
79	0.91	0.87	0.85	0.84	0.83	0.82	0.82
78	0.89	0.84	0.82	0.80	0.80	0.79	0.79
77	0.87	0.81	0.78	0.77	0.76	0.76	0.76
76	0.84	0.78	0.75	0.74	0.73	0.73	0.72
75	0.82	0.75	0.72	0.71	0.70	0.70	0.69
74	0.79	0.72	0.69	0.68	0.67	0.66	0.66
73	0.75	0.69	0.66	0.65	0.64	0.63	0.63
72	0.74	0.66	0.63	0.62	0.61	0.60	0.60
71	0.71	0.63	0.60	0.59	0.58	0.57	0.57
70	0.68	0.60	0.57	0.56	0.55	0.55	0.54
69	0.65	0.57	0.54	0.53	0.52	0.52	0.51
68	0.62	0.54	0.51	0.50	0.49	0.49	0.48
67	0.59	0.51	0.47	0.47	0.46	0.46	0.46
66	0.56	0.48	0.45	0.44	0.44	0.43	0.43
65	0.52	0.45	0.43	0.41	0.41	0.40	0.40
64	0.49	0.42	0.40	0.39	0.38	0.38	0.37
63	0.46	0.39	0.37	0.36	0.35	0.35	0.35
62	0.43	0.36	0.34	0.33	0.32	0.32	0.32

Table 3 - Quality Level Analysis by the Standard Deviation Method							
PU or PL	QU and QL for "n" Samples						
	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9
61	0.39	0.33	0.31	0.30	0.30	0.29	0.29
60	0.36	0.30	0.28	0.27	0.27	0.27	0.26
59	0.32	0.27	0.25	0.25	0.24	0.24	0.24

Table 4 - PWL Pay Adjustment Factors		
PWL	Pay Adjustment Factor (%) Column B	Pay Adjustment Factor (%) Column C
100	+5	0
99	+4	-1
98	+3	-2

97	+2	-3
96	+1	-4
95	0	-5
94	-1	-6
93	-2	-7
92	-3	-8
91	-4	-9
PWL<91	PWL - 100	PWL - 100

**(b) Pavement Construction - Pay Adjustments.**

The Engineer will determine the pavement construction pay adjustment by evaluating the construction of the pavement, based on the following parameter:

- Degree of compaction of the in-place material

Using the test values for the cores, the Engineer will use the following steps to determine the pavement construction pay adjustment for each lot of work. .

1. Calculate the core bulk specific gravity values from the subplot tests values, to the nearest 0.001 unit. Obtain the Theoretical maximum Specific Gravity values from the corresponding laboratory subplot tests.
2. Calculate the Degree of Compaction:  
Degree of Compaction =  
 $((\text{Core Bulk Specific Gravity}) / (\text{Theoretical Maximum Specific Gravity})) \times 100\%$  recorded to the nearest 0.1%.
3. The average compaction for the sublots shall be averaged together for the compaction level of the lot. The lots compaction test level shall be averaged and recorded to the nearest whole percent.
4. Locate the value of the Payment Adjustment Factor corresponding to the calculated degree of compaction from Table 5 or Table 5a.
5. Determine the pavement construction price adjustment by using the following formula:  
Construction Pay adjustment = (Lot Quantity) x (Bid Price) x (Pay Adjustment Factor) x 30%.

<b>Table 5: Compaction Price Adjustment Highway Locations</b>		
Degree of Compaction (%)	Range	Pay Adjustment Factor (%)
$\geq 97.0$	$\geq 96.75$	-100*
96.5	96.26 – 96.74	-5
96.0	95.75 – 96.25	-3
95.5	95.26 – 95.74	-2
95.0	94.75 – 95.25	0
94.5	94.26 – 94.74	0
94.0	93.75 – 94.25	1

93.5	93.26 – 93.74	3
93.0	92.75 – 93.25	5
92.5	92.26 – 92.74	3
92.0	91.75 – 92.25	0
91.5	91.26 – 91.74	0
91.0	90.75 – 91.25	-5
90.5	90.26 – 90.74	-15
90.0	89.75 – 90.25	-20
89.5	89.26 – 89.74	-25
89.0	88.75 – 89.25	-30
88.5	88.26 – 88.74	-50
=<88.0	=<88.25	-100*

\* or remove and replace it at Engineer's discretion

<b>Table 5A: Compaction Price Adjustment Other<sup>1</sup> Locations</b>		
Degree of Compaction	Range	Pay Adjustment Factor (%)
>= 97.0	>= 96.75	-100*
96.5	96.26 – 96.74	-5
96.0	95.75 – 96.25	-3
95.5	95.26 – 95.74	-2
95.0	94.75 – 95.25	0
94.5	94.26 – 94.74	0
94.0	93.75 – 94.25	0
93.5	93.26 – 93.74	1
93.0	92.75 – 93.25	3
92.5	92.26 – 92.74	1
92.0	91.75 – 92.25	0
91.5	91.26 – 91.74	0
91.0	90.75 – 91.25	0
90.5	90.26 – 90.74	0
90.0	89.75 – 90.25	0
89.5	89.26 – 89.74	0
89.0	88.75 – 89.25	-1
88.5	88.26 – 88.74	-3
88.0	87.75 – 88.25	-5

87.5	87.26 – 87.74	-10
87.0	86.75 – 87.25	-15
86.5	86.26 – 86.74	-20
86.0	85.75 – 86.25	-25
85.5	85.26 – 85.74	-30
85.0	84.75 – 85.25	-40
84.5	84.26 – 84.74	-50
=< 84.0	=<84.25	-100*

\* or remove and replace at Engineer's discretion

<sup>1</sup> This chart is to be used for areas where the structural value of the area to be paved is less than 1.75 as determined by the Engineer. See Appendix B - Method for Obtaining Cores for Determination of Roadway Structure. This chart is applicable to rehabilitation work only; full depth construction will not be considered for Table 5a.

**.04 Dispute Resolution.**

Disputes or questions about any test result shall be brought to the attention of the Contractor and the Engineer within two operational days of reported test results. The following dispute resolution procedures will be used.

The Engineer and the Contractor will review the sample quality, the test method, the laboratory equipment, and the laboratory technician. If these factors are not the cause of the dispute, a third party dispute resolution will be used.

Third party resolution testing can be performed at either another Contractor’s laboratory, the Engineer’s laboratory, or an independent accredited laboratory. Unless otherwise mutually agreed upon by DAPA and the Engineer, the Engineer’s qualified laboratory in Dover and qualified personnel shall conduct the necessary testing for third party Dispute Resolution after the Engineer has provided reasonable notice to allow the Contractor to witness this testing.

When disputes over production testing occur, the samples used for Dispute Resolution testing will be those samples the properly captured, labeled, and stored, as described in the second paragraph of the section of these specifications titled **.02 Acceptance Plan, (a) Material Production - Tests and Evaluations**. If no samples are available, the original testing results will be used for payment calculations.

Dispute Resolution samples for air void content will be heated by a microwave oven.

If there is a discrepancy between the Engineer’s acceptance test result and the Contractor’s test result, the Contractor may ask for the Dispute Resolution sample to be tested. The Contractor may request up to two dispute resolution samples be tested per calendar year without charge. Any additional Dispute Resolution samples run at the Contractors request where the results substantiate the acceptance test result will be assessed a fee of \$125. Any additional Dispute Resolution samples that substantiate the Contractors test result will not be assessed the fee.

When disputes over compaction core test results occur, the Engineer’s acceptance core will be used for the dispute resolution sample. The Contractor will be advised on when the testing will occur as referenced above to witness the testing.

The results of the dispute resolution testing shall replace all of the applicable disputed test results for payment purposes.

## **Appendix A - Repairing Core Holes in Bituminous Asphalt Pavement**

### **Description.**

This appendix describes the procedure required to repair core holes in a bituminous concrete pavement.

### **Materials and Equipment.**

The following material shall be available to complete this work:

- Patch Material - DelDOT approved High Performance Cold Patch material shall be used.

The following equipment shall be available to complete this work:

- Sponge or other absorbent material - Used to extract water from the hole.
- Compaction Hammer - mechanical (electrical, pneumatic, or gasoline driven) tamping device with a flat, circular tamping face smaller than 6 inches in diameter. .

### **Construction Method.**

After core removal from the hole, remove all excess water from within the hole, and prevent water from re-entering the hole.

Place the patch material in lifts no greater than 3 inches and compact with mechanical tamping device. If the hole is deeper than 3 inches, use two lifts of approximately equal depths so that optimum compaction is achieved. Make sure that the patch surface matches the grade of the existing roadway. Make every effort to achieve the greatest possible compaction

### **Performance Requirements.**

The Engineer will judge the patch on the following basis:

- The patch shall be well compacted
- The patch surface shall match the grade of the surrounding roadway surface.

### **Basis of Payment.**

No measurement or payment will be made for the patching work. The Contractor must gain the Engineer's acceptance of the patching work before the Engineer will accept the material represented by the core.

**Appendix B - Method for Obtaining Cores for Determination of Roadway Structure**

The Contractor is responsible for obtaining cores in areas that they propose are eligible for compaction price adjustments according to Table 5a in this specification. Table 5a is not applicable for new full-depth pavement box construction. Cores submitted for this process shall be obtained according to the following process.

1. Contact Materials & Research (M&R) personnel to determine if information about the area is already available. If M&R has already obtained cores in the location that is being investigated, the contractor may opt to use the laboratory information for the investigation and not core the area on their own.
2. If M&R does not have information concerning the section of the roadway, the contractor needs to contact M&R to arrange for verification of coring operations. Arrangements shall be made to allow for an individual from M&R to be on the site when the cores are obtained. Cores will be turned over to M&R for evaluation.
3. The Contractor is responsible for providing all traffic control and repairing core holes in accordance to 401699 Appendix A - Repairing Core Holes in Bituminous Asphalt Pavements.
4. Cores are to be taken throughout the entire project for the area in question. Cores will be spaced, from the start of the project in increments determined based on field and project specifics. Cores will be evenly distributed throughout the project location. The cores will be taken in the center of the lane in question.
5. Additional cores may be taken at other locations, if surface conditions indicate that there may be a substantial difference in the underlying section. The location of these cores should be documented and submitted to M&R.
6. Cores shall be full depth and include underlying materials. If there is a stone base included in the pavement section, at a minimum 1 core must have information concerning the thickness of the base. This is determined by augering to the subgrade surface.
7. The calculations used to determine the structural capacity of the roadway is as follows. If the contractor finds, upon starting the coring process, that the areas are of greater thickness than applicable to Table 5a, they may terminate the coring process on their own and retract the request.

**Structural Number Calculations**

Each pavement box material is assigned a structural coefficient based upon AASHTO design guides. The structural coefficient is used to determine the total strength of the pavement section.

Materials used in older pavement sections are assigned lower structural coefficients to compensate for aging of the materials. The coefficients used to determine the structural number of an existing pavement are:

<b>Existing Material</b>	<b>Structural Coefficient</b>
HMA	0.32
Asphalt Treated Base	0.26
Soil Cement	0.16
Surface Treatment (Tar & Chip)	0.10
GABC	0.14
Concrete	0 - 0.7*

\* The Structural Coefficient of Concrete is dependent upon the condition of the concrete. Compressive strengths & ASR analysis are used to determine condition - contact the Engineer if this situation arises.

Newly placed materials use a different set of structural coefficients. They are as follows:

New Material	Structural Coefficient
HMA	0.40
Asphalt Treated Base (BCBC)	0.32
Soil Cement	0.20
GABC	0.14

**Example:**

Location includes placement of a 1.25" Type C overlay on 2.25" Type B. Existing roadway is cored and is shown to consist of 2" HMA on 7" GABC.

Calculation:

For the Type B lift the calculation would be:

Existing HMA	2 * 0.32	=	0.64
GABC	7 * 0.14	=	0.98
			<hr/>
			1.62

For the Type C lift the calculation would be:

Newly Placed B	2.25 * 0.4	=	0.90
Existing HMA	2 * 0.32	=	0.64
GABC	7 * 0.14	=	0.98
		=	<hr/>
			2.52

11/3/14

**701505 - PORTLAND CEMENT CONCRETE PARKING BUMPER**

**Description:**

This work consists of furnishing and installing portland cement concrete bumpers in accordance with the details and notes shown on Plans. The locations of installing the parking bumpers shall be in accordance with Plans or will be determined in the field by the Engineer.

**Materials and Construction Methods:**

Portland cement concrete shall be Class B, and shall conform to the requirements of Section 1022, and bar reinforcement shall conform to Section 611 of the Standard Specifications.

Unless specified otherwise on the Plans, each parking bumper shall be anchored with two (2) 18 inch number 13 rebars driven flush with the top of the bumper. Any surface preparation necessary to provide a stable installation of the bumpers will be considered incidental to this item.

**Method of Measurement:**

The quantity of P.C.C. parking bumpers will be measured as the actual number of bumpers installed and accepted.

**Basis of Payment:**

The quantity of P.C.C. parking bumpers will be paid for at the Contract unit price per each. Price and payment will constitute full compensation for furnishing all materials including, but not limited to, concrete, bar reinforcement, anchor pins, installing the bumper as directed, for all labor, equipment, tools and incidentals to complete the item.

8/29/2018

**710500 - INSTALLATION OF WATER MAIN AND ACCESSORIES**

**Description:**

The items shall consist of installing the Artesian Water Company, Inc. (“AWC”) water main and accessories in accordance with the locations, details and notes on the Plans, and as directed by the Engineer. The work shall be performed in accordance with these Special Provisions, Delaware Standard Specifications, and the requirements of the Standards and Specifications of AWC. In case of conflict between these Special Provisions, Delaware Standard Specifications, and the Standards and Specifications of AWC, the Standards and Specifications and all other requirements of AWC shall prevail. Prior to this item, the existing water main shall be removed as specified in Provision 710501 – Removal of Existing Water Main and Accessories.

**Materials:**

Waterline materials such as pipe, valves, fittings, and other accessories as listed on the attached Material Take-off Sheet under this Special Provisions shall be supplied by AWC.

The Contractor shall be responsible for providing all other materials not included on the attached Material Take-off Sheet that are necessary to complete the waterline installation.

Portland Cement Concrete required for the job shall be Class B, and shall conform to Section 1022 of the Delaware Standard Specifications.

**Water Main Installation Description of Work:**

**INSTALLATION OF NEW FACILITIES**

1. Artesian shall supply all pipe, fittings, valves, valve boxes, roller hanger assemblies and modular end seals required for the project and as indicated on the attached Material Take-off Sheet.
2. Contractor shall install new 14” diameter pipe sleeves through each abutment wall in accordance with the waterline support details. Centerline of new sleeves to match the centerline of the existing pipe.
3. Contractor shall install new roller pipe supports in accordance with manufacturers specifications at existing interior steel channel diaphragms as per plan, reusing existing both holes in diaphragms. At Piers and Abutment B, install new roller pipe supports in proposed concrete diaphragms in accordance with waterline support details shown in the plans.
4. Contractor shall install new 8” TR-Flex ductile iron pipe, per plan, between Stations 48+02.58 and 50+98.27, a distance of approximately 296’. Lay pipe in the direction of station back so that the pipe bell is laid before connecting segment. Install TR-Flex ductile iron pipe in accordance with manufacturers recommendations. The new 8” TR-Flex ductile iron pipe below the bridge shall be installed across the new roller pipe supports. Match the horizontal and vertical alignment of the existing pipe. Placement of pipe joints and attachment of pipe to the roller supports shall be in accordance with waterline support details shown in the plans.
5. At the abutments, Contractor shall install the new 8” TR-Flex ductile iron pipe through the new 14” pipe sleeves and seal annular space using link-seal modular seal.
6. Contractor shall install 8” caps, jumper assembly and blow-off assembly on the ends of the new 8” TR-Flex ductile iron pipe at Station 48+02.58 and 50+98.27, in accordance with the waterline support details shown in the plans.
7. Contractor shall test completed section of TR-Flex ductile iron pipe for leakage in accordance with the requirements of AWWA C600, 2-hour duration at 150 psi. All tests shall be coordinated with the AWC Inspector.
8. Contractor shall disinfect all new water mains in accordance with AWWA C601, latest edition. Disinfection shall be coordinated with the AWC Inspector.

9. AWC shall be responsible for obtaining bacteriological tests to show that the disinfection has been satisfactory and the main can be placed in service.
10. Contractor shall remove the end caps, jumper assembly and blow-off assembly.
11. Contractor shall connect the new 8" TR-Flex ductile iron pipe to the existing 8" cast iron main at Station 47+90 and 51+10 using new 8" gate valves and 8" sleeves in accordance with the waterline valve details shown in the plans.
12. Contractor shall coordinate with the AWC Inspector to return the water system to normal operating conditions.

**Installation of Water Main General Notes:**

1. All water main installation and tie-ins shall be performed by an approved AWC contractor. Contractor shall contact AWC for the latest list of approved contractors. Contractor or perspective subcontractors may apply to become approved AWC contractors by contacting AWC for the latest Contractor Qualification Package.
2. Contractor will be required to execute an AWC Contractor Agreement prior to start of waterline activities. A sample agreement is included in these provisions for reference.
3. Depth and location of water main in project area is based on best available information. Actual location of connection between existing pipe and new pipe may be adjusted as directed by AWC based on field conditions.
4. No valve or other control on the existing system shall be operated for any purpose by Contractor. The proper AWC personnel will operate all existing system devices
5. Hydrant connections by Contractor are prohibited. This method may not be utilized during any phase of the project.
6. Contractor shall contact the AWC Inspector at (302) 218-0489 at least 1 week prior to the start of construction. A representative from AWC must observe and approve all water utility work in accordance with these Special Provisions, Delaware Standard Specifications, and the requirements of the Standards and Specifications of AWC.
7. Contractor shall field verify all utilities prior to the start of construction.
8. All excavations for installation of water main and accessories shall be kept free from water.
9. A minimum ten feet (10') horizontal and eighteen inch (18") vertical separation, as measured from the outside of each pipe, shall be provided for all water mains from sanitary sewer (gravity and force mains) and storm sewers. A minimum eighteen inch (18") vertical separation shall be provided between the water main and any crossing utility.
10. Contractor shall provide accurate as-built information to the AWC Inspector and Engineer prior to substantial completion of the work indicating both horizontal and vertical coordinates of all fittings, valves and water main (on 50' stationing), located by GPS using Delaware State Plane Coordinate System NAD83/91 horizontal and NAVD88 vertical datum.

**Method of Measurement:**

The quantity for this item will not be measured. The item Lump Sum price shall include the cost of furnishing all labor, equipment, instruments, concrete, all-thread and other material necessary to satisfactorily complete the work as herein described under this item that are a part of this contract.

**Basis of Payment:**

Payment will be made at the item Lump Sum price.

8/8/17

**720556 - BOLLARD**

**Description:**

This work consists of furnishing and installing a timber bollard in accordance with the notes and details on the Plans and as directed by the Engineer.

**Materials:**

**Timber:** All timber components shall conform with Section 1041. In addition, all timber shall conform to the following:

- a) Variations in the size of any dimension shall not be more than  $\pm$  1/2-inch.
- b) To the extent possible, all wood shall be cut and completely fabricated prior to pressure treatment with preservatives. When field fabrication of wood is required if wood is damaged, all cuts, bore holes, and damage shall be immediately treated with wood preservative in accordance with AASHTO M133.
- c) Kiln or air dried to a maximum moisture content of 25% after treatment (KDAT - 25)

**Portland Cement Concrete:** Concrete shall conform to the requirements of Section 1022, Class B of the Standard Specifications.

**Delaware No. 57 Stone:** All Delaware No. 57 Stone shall conform with Section 1004 of the Standard Specifications.

**Construction Methods:**

Construction and installation of the bollards shall be in accordance with the Section 727.03.3 of the Standard Specifications and notes and details on the Plans.

**Method of Measurement:**

The quantity of bollards will be measured as the actual number of bollards installed and accepted.

**Basis of Payments:**

The quantity of bollards will be paid for at the Contract unit price per each. Price and payment will constitute full compensation for furnishing and installing all materials including timber as described herein, Portland cement concrete, Delaware No. 57 stone, for all excavation and backfill, disposing of surplus material, for all labor, tools, equipment, and necessary incidentals to complete the work.

09/28/2018

**763501 - CONSTRUCTION ENGINEERING**

**Description:**

This work consists of construction lay out including: stakes, lines and grades as specified below. Subsection 105.10 Construction Stakes, Lines and Grades of the Standard Specifications is voided.

Based on contract plans and information provided by the Engineer, the Contractor shall stake out right-of-way and easements lines, limits of construction and wetlands, slopes, profile grades, drainage system, centerline or offset lines, benchmarks, structure working points and any additional points to complete the project.

The Engineer will only establish the following:

- (a) Original and final cross-sections for borrow pits.
- (b) Final cross-sections: Top and bottom pay limit elevations for all excavation bid items that are not field measured by Construction inspection personnel. The Contractor shall notify the Engineer when these pay limit elevations are ready and allow for a minimum of two calendar days for the Engineer to obtain the information.
- (c) Line and grade for extra work added on to the project plans.

**Equipment.** The Contractor shall use adequate equipment/instruments in a good working order. He/she shall provide written certification that the equipment/instrument has been calibrated and is within manufacturer's tolerance. The certification shall be dated a maximum of 9 months before the start of construction. The Contractor shall renew the certification a minimum of every 9 months. The equipment/instrument shall have a minimum measuring accuracy of [3mm+2ppmxD] and an angle accuracy of up to 2.0 arc seconds or 0.6 milligons. If the Contractor chooses to use GPS technology in construction stakeout, the Contractor shall provide the Engineer with a GPS rover and Automatic Level for the duration of the contract. The GPS rover shall be in good working condition and of similar make and model used by the Contractor. The Contractor shall provide up to 8 hours of formal training on the Contractor's GPS system to a maximum of four Engineer's appointees (DELDOT Construction Inspectors). At the end of the contract, the Engineer will return the GPS rover to the Contractor. If any of the equipment/instruments are found to be out of adjustment or inadequate to perform its function, such instrument or equipment shall be immediately replaced by the Contractor to the satisfaction of the Engineer. Choosing to use GPS technology does not give the contractor authority to use machine control.- Construction Engineering (GPS) Machine Control Grading shall only be used if noted in the General Notes in the plan set outlining the available files that will be provided to the Contractor and "the Release for delivery of documents in electronic form to a contractor" are signed by all parties prior to delivery of any electronic files. Only files designated in the General Notes shall be provided to the contractor. If machine control grading is allowed on the project see the "machine control" section of this specification. GPS technology and machine control technology shall not be used in the construction of bridges.

**Engineering/Survey Staff.** The Contractor shall provide and have available for the project an adequate engineering staff that is competent and experienced to set lines and grades needed to construct the project. The engineering personnel required to perform the work outlined herein shall have experience and ability compatible with the magnitude and scope of the project. Additionally, the Contractor shall employ an engineer or surveyor licensed in the State of Delaware to be responsible for the quality and accuracy of the work done by the engineering staff. When individuals or firms other than the Contractor perform any professional services under this item, that work shall not be subject to the sub contracting requirements of Subsection 108.01 of the Standard Specifications. The Contractor shall assume full responsibility for any errors and/or omissions in the work of the engineering staff described herein. If construction errors are caused due to erroneous work done under Construction Engineering the Contractor accepts full responsibility, no matter when the error is discovered. Consideration will not be given for any extension of contract time or additional compensation due to delays, corrective work, or additional work that may result from faulty and erroneous construction stakeout, surveying, and engineering required by this specification.

**Construction Methods:**

**Performance Requirements:**

- (a) Construction Engineering shall include establishing the survey points and survey centerlines; finding, referencing, offsetting the project control points; running a horizontal and vertical circuit to verify the precision of given control points. Establishing plan coordinates and elevation marks for culverts, slopes, subbase, subsurface drains, paving, subgrade, retaining walls, and any other stakes required for control lines and grades; and setting vertical control elevations, such as footings, caps, bridge seats and deck screed. The Contractor shall be responsible for the preservation of the Department's project control points and benchmarks. The Contractor shall establish and preserve any temporary control points (traverse points or benchmarks) needed for construction. Any project control points (traverse points) or benchmarks conflicting with construction of the project shall be relocated by the Contractor. The Contractor as directed by the Engineer must replace any or all stakes that are destroyed at any time during the life of the contract. The Contractor shall re-establish centerline points and stationing prior to final cross-sections by the Engineer. The Vertical Control error of closure shall not exceed 0.035 ft times. The Horizontal Control precision ratio shall have a minimum precision of 1:20,000 feet of distance traversed prior to adjustment.
- (b) The Contractor shall perform construction centerline layout of all roadways, ramps and connections, etc. from project control points set by the Engineer. The Contractor using the profiles and typical sections provided in the plans shall calculate proposed grades at the edge of pavement or verify information shown on Grades and Geometric sheets.
- (c) The Contractor shall advise the Engineer of any horizontal or vertical alignment revisions needed to establish smooth transitions to existing facilities. The Contractor must immediately bring to the attention of the Engineer any potential drainage problem within the project limits. The Engineer must approve any proposed variation in profile, width or cross slope.
- (d) The Contractor shall establish the working points, centerlines of bearings on bridge abutments and on piers, mark the location of anchor bolts to be installed, check the elevation of bearing surfaces before and after they are ground and set anchor bolts at their exact elevation and alignment as per Contract Plans. Before completion of the fabrication of beams for bridge superstructures, the Contractor shall verify by accurate field measurements the locations both vertically and horizontally of all bearings and shall assume full responsibility for fabricated beams fitting and bearing as constructed. After beam erection and concurrently with the Department project surveyors or their designated representative, the Contractor shall survey top of beam elevations at a maximum of 10-ft stations and compute screed grades. These shall be submitted to the Engineer for review and approval before the stay in place forms are set. Construction stakes and other reference control marks shall be set at sufficiently frequent intervals to assure that all components of the structure are constructed in accordance with the lines and grades shown on the plans. The Contractor will be responsible for all structure alignment control, grade control and all necessary calculations to establish and set these controls.
- (e) The Contractor, using contract plans, shall investigate proposed construction for possible conflicts with existing and proposed utilities. The Contractor shall then report such conflicts to the Engineer for resolution. All stakes for utility relocations, which will be performed by others, after the Notice to Proceed has been given to the Contractor, shall be paid for under item 763597  
- Utility Construction Engineering.
- (f) The Contractor shall be responsible for the staking of all sidewalk and curb ramp grades in accordance with the plans and the Departments Standard Construction Details. The Contractor shall review the stakeout with the Engineer prior to construction. The Engineer must approve any deviation from plans, Department Standard Construction Details and Specifications in writing. The Contractor shall be responsible for any corrective actions resulting from problems created by adjustments if they fail to obtain such approval.
- (g) If wetland areas are involved and specifically defined on the Plans the following shall apply:
  - i. It is the intent of these provisions to alert the Contractor, that he/she shall not damage or destroy wetland areas, which exist beyond the construction limits. These provisions will

- be strictly enforced and the Contractor shall advise his/her personnel and those of any Subcontractor of the importance of these provisions.
- ii. All clearing operations and delineation of wetlands areas shall be performed in accordance with these Special Provisions. Before any clearing operation commences the Contractor shall demarcate wetlands at the Limits of Construction throughout the entire project as shown on the Plans labeled as Limits of Construction or Wetland Delineation to the satisfaction of the Engineer.
  - iii. The material to be used for flagging the limits of construction shall be orange vinyl material with the wording "Wetland Boundary" printed thereon. In wooded areas, the flagging shall be tied on the trees, at approximate 20-foot intervals through wetland areas. In open field and yard areas that have been identified as wetlands, 6 foot posts shall be driven into the ground at approximate 50-foot intervals and tied with the flagging. The flagging shall extend approximately 12 inches in length beyond the post. Posts shall be oak with cross sectional dimensions of 1 ½ inches to 2 inches by 1 ½ inches to 2 inches or ¼ inch rebar.
  - iv. If the flagging has been destroyed and the Engineer determines that its use is still required, the Contractor shall reflag the area at no cost to the Department. If the Contractor, after notification by the Engineer that replacement flagging is needed, does not replace the destroyed flagging within 48 hours, the Engineer may proceed to have the area reflagged. The cost of the reflagging by the Engineer will be charged to the Contractor and deducted from any monies due under the Contract.
  - v. At the completion of construction, the Contractor shall remove all posts and flagging.
  - vi. The Contractor shall be responsible for any damages to wetlands located beyond the construction limits, which occurs from his/her operations during the life of the Contract. The Contractor shall restore all temporarily disturbed wetland areas to their preconstruction conditions. This includes restoring bank elevations, streambed and wetland surface contours and wetlands vegetation disturbed or destroyed. The expense for this restoration shall be borne solely by the Contractor.
- (h) Whenever the Engineer will be recording data for establishment of pay limits, the Contractor will be invited to obtain the data jointly with the Engineer's Survey Crew(s) in order to agree with the information. If the Contractor's representative is not able to obtain the same data, then the information obtained by the Engineer shall be considered the information to be used in computing the quantities in question.

**Submittals.** All computations necessary to establish the exact position of all work from the control points shall be made and preserved by the Contractor. All computations, survey notes, electronic files, and other records necessary to accomplish the work shall be made available to the Department in a neat and organized manner at any time as directed by the Engineer. The Engineer may check all or any portion of the stakeout survey work or notes made by the Contractor and any necessary correction to the work shall be made as soon as possible. The Contractor shall furnish the Engineer with such assistance as may be required for checking all lines, grades, and measurements established by the Contractor and necessary for the execution of the work. Such checking by the Engineer shall not relieve the Contractor of his/her responsibility for the accuracy or completeness of the work. Copies of all notes must be furnished to the engineer at the completion of the project.

The Contractor shall submit any of the following at the Engineer's request:

- (a) Proposed method of recording information in field books to ensure clarity and adequacy.
- (b) A printout of horizontal control verification, as well as coordinates, differences and error of closure for all reestablished or temporary Control Points.
- (c) A printout of vertical control verification, with benchmark location elevation and differences from plan elevation.
- (d) Sketch of location of newly referenced horizontal control, with text printout of coordinates, method of reference and field notes associated with referencing control - traverse closure report.
- (e) Description of newly established benchmarks with location, elevation and closed loop survey field notes - bench closure report
- (f) All updated electronic and manuscript survey records.
- (g) Stakeout plan for each structure and culvert.

- (h) Computations for buildups over beams, screed grades and overhang form elevations.
- (i) A report showing differences between supplied baseline coordinates and field obtained coordinates, including a list of preliminary input data.
- (j) Any proposed plan alteration to rectify a construction stakeout error, including design calculations, narrative and sealed drawings.
- (k) Baseline for each borrows pit location.
- (l) Detailed sketch of proposed overhead ground mounted signs or signals showing obstructions that may interfere with their installation.
- (m) Copies of cut sheets.

### **Machine Control Grading**

**This Section of the specification shall only be used if machine control is authorized for use on the project.**

#### **Description:**

This specification contains the requirements for grading operations utilizing Global Positioning Systems (GPS).

Use of this procedure and equipment is intended for grading the subgrade surface; it is not intended for the use in constructing final surface grades.

The Contractor may use any manufacturer's GPS machine control equipment and system that results in achieving the grading requirements outlined in section 202 of the standard specifications. The Contractor shall convert the electronic data provided by the Department into the format required by their system. The Department will only provide the information outlined in this document and no additional electronic data will be provided.

The Contractor shall perform at least one 500 foot test section with the selected GPS system to demonstrate that the Contractor has the capabilities, knowledge, equipment, and experience to properly operate the system and meet acceptable tolerances. The engineer will evaluate and make the determination as to whether additional 500 foot test sections are required. If the Contractor fails to demonstrate this ability to the satisfaction of the Department, the Contractor shall construct the project using conventional surveying and staking methods.

#### **Materials:**

All equipment required to perform GPS machine control grading, including equipment needed by DelDOT to verify the work, shall be provided by the Contractor and shall be able to generate end results that are in accordance with the requirements of Division 200 - EARTHWORK of the Standard Specifications.

#### **Construction:**

##### **A. DelDOT Responsibilities:**

1. The Department will set initial vertical and horizontal control points in the field for the project as indicated in the contract documents, (plans set). If the Contractor needs to establish new control points they shall be traversed from existing control points and verified to be accurate by conventional surveying techniques.
2. The Department will provide the project specific localized coordinate system.
3. The Department will provide data in an electronic format to the Contractor as indicated in the General Notes.
  - a. The information provided shall not be considered a representation of actual conditions to be encountered during construction. Furnishing this information does not relieve the Contractor from the responsibility of making an investigation of conditions to be encountered including, but not limited to site visits, and

basing the bid on information obtained from these investigations, and the professional interpretations and judgments of the Contractor. The Contractor shall assume the risk of error if the information is used for any purpose for which the information is not intended.

- b. Any assumption the Contractor makes from this electronic information shall be at their risk. If the Contractor chooses to develop their own digital terrain model the Contractor shall be fully responsible for all cost, liability, accuracy and delays.
- c. The Department will develop and provide electronic data to the Contractor for their use as part of the contract documents in a format as indicated in the General

Notes. The Contractor shall independently ensure that the electronic data will function in their machine control grading system.

- 4. The Files that are provided were originally created with the computer software applications MicroStation (CADD software) and INROADS (civil engineering software). The data files will be provided in the native formats and other software formats described below. The contractor shall perform necessary conversion of the files for their selected grade control equipment. The Department will furnish the Contractor with the following electronic files:

- a. CAD files
  - i. Inroads -Existing digital terrain model (.DTM)
  - ii. Inroads -Proposed digital terrain model (.DTM)
  - iii. Microstation -Proposed surface elements - triangles
- b. Alignment Data Files:
  - i. ASCII Format

- 5. The Engineer shall perform spot checks of the Contractor's machine control grading results, surveying calculations, records, field procedures, and actual staking. If the Engineer determines that the work is not being performed in a manner that will assure accurate results, the Engineer may order the Contractor to redo such work to the requirements of the contract documents, and in addition, may require the Contractor to use conventional surveying and staking, both at no additional cost to the Department.

#### B . Contractor's Responsibilities

- 1. The Contractor shall provide the Engineer with a GPS rover and Automatic Level, for use during the duration of the contract. At the end of the contract, the GPS rover and Automatic Level will be returned to the Contractor. The Contractor shall provide a total of 8 hours of formal training on the Contractor's GPS machine control system to the Engineer and up to three additional Department appointees per rover.
- 2. The Contractor shall review and apply the data provided by the Department to perform GPS machine control grading.
- 3. The Contractor shall bear all costs, including but not limited to the cost of actual reconstruction of work, that may be incurred due to application of GPS machine control grading techniques. Grade elevation errors and associated corrections including quantity adjustments resulting from the contractor's use of GPS machine control shall be at no cost to the Department.
- 4. The Contractor shall convert the electronic data provided by the Department into a format compatible with their system.

5. The Contractor's manipulation of the electronic data provided by the Department shall be performed at their own risk.
6. The Contractor shall check and if necessary, recalibrate their GPS machine control system at the beginning of each workday in accordance with the manufacturer's recommendations, or more frequently as needed to meet the requirements of the project.
7. The Contractor shall meet the accuracy requirements as detailed in the Standard Specifications.
8. The Contractor shall establish secondary control points at appropriate intervals and at locations along the length of the project. These points shall be outside the project limits and/or where work is performed. These points shall be at intervals not to exceed 1000 feet. The horizontal position of these points shall be determined by conventional survey traverse and adjustments from the original baseline control points. The conventional traverse shall meet or exceed the Department's Standards. The elevation of these control points shall be established using differential leveling from the project benchmarks, forming a closed loop. A copy of all new control point information including closure report shall be provided and approved by the Engineer prior to construction activities. The Contractor shall be responsible for all errors resulting from their efforts and shall correct deficiencies to the satisfaction of the Engineer and at no additional cost to the Department.
9. The Contractor shall provide stakes at all alignment control points, at every 500 foot stationing, and where required for coordination activities involving environmental agencies and utility companies at the Contractor's expense. Work that is done solely for utility companies and that is beyond the work performed under item 763501 - Construction shall follow and be paid for under item 763597 -Utility Construction Engineering.
10. The Contractor shall at a minimum set hubs at the top of finished grade at all hinge points on the cross section at 500 foot intervals on the main line and at least 4 cross sections on side roads and ramps as directed by the engineer or as shown on the plans. Placement of a minimum of 4 control points outside the limits of disturbance for the excavation of borrow pits, Stormwater Management Ponds, wetland mitigation sites etc. These control points shall be established using conventional survey methods for use by the Engineer to check the accuracy of the construction.
11. The Contractor shall preserve all reference points and monuments that are identified and established by the Engineer for the project. If the Contractor fails to preserve these items the Contractor shall reestablish them at no additional cost to the Department.
12. The Contractor shall provide control points and conventional grades stakes at critical points such as, but not limited to, PC's, PT's, superelevation points, and other critical points required for the construction of drainage and roadway structures.
13. No less than 2 weeks before the scheduled preconstruction meeting, the Contractor shall submit to the Engineer for review a written machine control grading work plan which shall include the equipment type, control software manufacturer and version, and proposed location of the local GPS base station used for broadcasting differential correction data to rover units.
14. The Contractor shall follow the guidelines set forth in the "Geometric Geodetic Accuracy Standards and Specifications for Using GPS Relative Positioning Techniques" and follow a minimum of Second Order Class 1, (2-I) classification standards.

Automated equipment operations have a high reliance on accurate control networks from which to take measurements, establish positions, and verify locations and features. Therefore, a strong contract control network in the field which is the same or is strongly integrated with the project control used during the

design of the contract is essential to the successful use of this technology with the proposed Digital Terrain Model (DTM). Consistent and well designed site calibration for all machine control operations (as described below under Contract Control Plan) are required to ensure the quality of the contract deliverables. The Contract Control Plan is intended to document which horizontal and vertical control will be held for these operations. Continued incorporation of the Base Station(s) as identified in the Contract Control Plan is essential to maintaining the integrity of positional locations and elevations of features. The Contract Control Plan shall be submitted to the Department for review and approval by the Departments Survey Section 3 weeks prior to the start of any machine control work. The Contractor shall operate and maintain all elements of the Machine Grade Control continuously once the operations begin until otherwise approved by the Engineer.

**Contract Control Plan:**

The Contractor shall develop and submit a Contract Control Plan for all contracts which use Machine Control Grading. Contract control includes all primary and secondary horizontal and vertical control which will be used for the construction contract. Upon the Contractor's completion of the initial survey reconnaissance and control verification, but prior to beginning primary field operations, the Contractor shall submit a Contract Control Plan document (signed and sealed by the Delaware licensed Land Surveyor or Delaware Professional Engineer who oversees its preparation) for acceptance by the Engineer, which shall include the following:

1. A control network diagram of all existing horizontal and vertical control recovered in the field as contract control.
2. Include a summary of the calculated closures of the existing control network, and which control has been determined to have been disturbed or out of tolerance from its original positioning.
3. An explanation of which horizontal and vertical control points will be held for construction purposes. If necessary include all adjustments which may have been made to achieve required closures.
4. An explanation of what horizontal and vertical control (including base stations) was set to accomplish the required stakeout or automated machine operation. Include how the position of these new control points was determined.
5. Describe the proposed method and technique (technology and quality control) for utilizing the control to establish the existing and/or proposed feature location and to verify the completed feature location and/or measured quantity.
6. A listing of the horizontal and vertical datums to be used and the combined factor to be used to account for ellipsoidal reduction factor and grid scale factor.
7. If the Contractor chooses to use machine control as a method of measuring and controlling excavation, fill, material placement or grading operations as a method of measuring and controlling excavation, fill, material placement or grading operations, the Contractor Control Plan shall include the method by which the automated machine guidance system will initially be site calibrated to both the horizontal and vertical contract control, and shall describe the method and frequency of the calibration to ensure consistent positional results.
8. Issues with equipment including inconsistent satellite reception of signals to operate the GPS machine control system will not result in adjustment to the "Basis of Payment" for any construction items or be justification for granting contract time extension.

**Method of Measurement:**

The quantity of Construction Engineering will not be measured.

**Basis of Payment:**

Payment will be made at the Lump Sum price bid for the item "Construction Engineering". The price bid shall include the cost of furnishing all labor, equipment, instruments, stakes and other material necessary to satisfactorily complete the work as herein described under this item for all roads and structures that are a part of the contract. Adjustment in payment will be made for the deletion or addition of work not shown in the contract documents.

Monthly payment will be made under this item in proportion to the amount of work done as determined by the Engineer.

2/28/2018

**763504 - SITE WORK**

**Description:**

This work consists of performing site work and furnishing the materials necessary to complete the site work including the Masonry Monument Sign, Wash Pad, Fuel Dispensing Station, Earthwork, Stormwater Management, Stormwater Management Outfall Modifications, and Electrical Site Work as indicated in the Contract documents and further described in the technical specifications in Appendix A – Technical Specifications for Crew Operations Building, Maintenance Shop Building, and Site Work.

**Materials and Construction:**

All materials and construction shall conform to the requirements of the Contract drawings, the Delaware Department of Transportation Standard Specifications, and the technical specifications in Appendix A – Technical Specifications for Crew Operations Building, Maintenance Shop Building, and Site Work.

**Method of Measurement:**

Payment for this item will be made on a lump sum basis wherein no measurement will be made.

**Basis of Payment:**

The payment for the work under this item shall be made at the contract unit price per Lump Sum bid, which price and payment shall constitute full compensation for performing the work specified and for furnishing all materials, labor, tools, equipment and incidentals necessary to complete the item.

8/16/2017

**763508 - PROJECT CONTROL SYSTEM DEVELOPMENT PLAN**  
**763509 - CPM SCHEDULE UPDATES AND/OR REVISED UPDATES**

**Description:**

The Contractor shall plan, schedule and construct the Project by using a Critical Path Method Project Schedule (CPM) meeting the requirements of these specifications. Use the CPM for coordinating and monitoring the Work specified in the Contract Documents including all activities of Subcontractors, vendors, suppliers, utilities, railroads, the Department, and all other parties associated with the construction of the Contract. Include all Work in the CPM; including but not limited to submittals, major procurement, delivery, and construction activities. Include all activities, including bid items, quantified in the Contract Documents. Base the CPM upon the entirety of the Contract Documents. Utilize CPM software that generates files compatible with Primavera P6 Project Management Release: 7.0.0.

**Scheduling Representative:**

Designate a scheduling representative prior to submission of the Original Critical Path Method Project Schedule (OCPM). The scheduling representative is the person primarily responsible for development and maintenance of the CPM schedule; the Contractor's representative in all matters regarding the schedule; and the Contractor's designated attendee for all schedule related meetings. The scheduling representative shall also be knowledgeable of the status of all parts of the Work throughout the duration of the Project. Replacement of the scheduling representative will require written approval from the Engineer.

Submit the qualifications of the scheduling representative to the Engineer for approval. This approval is required before the OCPM will be accepted. The scheduling representative shall have at least three years of verifiable experience for preparing and maintaining CPM project schedules on Contracts of similar size and complexity.

**Critical Path, Project Completion Date, and Float:**

The critical path is defined as the series of activities in a CPM that has the longest path in time. The submitted activity sequence and durations must generate a CPM with only one critical path. Divide Project wide activities such as Maintenance of Traffic, Construction Engineering, or Temporary Erosion Control that, by their nature, generate long durations and complement other activities into "establish" and "conclude" activities to prevent this type of Work from occupying a significant portion of the critical path.

The project start date, or initial data date, of the original CPM shall be the first chargeable day of Work. Nonproductive Work and administrative activities may begin and/or end prior to the project start date. The Original CPM must use all of the Contract Time and contain a critical path containing exactly zero float. Early completion schedules are not permitted. The schedule ending date of the Original CPM that uses all of the Project Time is the contract completion date.

Total Float is the difference between the schedule's finish date and the contract completion date. Free float is the difference in time between an activity's early finish and late finish. Free float is a shared commodity for the use of the Department and the Contractor and is not for the exclusive use or benefit of either party. Both parties have the full use of free float until depleted.

**Submittal of the OCPM; the Start of Work and the Schedule of Record:**

Complete and submit the proposed original CPM schedule (OCPM) database and the written narrative (WN) within 30 calendar days after Contract is Awarded. The WN is a description of any elements of the Schedule that deviate from the proposed construction sequence shown in the Contract Documents. Submit the OCPM in CPM format fully compatible with Primavera P6 Project Management Release: 7.0.0 by email or CD ROM as a single compressed database in CPM format.

The Engineer will complete the review of the OCPM within 30 calendar days after submittal. If required, a Joint Review Conference will be convened at which time the Engineer and Contractor may

make corrections and adjustments to the proposed OCPM. If a revision is necessary due to the Engineer's review or the Joint Review Conference, submit the proposed revision within seven calendar days after receiving the Engineer's review comments or within seven calendar days after the date of the Joint Review Conference, whichever is the latest. Make revisions in accordance with the requirements for the OCPM. The Engineer will respond to the revised OCPM within seven calendar days after receipt. Clearly identify each submittal and resubmittal for clarity by labeling "2<sup>nd</sup> Draft", "3<sup>rd</sup> Draft", etc.

Do not start any Work until the OCPM is accepted. If the Engineer is ready to issue a Notice to Proceed but the OCPM is not yet accepted, the Engineer may issue the NTP and start Contract Time, but forbid Work to begin until the OCPM is accepted. The Engineer may partially accept a OCPM and allow Work to begin if the required corrections to the OCPM are minor, but the Engineer will not accept submittals that do not show the complete schedule. The Engineer will not pay any estimates until the OCPM is partially accepted. Once the OCPM is partially accepted, the Engineer will pay the first estimate. If the Contractor fails to make a good faith effort to address the Engineer's comments before the second estimate is due for payment, the Engineer will not pay the second estimate until a good faith effort is made by the Contractor to comply. The Engineer may not withhold an estimate payment if, within the estimate period in question, the Engineer has failed to provide timely review comments in response to the Contractor's submittal. The Engineer may, however, withhold the payment of subsequent estimates if the Contractor fails to make a good faith effort to address the Engineer's comments. Upon issuance of the Notice to Proceed, the start date utilized in the OCPM will be adjusted to comply with the first chargeable day of Work. Any delay in starting Work caused by the acceptance of the OCPM by the Engineer will not be considered as a basis for any adjustment in the Contract amount or time. For Contracts that have fast-tracked starts, the Engineer and the Contractor may agree to alter the response times and approval dates listed above. Upon notification that the OCPM has been accepted, the corrected copy will become the CPM of record. The CPM of record shall be the Contractor's work plan for completing the entire Contract as specified in the Contract Documents.

#### **Requirements for the OCPM:**

The format of the OCPM database shall be the precedence diagram method with days as the planning unit and shall be based on Calendar Days. Use the Department's partially predetermined coding structure (CS) that is furnished by the Engineer.

*Activity Sequencing.* Activity sequence must be logical and representative of the Contractor's order of the Work. Successors and predecessors determine the schedule logic or activity sequence. A given activity cannot start until all of the given activity's predecessors have been completed. Use only finish to start dependency relationships (links); do not use lag times without approval from the Engineer. The Engineer may request that the Contractor resequence the activities to reflect realistic job logic. When scheduling using multiple resources, each resource unit shall have a corresponding activity. Durations of activities include all the time necessary to complete the activity including, but not limited to, Contractor's non-work periods (other than those shown on the calendars), reasonably foreseeable inclement weather, weekends and holidays. Base schedule calculations on retained logic, contiguous durations, and total float as finish float.

*Activity Resources.* Sequence activities to reflect resource apportionment. Logically connect and code each activity to reflect the crew (resource) performing the operation. Submit a summary list of crews, their crew codes, and their operation(s) with each schedule submission, unless unchanged. Identify responsibility for each activity. Identify Subcontractors, DBE's, utilities and Work performed by others that affects the Schedule.

*Breakdown and Durations of Activities.* An individual activity is required for each construction element or each activity not under the control of the Contractor that affects the sequence or progress of the Work. The Engineer reserves the right to require additional breakdown of the Work activities at any time. Each activity must be identified by a name, symbol and coding, and shall have a duration, sequence, responsibility and resource(s). Choose activity names that are descriptive and identify single construction elements. Activity symbols, or ID's, shall be unique and systematic.

Activity types must be either "task", "start milestone", or "finish milestone". Do not use "hammock" type activities. Date constraints, float and duration constraints, and/or flags for activities are not permitted.

Assign a reasonable duration to each activity representative of its scope. Durations may not exceed 14 calendar days unless approved by the Engineer. Determine the duration of each activity by using productivity rates based on Calendar Days.

Include the preparation and approval of Working Drawings as activities. Include phasing (staging) milestones as activities. Correlate phasing milestones with the sequence of construction provided in the Contract Documents. Use a separate start and finish milestone activity to delineate each phase (stage).

*Utility Work.* Include all Work performed by utilities on the Project as activities in the OCPM. Include each utility item of Work shown in the Contract's Utility Statement as an activity. Durations for utility activities shall be the same as the durations shown in the Utility statement for each activity unless otherwise approved by the Engineer.

*Calendars.* Assign a calendar to each activity in the schedule. Use a minimum of 6 calendars, when applicable: (1) Full Schedule; (2) Permit Requirements; (3) Winter Condition; (4) Concrete Work; (5) Asphalt Paving Work; and (6) Nighttime Asphalt Paving Work. Use additional calendars if needed. Calendar non-work periods shall reflect the average Delaware weather history for the jobsite and the restrictions identified in the Contract Documents. The Contractor may choose perform Work during an activity's calendar non-work period at no additional cost to the Department if weather conditions are favorable for such Work and the Work does not violate a set forth in the Contract Documents. The maximum allowable non-work period for each calendar is set forth below. The Contractor may choose to shorten non-work periods at his/her discretion.

CALENDAR	MAXIMUM NON-WORK PERIOD
Full Schedule	None
Winter Condition	December 1 through March 15
Concrete Work	December 1 through March 15
Asphalt Paving	November 15 through March 15
Nighttime Asphalt Paving	October 15 through April 30

*Written Narrative (WN).* Provide a written narrative (WN) as part of the OCPM explaining the following:

- (a) Relationships between activities not obviously identified
- (b) Equipment usage and limitations.
- (c) Manpower usage and limitations.
- (d) Use of additional shifts and overtime.
- (e) Activity codes, abbreviations, and activity identification system.
- (f) All calendars utilized in the CPM and the basis of determining each non-work period
- (g) All abbreviations.
- (h) Use of calendars.
- (i) Any other conditions that affect the schedule and are not readily discernible in the database.

**CPM Updates:**

Provide monthly updates to the CPM of record. Meet with the Engineer once a month prior to submitting the update to review the status of the schedule's activities. Prepare an updated list of activities showing all of the actual start and actual finish for each of the schedule's activities so that both parties can agree on the dates. Use the dates that were agreed upon in the meeting to status the CPM of record and submit the updated schedule to the Engineer for approval. Assign a unique file name to each update (Number/version). The data date of the update shall be the next day after the end of the update period. As part of the monthly update, submit a written description that identifies any delays or disruptions to the schedule experienced during the period of an update, any change in manpower or equipment, and any potential delays to the completion date of the schedule.

Do not include any revisions to the CPM without prior approval. Failure to submit complete updates in a timely manner may result in the withholding of estimates by the Engineer. The Engineer agrees to refrain from withholding estimates unless the Contractor is habitually late in providing updates, is more than four weeks late in submitting an update or has failed to submit an update that is part of a resolution to a serious problem that must be addressed immediately.

**Revisions to the Schedule of Record:**

Revisions are defined as any changes to the database other than status updates, log entries and moving the data date. Discuss any proposed revisions to the CPM verbally with the Engineer. If the revision is minor in nature, the Engineer may allow the revision to be included on the next Update of the CPM. If the Engineer determines that the revision is not minor in nature, submit the proposed revision for review and approval prior to deviating from the approved CPM. When a revision to the CPM is required due to changes in the Contract initiated by the Engineer, immediately contact the Engineer to discuss the changes. The Engineer may allow a deviation from the approved CPM for specific mitigating activities.

The Engineer may direct the Contractor to revise the schedule of record at the Contractor's expense if: the critical path has less than minus ten (-10) Calendar Days of total float due to the Contractor's failure to perform the Work in accordance with the schedule; the Contractor requests to re-sequence the Work; and/or the Contractor has performed a significant amount of Work out of sequence. The Engineer may direct the Contractor to revise the schedule for any other reason; and such a revision will be paid at the unit cost for a CPM Revision.

The Engineer will review and respond to the proposed revision within 7 Calendar Days after receipt. Resubmit, if required, within seven calendar days after receipt of the Engineer's review comments. The Engineer reserves the right to reject any proposed revision that adversely impacts the Department, utilities, or other concerned parties.

**Extensions of Contract Time and/or Incentive/Disincentive Dates.**

Make requests for extension of Contract time in writing and subject to the notice and timeliness of submission provisions as provided for elsewhere in the Contract. Requests for an extension of Contract time or change in an incentive/disincentive date will be evaluated by the Engineer's analysis of the CPM of record and any proposed revision submitted. Include in the request a written narrative of the events that impacted the schedule and a detailed explanation of why the Contractor cannot meet the requirements of the schedule of record. Only delays to activities that affect the Contract completion date or will be considered for an extension of Contract time. Only delays to activities that affect the completion duration of an incentive/disincentive period will be considered for an extension of an incentive/disincentive completion date. The extension of the specified Contract completion date or incentive/disincentive date will be based upon the number of Calendar Days the Contract completion date or incentive/disincentive date is impacted as determined by the Engineer's analysis. The Engineer and Contractor may agree to defer the analysis of a potential impact to the schedule until the completion of the activities that are affected. Such a deferment does not relieve the Contractor of his/her duty to identify potential impacts to the schedule in the applicable schedule updates.

All requests for extensions of Contract Time must be supported by the most recent CPM Update. If, within a reasonable period of time, the Contractor fails to make a good faith effort to produce an acceptable CPM update and uses an unacceptable CPM update to support a request for a time extension, the Contractor loses the right to receive that time extension; and/or the right to receive compensation for that delay caused in whole or in part by the Engineer.

**Final As Built Schedule.**

Submit a final CPM Schedule database within 14 Calendar Days of Substantial Completion. Failure to submit a final CPM Schedule may result in the withholding of estimates by the Engineer.

**Method of Measurement:**

The Project Control System will be measured in two items. The item, "Project Control System Development Plan" will be lump sum. The item "CPM Schedule Updates and/or Revised Updates" will be measured one each per update that is submitted and accepted.

**Basis of Payment:**

The item, "763508 – Project Control System Development Plan" will be paid at the Contract's lump sum bid price on the next monthly estimate after completion of the requirements of the Project Control System Development Plan, which includes the approval of the Original CPM Schedule. Price and payment will constitute full compensation for preparing the CPM database, acquiring the necessary

software, attending all scheduling meetings with the Department, submitting and resubmitting all documents and for all labor, tools, equipment and incidentals necessary to complete the Work.

The item, “763509 – CPM Schedule Updates and/or Revised Updates” will be paid at the Contract unit price per each approved CPM schedule update as described above. Price and payment will constitute full compensation for preparing, submitting and resubmitting all CPM updates, for attendance at all scheduling meetings with the Department, for preparing and reviewing a list of actual start and actual finish dates with the Engineer, and for all labor, tools, Equipment and incidentals necessary to complete the Work.

2/11/2015

**763511 – MAINTENANCE BUILDINGS**

**Description:**

This bid item shall consist of furnishing and installing materials and constructing the hopper racks as indicated on the Contract Drawings. The work shall include the concrete footers and piers (including anchor bolts), steel columns, steel beams, wood trusses, roofing, gutters, downspouts, chains and/or winches and all else necessary to provide the hopper racks complete per the contract drawings. This contract may be awarded to multiple contractors. Work included as part of the buildings specification breakout pay items shall be as described below.

This open-end contract includes 1 known location (Middletown) with detailed drawings. This contract also calls for hopper racks at sites to be determined in 3 counties. The sites to be determined may include covered roofing. Cost proposal shall assume hopper rack bays and optional roofing are constructed in units of 5 or more bays at a time. All bid breakout items shall include the concrete footers and piers (including anchor bolts), steel columns, steel beams, chains/winches, and all miscellaneous items necessary to install the hopper racks complete without a roof for the amount of bays required for each site.

Location number 1 (Middletown) shall include all labor, materials, and equipment necessary to furnish and provide the 12 bay hopper racks for 6 wheeled vehicles and 6 bay hopper racks for 10 wheeled vehicles. Middletown hopper racks will utilize chains. These hopper racks shall be furnished with the roof system (trusses, sheathing, asphalt shingles, gutters, and downspouts). Include all earthwork, select fill, seeding and mulching, and grading necessary to bring the subgrade to the proper grade under stone/pavement areas, or to final grade when not under impervious surface. The scope shall include all work identified in Middletown Location 1 plans.

New Castle County shall include all labor, materials, and equipment necessary to furnish and provide an estimated 30 bay hopper racks for 6 wheeled vehicles and 20 bay hopper racks for 10 wheeled vehicles. Optional roof system (trusses, sheathing, asphalt shingles, gutters, and downspouts) pricing shall be provided. Earthwork, saw-cutting, any pavement repair necessary to install the racks to be evaluated at each location.

Kent County shall include all labor, materials, and equipment necessary to furnish and provide an estimated 15 bay hopper racks for 6 wheeled vehicles and 10 bay hopper racks for 10 wheeled vehicles. Optional roof system (trusses, sheathing, asphalt shingles, gutters, and downspouts) pricing shall be provided. Earthwork, saw-cutting, any pavement repair necessary to install the racks to be evaluated at each location.

Sussex County shall include all labor, materials, and equipment necessary to furnish and provide an estimated 10 bay hopper racks for 6 wheeled vehicles and 15 bay hopper racks for 10 wheeled vehicles. Optional roof system (trusses, sheathing, asphalt shingles, gutters, and downspouts) pricing shall be provided. Earthwork, saw-cutting, any pavement repair necessary to install the racks to be evaluated at each location.

In addition, a unit price to add-on an extra hopper rack bay is requested for the possible event where 1 or more bays are added to an existing rack. This will require 1 less side and 2 less support beams. A unit price will be requested for each county.

**Materials and Construction Methods:**

All materials and construction shall conform to the requirements of the Contract Drawings, DelDOT Standard Specifications and the technical specifications included as part of Appendix A.

**Method of Measurement:**

Payment for this item will be made on a lump sum basis wherein no measurement will be made.

**Basis of Payment:**

Payment will be made at the Lump Sum price bid for this item. The price bid shall include the cost for performing the work specified and furnishing all labor, materials, tools, equipment and incidentals necessary to provide a complete, working and usable facility acceptable to the Engineer.

**Note:**

The breakout sheet attached to the proposal shows the proposed Bays for this Contract. The Contractor shall fill in a price per each bid item number. The lump sum price bid for item 763511 – Maintenance Buildings shall be the sum of the total cost for all bid item number listed.

The Department reserves the right to delete from the Contract. The lump sum to be paid will be adjusted in accordance with the Contractor's unit prices as required above. There will be no extra compensation to the Contractor if such additions and/or deletion are made

10/10/17

**763598 - FIELD OFFICE, SPECIAL I**

**Description:**

The field office work shall consist of furnishing, erecting, equipping, maintaining, and removing a singlewide modular office and adjacent parking area. The Contractor shall submit a specific location layout drawing and construction details for the proposed field office and its parking area for approval by the Engineer. The field office and parking area shall be for the exclusive use of Department Officials, Engineers, Designers, North Region Construction (NRC) Personnel, Consultants, and Inspectors.

The field office structure shall be free of asbestos and/or other hazardous materials. The field office and its parking area shall be constructed and installed in accordance with all applicable city, county, state, and federal codes. The Contractor shall be responsible for obtaining all required licenses and permits for installation and placement of the field office and its parking area. The costs of obtaining such licenses and permits to be incidental to the "Field Office, Special" Item. The field office shall be available for use by the Department continuously throughout the duration of the project.

**Construction and Equipment:**

The field office shall be new and have a minimum floor space of 600 square feet with minimum exterior dimensions of 50'-0" length by 12'-0" width. The floor to ceiling height shall be nominal 8'-0". The exterior walls, ceiling, and floor shall be insulated. The field office shall be of weather-proof construction, tightly floored and roofed, constructed with an air space above the ceiling for ventilation, supported above the ground, safely secured to its support if the support is an inground anchored foundation or otherwise by tie-downs to the ground, and fully skirted with rigid watertight covering overlapping the bottom of the exterior siding to the existing ground.

The Contractor shall provide entries to the field office by constructing a stair and deck platform with canopy at each exterior door. These entries shall be fabricated using treated dimension lumber, be constructed with hand and safety railing, be designed to last the life of the Contract, and conform to the requirements of the Architectural Accessibility Board and other federal, state and local boards, bodies and/or courts having jurisdiction in the Contract limits.

The Contractor shall construct and maintain an all weather parking area adjacent to the office of at least 2500 square feet and having a minimum of 10 functional parking spaces striped for full size cars. All weather pathways from the parking area to the entrances of the field office shall also be constructed and maintained. This parking area and entrance pathways shall have a minimum of 2" type "C" hot mix on top of minimum 6" graded aggregate subbase. Snow and/or ice shall be removed from the parking area and from the entrance pathways to the field office within 12 hours after each occurrence. Costs for furnishing, placing, and maintaining the aggregate base and hot mix, and for snow and/or ice removal, to be incidental to the Field Office, Special" Item.

The ground area 30'-0" from around the perimeter of the field office to the field office shall be landscaped and maintained. If the earthen grounds do not have a stand of weed free grass, the surface of this area shall be loosened to a depth of 4" and a satisfactory seedbed shall be prepared free of debris and extraneous matter. The area shall be seeded to a healthy stand of grass or sodded, after which the area shall be watered, mowed, and trimmed a minimum of three times a month during the growing seasons. Cost for this landscaping and maintenance to be incidental to the "Field Office, Type I Special" Item.

The field office shall have full carpeting, kitchenette facilities, and interior and exterior paneling, lighting, and plumbing fixtures. The field office shall have a minimum of two (2) exterior doors, each door having a passage and a deadbolt lock. These door locks shall be keyed and at least 2 complete sets of keys shall be supplied to the Engineer's representatives. The exterior doors shall be insulated or have storm doors. The field office shall have a minimum of six (6) windows, each window having a minimum glass area of 1150 square inches and a horizontal mini-blind covering the full glass area. The windows shall be insulated or have storm windows. All windows shall be equipped with a locking device. All doors and windows shall have screens installed and repaired when damaged.

At least two (2) outside water service connections shall be provided at the field office. Each water connection shall have a 3/4" frost proof hose bib with vacuum breaker and shall include 100 linear feet of 5/8" minimum diameter reinforced, industrial or commercial grade, soft rubber hose per connection.

The field office shall be provided with sufficient natural and artificial light and shall be adequately heated and cooled to provide comfortable working conditions.

The field office shall have satisfactory lighting, electrical outlets, heating equipment, exhaust fan, and air-conditioning connected to an operational power source. Plan and drawing areas shall have individual fluorescent lights situated over their worktables. Replacement fluorescent lights shall be furnished as required. Electrical current, water, and any fuel for heating equipment shall be furnished and the cost of such shall be borne by the Contractor. Maintenance of the heating, exhaust fan, and air-conditioning equipment shall be provided for by validated service contracts for the length of the Contract. These service contracts shall allow a Department authorized project person to deal directly with the service organization to request repair.

The Contractor shall furnish and maintain two fire extinguishers and provide one lighted "Exit" sign for each exterior passage door. Fire extinguisher(s) may be chemical or dry power and shall be UL Classification 10-B:C(min.) and shall be suitable for Types A:B:C fires. A commercial or industrial type first aid and safety kit suitable for project conditions and hazards (including snakebite) shall be provided and maintained to full capacity on a monthly basis.

The Contractor shall provide an alarm system for field office security with electronic, direct connection to a security service provider. The security system shall have interior motion, window, and entrance detectors and built in manual fire alarm. All windows of the field office shall be covered with steel bar grids as a deterrent to forced entry. The Contractor shall provide validated monitoring and service contracts for the length of the Contract. These contracts shall allow a Department authorized project person to deal directly with the security service provider to request service and/or repair.

The Contractor shall furnish and maintain an adequate supply of cold potable water, a minimum 23 cubic foot new refrigerator, and a minimum 900-watt new microwave oven. Maintenance of the potable water supply equipment, refrigerator, and microwave shall be provided for by validated service contracts for the length of the Contract. These service contracts shall allow a Department authorized project person to deal directly with the service organization to request repair.

Suitable indoor toilet facilities, conforming to the requirements of the State and Local Boards of Health or of other bodies or courts having jurisdiction in the area, shall be provided. When separate facilities for men and women are not available or required, a sign with the wording "Rest Room" (letter heights 1" minimum) shall be placed over the doorway and an adequate positive locking system shall be provided on the inside of the doorway to insure privacy. The facility(s) shall be maintained by the Contractor to be clean and in good working condition and shall be stocked by the Contractor with adequate lavatory and sanitary supplies at all times during the period of the Contract.

The Contractor shall be responsible for performing or for making arrangements for all necessary telephone connections and/or for their maintenance; for providing a new telephone equipment system, for payment of all connections and the new telephone system equipment and its installation; and for final disconnection of the telephones.

The field office telephone system shall have a total of 5 lines consisting of 2 direct single lines with call forward busy feature, 2 dedicated computer use line with broadband connection for either DSL or cable, and 1 dedicated facsimile line and have 5 key sets consisting of 1 master key set having privacy feature, and 4 four-button key sets having privacy feature (1 set which may be for wall mounting), all for the official and exclusive use of the Engineer and other representatives of the Department. Arrangement shall be made to allow a Department authorized project person to deal directly with the telephone company to report outages and/or request repair. Monthly billings for the field office telephone system shall be received and paid by the Contractor. A copy of each bill shall be forwarded to the Project Resident for reimbursement on the subsequent contract pay estimate. The reimbursement will be for the amount of the bill only and shall not include any additional mark-up or profit.

For all other utilities, the Contractor shall be responsible for performing or for making arrangements for all necessary utility connections and/or for their maintenance; for payment of all utility connections, installations, service fees and bills; and for final disconnection of utilities.

The field office interior shall be furnished by the Contractor. The Contractor shall provide new and maintain the following office furnishings, all which are to be approved by the Engineer prior to installation in the field office. Placement of these furnishings shall be as directed by the Engineer. 6 full size office desks each with filing drawer and fully adjustable ergonomic design swivel chair with

armrests and five leg base having wheel casters, 1 computer station with acoustical panels having minimum 60 NRC rating for privacy screen and fully adjustable ergonomic design swivel chair with armrests and five leg base having wheel casters, 1 large conference table for a minimum of 12 people with surrounding chairs with armrests, 2 folding tables minimum 6'-0" by 3'-0" each with ergonomic design straight back chair with armrests, 1 work table, 1 supply cabinet, 2 rough plan racks, 2 legal size filing cabinets with 4 drawers, 2 legal size fire-resistant filing cabinets with lock and key with 4 drawers and meeting fire underwriters' approval for not less than one hour test, 2 book shelves minimum 3'- 6" by 4'- 6", 3 vertical surface legal size three compartment pockets, 2 dry erase boards minimum 4' by 3' each with markers and erasers, and 2 cork bulletin boards minimum height 3' by 2'. These office furnishings will remain the property of the Contractor at the conclusion of the project.

The Contractor shall also furnish new and maintain the following office equipment, all which are to be approved by the Engineer prior to installation in the field office. The required equipment will enable the Department to synchronize project record keeping and office functions. The equipment shall be delivered in working and useable condition:

4 heavy-duty calculators having extra large 12-digit fluorescent display, full size keyboard with contoured keys, two-color ribbon printer, and AC powered;

1 compact plain paper copying machine and cabinet with stationary platen, bypass feeding, and dual loading cassette system with cassettes for letter, legal, and ledger size paper. Copy machine to have zoom and preset reduction and enlargement features, automatic two (2) sided copying, automatic document feeder with minimum 30 sheet capacity, and 20 bin collator with automatic stapling capacity;

1 desktop model, compact facsimile machine with automatic paper cutter, 10-sheet feeder, halftones with 16 levels of gray, 50-number auto dialing, answering machine hook-up, large LCD readout, date and time stamp, and advanced telephone features;

1 DVD camcorder with on-screen programming, full-range auto focus, high-speed shutter, high-resolution, bookmark search, time-lapse recording, rechargeable batteries and charger, tripod, and protective carrying case;

1 integrated color monitor and DVD/VHS cassette recorder having minimum 20" screen, automatic on/play/rewind/stop, remote, full range speaker, and digital auto tracking;

1 micro cassette recorder, having fast playback, voice-activated system, three-digit tape counter, silent auto-stop and pause, two tape speeds, one-touch and follow-up, built-in condenser microphone, cue and review, and rechargeable with combination battery charger/AC adapter;

1 telephone answering machine having all-digital recording, 14 minute message capacity, selectable message time, voice prompt assistance, day/time stamp, call screening, two-digit LED message indicator, toll saver, power failure memory back-up, and message interrupt from any station; and

2 digital cameras with minimum 1/2.7" 4.0 mega pixel, 3X optical / 6X precision digital zoom, 12-bit DXP A/D conversion, 2.5" 123K pixel LCD display, 5-mode program AE and each with dual media slots, SXGA/XGA/VGA image resolution, E-mail mode. Also intelligent flash with red-eye protection, MPEG movie mode, clip motion, light metering, TEXT mode (GIF), playback zoom and resize, white balance, lithium battery system and in-camera picture effects, memory stick/card (minimum 256MB) capability, and storage case.

Consumables as required to manage the business of the project shall be provided for all office equipment for the length of the Contract. These consumables shall be furnished on request and shall include but not be limited to paper, tapes, ribbons, rolls, toner, cleaning kits, microcassette tapes and batteries, answering machine cassettes, camera batteries and memory sticks and/or discs, DVD and CD R/RW media, etc.

Maintenance of all office equipment shall be provided for by a validated service contract for the length of the Contract. This service contract shall allow a Department authorized project person to deal directly with the service organization to request repair.

Included in the unit price bid per month for the Field Office on this project will be two (2) IBM compatible Microcomputer Systems both which will be furnished and maintained by the Contractor for use by the Engineer. The specified computer systems will synchronize the construction management functions of the Department to monitor, report, and perform the accounting of the project work. The computer systems and all their related equipment specified below shall be furnished new and remain the property of the Contractor at the conclusion of the Contract. A detailed listing of the proposed computer systems and all their related equipment to be provided by the Contractor shall be submitted for approval by the Engineer prior to furnishing the Microcomputer Systems. The Microcomputer Systems shall be Laptop Computer Systems each with docking station. Each of the two (2) Microcomputer Systems shall consist of:

Central Processing Unit (CPU) – Lap Top

Pentium M processor, 740 (1.7 GHz) or better with integrated USB 2.0 and IEEE 1394 ports (firewire) and wireless networking included,

Minimum 1.0 GB RAM with expansion capability to at least 3.0 GB and clock/calendar card equivalent, and

Microsoft "Windows® XP Professional" operating system;

Memory (Storage)

CD/DVD +/- RW with double layer write capability, and 100GB hard drive minimum, integrated Ethernet 10/100, and internal modem. Included software shall support double layer media writing and automatic backup of data;

Monitor (Cathode Ray Tube)

Monitor for docking station and docking station - Super Video Graphics Adapter (SVGA) minimum. 19" minimum diagonal visual area flat panel with .26 dot pitch capable of multiple frequency 256 color graphics and at least 1024 pixel resolution. Swivel base with low radiation and eyestrain protection, brightness and contrast control and

Laptop - shall have 15.4" display minimum;

Color Graphics Card

Card must be SVGA AGP interface with 64 MB onboard video memory having maximum resolution of at least 1280x720 with at least 16 bit color and video control hardware and software;

Keyboard

Keyboard shall be ergonomic, enhanced layout minimum with keyboard interface cable;

Printers

LaserJet HP 2550N network capable printer or latest model with 64 MB minimum total memory having up to 600 dpi resolution and using HPL6 printer language with all necessary software and cables for proper operation; and a HP Desk Jet color printer or latest model with photo quality print capability and with all necessary software, equipment, and cables for general operation as well as connection and sharing on a local network;

Scanner

A HP6100 color scanner with HP5770 ScanJet ADF (or equivalent brand) with all necessary software, equipment, and cables for general operation as well as connection and sharing on a local network;

Software

The latest version programs for application management (operating system), word

processing, spreadsheet, and anti-virus shall be provided with all user manuals. Upgrades, maintenance, and full technical support by the manufacturer shall be provided for the length of the Contract. The required software will enable the Department to synchronize accounting and record keeping functions between the project, District, and Department offices. A list of programs to be provided shall be submitted to the Engineer for approval. Software, other than for application management and anti-virus, is to be delivered unopened to the Department's administrative office. All software is to be compatible with and for use to run on "Windows® XP Professional". The required applications software follows and is to be latest version unless noted:

office suite - "Microsoft® Office XP Professional",  
antivirus - "McAfee® Total Protection for Small Business",  
software supporting creation of DVD +/- R/RW disks (supporting double layer media writing) and DVDR and DVDRW disks using DVDRW drive, for example: Ahead Nero, Roxio DVD/CD Creator, or some equivalent product.  
Note: software commonly included as part of the standard CDRW upgrade/standalone package is acceptable if included with the unit;

#### Related Equipment

Wireless networking hub/router (802.11g or better) with all associated hardware (adapters, cables, etc) and soft to enable wireless networking and internet connection sharing for all office computers and printers,

An electrical outlet with dedicated circuit for the main computer unit,

An optical mouse with proper driving software having complete Microsoft emulation,

An internal 56/28.8/14.4 fax modem with MNP5 error checking and complete Hayes emulation having high-speed 14.4 fax capability and regular data transmission between 2400 and 56 baud, with the latest version proper driving software,

Necessary cables for proper operation,

An uninterruptible power supply (UPS) units for protection from power loss or fluctuation, minimum of 6 outlets, adequate to provide a minimum of 30 minutes backup power for an orderly shut down of the computer system with software and connections for automatic system shutdown,

24 bit Sound Blaster compatible PCI soundcard with quality desktop speakers,

A combination surge, spike, and noise protection device with receptacles for all peripherals (may be in combination with the UPS power supply),

A wrist rest suitable for use with the furnished keyboard,

Cleaning kits for disk drives,

An anti-glare filter with grounding wire suitable for use with the furnished monitor, and

All cards, hardware, and operating, anti-virus, and equipment software to be fully installed and operational;

#### Maintenance and Service

Maintenance of all specified equipment and components shall be provided for by a validated service agreement for the length of the Contract. Maintenance (upgrades, replacement, full technical support) for each software application shall be provided for by validated maintenance agreement for the length of the Contract. These agreements shall allow an authorized project person to deal directly with the service organization to request repair or the maintenance organization to request assistance; and

Supplies

Consumables as required to manage the business of the project shall be provided for the Microcomputer Systems for the length of the Contract. These consumables shall be furnished on request and include but not be limited to 3-1/2" double sided high density micro floppy diskettes, compatible diskettes for provided digital cameras and memory stick media, DVDR and DVDRW media compatible supporting operational minimum to maximum speed of the DVD/RW drive unit, cut sheet paper and labels compatible with the printers, hardware and screen cleaners, and toner cartridges.

Maintenance of the field office including its adjacent parking area, for the time required, shall consist of maintenance and/or replacement of all provided items, security system, furniture and equipment, computer systems, providing lavatory supplies, providing trash containers and waste baskets, providing entrance mats at each door, providing replacement items for lighting fixtures, maintaining all utilities, providing satisfactory and sanitary janitorial and waste disposal services twice a week, providing cleanup of trash and debris on the parking lot and landscaped area once a week, and shall be included in the monthly unit cost.

The Contractor shall provide and deliver a current copy of all validated field office, equipment, and computer maintenance, service, assistance and/or monitoring agreements and/or contracts as mentioned hereinabove to the Department's administrative office on or before the first day the field office is ready for use.

**Method of Measurement:**

This item will not be measured but will be paid for on a monthly basis. Partial months will be paid at the rate of 0.033 months per day.

**Basis of Payment:**

The field office will be paid for on a unit price bid per month, which price shall be full compensation for performing the work specified and the furnishing of all materials, labor, tools, equipment and incidentals necessary to maintain the field office and its adjacent parking area and restore the field office area and adjacent parking area to match the original site condition. No separate payment will be made for costs involved for removing hazardous material or underground tanks to install these offices or the parking area.

Payment will be made only for the actual number of months that the office is acceptably provided by the Contractor.

The field office shall be ready for use not later than thirty (30) calendar days after the date of the fully executed Contract and before construction operations begin.

3/3/08

## **911500 - PLANTINGS, TUBELINGS**

### **Description:**

This work shall consist of furnishing and installation of tubelings of the species specified and at locations as shown on the Contract Documents.

Tubelings shall be installed from March 1 to May 15 or from September 1 to November 30. Installation of live materials outside of this planting window may only occur during the dormancy season at the approval of the engineer.

### **Materials:**

Tubelings shall consist of grown cuttings of *Cornus amomum* (Silky Dogwood) and *Viburnum dentatum* (Southern Arrow-wood). Materials shall be purchased from a nursery specializing in the production of similar materials and shall include confirmation of species. Each tubeling shall have a minimum root volume of 6 to 10 cubic inches.

### **Construction:**

**Handling.** Tubelings shall be transported in climate-controlled conditions to ensure against temperatures greater than 50°F. Tubelings stored on site shall be kept moist, shaded, and protected against desiccation. Materials stored offsite shall be refrigerated and kept moist. In no case shall non-refrigerated materials be stored longer than five (5) calendar days.

During installation, tubelings shall be kept damp by heeling into moist mulch until ready for use. Cuttings shall be inspected for signs of desiccation, including but not limited to blackening of cut ends and lengthwise wrinkling of bark, and all unsuitable materials shall be appropriately discarded.

**Installation.** Tubelings shall be installed by alternating between the two species, in rows along the channel banks as shown in the Contract Documents. Tubelings shall be installed in one row along channel banks with coir blanket/mat encapsulated soil over furnished cascade material, and three rows along channel banks with a floodplain terrace as shown in the construction plan details. All tubelings shall be placed at a spacing of 1.5 feet on center. On banks with three rows, the row closest to the channel thalweg shall be planted at the top of the low bank in the soil adjacent to the cascade material. The second row shall be planted along the outside edge of the floodplain terrace (toe of slope). The third row shall be placed 1 vertical foot from the second row in a staggered pattern to the second row. With the approval of the Engineer, the Contractor shall achieve the specified spacing by preparing holes using a pointed digging bar, rebar, or other similar implements to achieve both the 6-10 inches of depth as well as the diameter required for each cutting. Tubelings shall be installed vertically into the bank with the root crown level with existing ground or slightly higher. The Contractor shall firmly backfill by hand, all voids surrounding all tubelings, hand tamping the soil tightly against each cutting without damaging the roots or plant. Tubelings shall be watered the equivalent of a 3 inch diameter container at 0.15 gallon per event.

### **Method of Measurement:**

Tubelings shall be measured per each live tubeling planted.

### **Basis of Payment:**

Tubelings will be paid for at the Contract unit price per each live tubeling installed. The payment will be full compensation for furnishing, transporting, storing, watering, and planting, and for all material, labor, equipment, tools, and incidentals necessary to complete this work.

6/20/17

**911502 - DECORATIVE STONE MULCH**

The requirements of Section 737 shall be followed except as modified below:

**Subsection 737.09 Mulch, Delete in its entirety and replace with the following:**

737.09 Mulch. All mulching materials will be visually inspected by the Engineer prior to delivery at the planting site and shall conform to the following requirements:

- (b) Decorative Stone Mulch shall be similar to Delaware River Jack, 1"-3" as furnished by: Holland Mulch, 135 Hay Road Edgemoor, DE 19809, 1-800-823-0020, [www.hollandmulch.com](http://www.hollandmulch.com)

or one of the following:

- (a) The Stone Store, 7535 Railroad Avenue, Harmans, MD 21077, 1-888-766-4242, fax: 410-766-2002, [www.thestonestore.com](http://www.thestonestore.com)
- (b) Wicki Stone Inc., P.O. Box 104, 17 Cemetery Road , Great Meadows, NJ 07838, Phone: 908-637-6004 Fax: 908-637-6282 [www.wickistone.com](http://www.wickistone.com)

Or approved equal by the Engineer.

**Color.** Color of the decorative stone mulch shall be a blended range of colors including tan, brown, light gray, dark gray, white, plum or peach.

**Depth.** Decorative stone mulch shall be place to a uniform depth of 3 inches.

Only the above mulches will be selected and approved for use throughout the entire Project, and written certification for the above listed requirements of the mulch shall be submitted by the Contractor.

**Subsection 737.19 Basis of Payment.**

Delete this section in their entirety and insert the following:

Decorative Stone Mulch will be paid for at the Contract unit price bid per SY. Payment for Decorative Stone Mulch shall be full compensation for all material, labor, hauling, installation and all items necessary to complete the item of work.

5/8/17



STATE OF DELAWARE  
**DEPARTMENT OF TRANSPORTATION**

800 BAY ROAD  
P.O. Box 778  
DOVER, DELAWARE 19903

JENNIFER COHAN  
SECRETARY

**UTILITY STATEMENT**

02/07/2019

**State Contract No. T201880103**  
**P6 #18-82202**  
**North District Improvements, Phase 1**  
**New Castle County**

The following utility companies maintain facilities near the project limits:

**Suez Water Company**  
**DelDOT – Consortium Fiber**  
**DelDOT – Fiber Optic Telecommunication**  
**Delmarva Power Electric - Transmission**  
**Delmarva Power Electric - Distribution**  
**New Castle County Department of Public Works – Sanitary Sewer**  
**DelDOT – Private Sanitary Sewer**

The following is a breakdown of the utilities involved, adjustments and/or relocations as required:

**Suez Water Company**

SUEZ Water Company maintains 12" and 16" cast iron mains through the site.

**Proposed water services:**

Suez:

- Suez Water will install one 8"x12" wet tap and 8" gate valve on the 12" existing main for the fire service at approximate station 2+92, offset 6' left.

State's Contractor work to be performed:

- After the wet tap is complete, DelDOT's contractor will connect an 8" DIP Class 52 water main to the 8" gate valve installed by Suez. The 8" water main will run for 642 LF before it reduces to a 6" DIP Class 52 water main for 14 LF before terminating at a proposed 6" gate valve and fire hydrant assembly.

- The 8" main will have a 8"x4" tee (approximate station 5+93, offset 9' left), this tee will transition from 4" DIP Class 52 to 4" DR-11 HDPE using an adapter. The 4" DR-11 HDPE will then reduce to a 3" DR-11 HDPE water main which extends for 50 LF to provide fire protection to the proposed building. A 3" gate valve will be located on the main before it enters the building.
- The approved contractor will also install a 2" DR-11 HDPE water main for the domestic water for the proposed building. This 2" main will run for approximately 429 LF to the nearest tie-in location to the existing 2" water main that is on site. Contractor will field locate the existing 2" water main using test holes (paid under item 204000 – Test Hole) and tie in the new water service using a 2"x2" tee and sleeves. A 2" curb stop will be located on the proposed 2" main shortly after the 2"x2" tee with the existing main. A 2" curb stop will also be located on the existing 2" main shortly after the 2"x2" tee. In addition, a 2" curb stop will be located outside of the proposed building.

State contractor to refer to sheets 15-16, 26-28 for more information.

Suez will require 42 days' notice prior to installation of new equipment.

No existing water facilities can be taken out of service. Existing facilities will remain in place and active during the duration of this contract.

#### **DelDOT ITMS Pathway and Fiber Optic Cable– (Formerly “Consortium” Fiber)**

DelDOT maintains an existing ITMS Pathway & Fiber Optic Cable service through the project site. The existing fiber facility consists of approximately 1 fiber run running through the project area consisting of 6 – direct buried 1-inch inner ducts.

#### **Proposed State’s Contractor work to be performed:**

Prior to DelDOT’s contractor beginning site work, DelDOT’s internal forces will abandon approximately 5292 linear feet of fiber pathway (6 inner duct runs at 882 linear feet each) and 2 existing “type 7” junction wells. DelDOT Forces will remove the existing fiber optic line at 882 linear feet. DelDOT’s internal forces will install new fiber lines within a trench approximately 1030 linear feet through the project area (multiple conduits and a fiber line) and install 2 new conduit junction wells: 1 each at Station 11+49 (offset 292 linear feet right of baseline) and Station 11+60 (offset 113 linear feet right of baseline).

DelDOT’s general contractor, after verification of limits of abandonment from DelDOT internal forces, will remove the abandoned consortium fiber facilities between approximate Station 3+22 (offset 264' right of baseline) to approximate Station 11+60 (offset 113' right of baseline). Items to be removed include, but are not limited to, direct buried inner ducts and existing junction wells. The removal of the above items will be paid as a lump sum under item 211000 – Removal of Structures and Obstructions.

The State’s contractor shall not perform any earth moving or other construction activities within the vicinity of the existing or relocated fiber lines until DelDOT has provided verification that the lines have been abandoned and the new consortium fiber services are operational.

State contractor to refer to sheet 26 in the project plans for more information.

#### **DelDOT – Fiber Optic Telecommunication**

DelDOT maintains a Fiber Optic network throughout the site.

Proposed installations:

It is anticipated that DelDOT's general contractor will install approximately 300' of 2W-4" conduit from an existing junction well to the Crew Ops building and 1 additional junction well in accordance with Division 26 of the Site Specifications. After the installation of junction well and conduit, DelDOT Internal Forces will install new fiber optic lines.

State contractor to refer to sheet 67 of the project plans for more information.

**Delmarva Power Electric - Transmission**

Delmarva Power maintains overhead transmission lines within a private easement across the project area. No impacts to the transmission lines are anticipated as part of the project.

The State's contractor shall allow access to Delmarva Power easement through the site at all times for maintenance.

**NO CONSTRUCTION EQUIPMENT CAN BE WITHIN 20 FEET OF THESE TRANSMISSION LINES.**

**No existing electric facilities can be taken out of service.**

**These facilities will remain in place and active during the duration of the contract.**

**Delmarva Power Electric - Distribution**

Delmarva Power maintains 12kv primary distribution along Chapman Road with no impacts.

Proposed Electric Service:

State's contractor:

- DelDOT will have a Delmarva Power approved (at the time of bid) contractor install approximately 600' ft of 2 - 4" schedule 40 conduit for Primary electric feed to site.
- DelDOT's approved contractor will provide and install 3 phase 25 kv primary cable from the Utility Pole specified by Delmarva Power along Chapman Road to the new 3-phase pad location shown on the utility plan sheet. Enough 3 phase primary cable will be rolled up by the Delmarva Power pole for Delmarva Power to take the cable up the pole and make proper connections.

Delmarva Power will provide the required 3 phase pad-mounted transformer with elbows included.

Any secondary connectors will be provided by DelDOT's contractor. All connections made inside the 3-phase transformer will be made by Delmarva Power. All material used by contractor will be Delmarva Power approved material. There will be electrical outages to DelDOT's facilities when the change over to the new service takes place. If outages have to be done on off hours DPL will charge DelDOT for any night work in addition to cost of the project.

It is anticipated that Delmarva Power will need 60 days of advance notice prior to installation of equipment and approximately 5 days to install new equipment. A field meeting will be required between DelDOT's contractor and a Delmarva Power representative before the preconstruction meeting occurs.

For exact location of electric facilities, please contact Miss Utility at (800) 282-8555.

*16 Del. C. § 7405B requires notification to and mutually agreeable measures from the public utility from any person intending to carry on any function, activity, work or operation within dangerous proximity of any high voltage overhead lines. All contractors/other utilities must also maintain a distance of 10'-0" from all aerial energized lines.*

**No existing electric facilities can be taken out of service.**

**These facilities will remain in place and active during the duration of this contract.**

### **New Castle County Department of Public Works – Sanitary Sewer**

New Castle County maintains an 8" gravity sewer to service the site with no impacts.

#### **Proposed Sanitary Sewer Service:**

DelDOT's general contractor will connect internally to the existing privately owned (DelDOT) sewer service.

- The connection will occur at the existing manhole located at station 4+48 (offset 66 linear feet right of baseline). At the time of connection DelDOT's general contractor will be required to modify the manhole to provide a flow channel per New Castle County Specifications. The new connection is subject to inspection from New Castle County. The contractor is to notify New Castle County of the proposed modification and schedule the inspection.
- After the connection to the manhole is made the contractor will install 213 LF of 6" PVC sewer lateral and two 6" cleanouts to provide service to the proposed crew operations building.

State contractor to refer to sheets 15, 26, and 28 in the project plans for further information.

**No existing sanitary sewer facilities can be taken out of service.**

**These facilities will remain in place and active during the duration of this contract.**

## GENERAL UTILITY NOTES

Outside of the companies and facilities discussed above, no additional utility involvement is anticipated. Should any conflicts be encountered as a result of the contractor's means and methods during construction requiring adjustment and/or relocation, the necessary relocation work shall be accomplished by the respective utility company and funded by the State's Contractor as directed by the District Engineer. The State Contractor shall coordinate any potential conflicts with utility companies and provide adequate notice prior to performing work. Any utility conflicts that are not readily discernable shall be coordinated by the State Contractor once the conflict is recognized. The time to complete any relocations/adjustments found to be necessary during construction of the project will depend on the nature of the work.

Once the State's contractor has given the Utility the advance notice required above, it is the responsibility of the State's contractor to have the work area prepared and accessible for the Utility to perform the tasks listed above. If the site conditions are not ready and the state contractor has given notice to the utility on when the work is to be accomplished, the State's Contractor shall be responsible for any extra cost incurred by the utility company and the State Contractor shall also be responsible for any time delays. Between when the required notice is given to the Utility and when the work is performed and completed, the coordination and scheduling of the Utility is the sole responsibility of the State's Contractor. All costs related to the coordination and scheduling of the utilities is incidental to the contract.

Any adjustments and/or relocations of municipally owned sewer or water facilities shall be performed by the State's Contractor in accordance with the respective agency's standard specifications as directed by the District Engineer. The State contractor shall coordinate any potential conflicts of municipally owned sewer or water facilities with facility owners and provide adequate notice to the municipally and to the District Engineer prior to performing work.

## GENERAL NOTES

1. The Contractor's attention is directed to Section 105.09 Utilities, Delaware Standard Specifications, August 2016. The Contractor shall contact Miss Utility (1-800-282-8555) two working days prior to any excavation. The Contractor is responsible for the support and protection of all utilities when excavating. The Contractor is responsible for ensuring proper clearances, including safety clearances, from overhead utilities for construction equipment. The Contractor is advised to check the site for access and operating purposes for his equipment and, if necessary, make arrangements directly with the utility companies for field adjustments for adequate clearances.
2. The information shown in the Contract Documents, including the Utility Statement and the Utility Schedule contained herein, concerning the location, type, and size of existing and proposed utilities, their locations, and construction timing has been compiled by the preparer based on information furnished by each of the involved Utility Companies. It shall be the responsibility of the State's Contractor to verify all information and coordinate with the Utility Companies prior to and during construction, as specified in Section 105.09 of the Standard Specifications.
3. It is understood and agreed that the Contractor has considered in his bid all permanent and temporary utility appurtenances in their present and relocated positions as shown on the plans or described in the Utility Statement or are readily discernible and that no additional compensation will be allowed for any delays, inconvenience, or damage due to any interference from the utility facilities and appurtenances or the operation of moving them, except that the Contractor may be granted an equitable extension of time unless the delay is caused by the Contractor's delay in having the site conditions ready for the utility relocation work after the Contractor has provided the advance notice

that the site conditions would be ready for the utility relocation work. The contractor's means and method of construction are not taken into account when known utility conflicts are identified. If the Contractor's means and method of construction create a utility conflict, the Utility Statement will prevail in discussions with the utility and the Contractor. The State's Contractor shall be responsible for any costs associated with any temporary outages; holding, bracing and shielding of utility facilities; temporary relocations; or permanent relocations that are not specifically identified in this utility statement or shown in the contract plan set.

4. Coordination and cooperation among the Utility Companies and the State's Contractor are of prime importance. Therefore, the Contractor is directed to contact the following Utility Company representatives with any questions regarding this work prior to submitting bids and work schedules. Proposed work schedules should reflect the Utility Companies' proposed relocations. The Utility Companies do not work on weekends, nights or legal holidays.

NAME	COMPANY	PHONE
Ted Harris	Suez Water Company	(302) 252-3016
Tom Smith	Delmarva Power – Electric	(302) 283-5757
Dan Netta	New Castle County Dept. of Public Works	302-395-5817

5. As outlined in Chapter 3 of the DelDOT Utilities Manual, individual utility companies are responsible for obtaining all required permits from municipal, State and federal government agencies and railroads. This includes but is not limited to water quality permits/DNREC Water Quality Certification, DNREC Subaqueous Lands/Wetlands permits, DNREC Coastal Zone Consistency Certification, County Floodplain permits (New Castle County only), U.S. Coast Guard permits, US Army Corps 404 permits, sediment and erosion permits, and railroad crossing permits.
6. Individual utility companies are required to restore any areas disturbed in conjunction with their relocation work. If an area is disturbed by a utility company and is not properly restored, the Department may have the State's Contractor perform the necessary restoration. Any additional costs incurred as a result will be forwarded to the utility company.
7. 16 Del. C. § 7405B requires notification to and mutually agreeable measures from the public utility operating the electric line for any person intending to carry on any function, activity, work or operation within dangerous proximity of any high voltage overhead electric lines. All contractors/other utilities must also maintain a minimum distance of 10'-0" from all energized lines. Additional clearance may be required from high voltage transmission lines.
8. Any existing facilities that are comprised of hazardous materials will be removed by the Utility Company unless otherwise outlined in the contract documents or language above. Any existing facilities containing hazardous materials will be purged by the Utility Company unless otherwise outlined in the contract documents or language above.

**Prepared and Recommended by:**



William Dougherty, PE / JMT

bdougherty@jmt.com  
EMAIL

02/07/2019  
DATE

**Approved as to form by:**



Utilities Section, DelDOT

deborah.kukulich@delaware.gov  
EMAIL

February 11, 2019  
DATE

cc. Deborah Kukulich, DelDOT Utilities  
Taylor King, DelDOT Statewide Support Services  
Jeff Armstrong, DelDOT Statewide Support Services

STATE OF DELAWARE  
DEPARTMENT OF TRANSPORTATION  
PO BOX 778  
DOVER, DELAWARE 19903

CERTIFICATE OF RIGHT-OF-WAY STATUS

STATE PROJECT NO. T201880103

F.A.P. NO. N/A for R/W

NORTH DISTRICT IMPROVEMENTS, PHASE 1A

NEW CASTLE COUNTY

Certificate of Right-of-Way Status – 100%

Level 1

**As required by 23 CFR, Part 635, and other pertinent Federal and State regulations or laws, the following certifications are hereby made in reference to this highway project:**

All project construction or work shall be performed within existing rights of way and permanent easements; and,

**All necessary real property interests, including control of access rights when pertinent, were acquired as part of previous highway projects, and include legal and physical possession; and,**

This project does not cause any persons to be displaced as defined in 49 CFR, Part 24; and,

The State has the right to remove, salvage, or demolish any improvements or personal property that may be located within project limits.

RIGHT OF WAY SECTION



Robert Cunningham  
Chief, Right of Way

May 3, 2018



STATE OF DELAWARE  
**DEPARTMENT OF TRANSPORTATION**  
800 BAY ROAD  
P.O. BOX 778  
DOVER, DELAWARE 19903

JENNIFER COHAN  
SECRETARY

January 28, 2019

ENVIRONMENTAL REQUIREMENTS

FOR  
State Contract No. T201880103  
Federal Aid No.: N/A

Contract Title: North District Improvements, Phase I

Due to the nature of the proposed construction activities, permits are not required for this project. However, the following construction requirements and special provisions have been developed to minimize and mitigate impact to the surrounding environs. These requirements by DelDOT, not specified within the contract, are listed below. These requirements are the responsibility of the contractor and are subject to risk of shut down at the contractor's expense if not followed.

GENERAL REQUIREMENTS:

1. All construction debris, excavated material, brush, rocks, and refuse incidental to such work shall be placed either on shore above the influence of flood waters or on some suitable dumping ground.
2. That effort shall be made to keep construction debris from entering adjacent waterways or wetlands. Any debris that enters those areas shall be removed immediately.
3. The disposal of trees, brush, and other debris in any stream corridor, wetland, surface water, or drainage area is prohibited.
4. DelDOT Environmental Studies Section (302) 760-2264 must be notified if there are any changes to the project methods, footprint, materials, or designs, to allow the Department to coordinate with the appropriate resource agencies (COE, DNREC, and SHPO), for approval.



STATE OF DELAWARE  
**DEPARTMENT OF TRANSPORTATION**  
 800 BAY ROAD  
 P.O. BOX 778  
 DOVER, DELAWARE 19903

JENNIFER COHAN  
 SECRETARY

**RAILROAD STATEMENT**

**For**

**State Contract No.:** T201880103

**Federal Aid No.:** N/A

**Project Title:** North District Maintenance Yard Phase I Site Improvements

**The following railroad companies maintain facilities within the contract limits:**

- |  |   |
|--|---|
| <input type="checkbox"/> Amtrak              | <input type="checkbox"/> Maryland & Delaware  |
| <input type="checkbox"/> CSX                 | <input type="checkbox"/> Norfolk Southern     |
| <input type="checkbox"/> Delaware Coast Line | <input type="checkbox"/> Wilmington & Western |
| <input type="checkbox"/> East Penn           | <input checked="" type="checkbox"/> None      |
| <input type="checkbox"/> Delmarva Central    |   |

DOT Inventory No.:     N/A     No. Trains/Day:     N/A     Passenger Trains (Y / N):     N/A    

**In accordance with 23 CFR 635, herein is the railroad statement of coordination (check one):**

- No Railroad involvement.
  
- Railroad Agreement unnecessary but railroad flagging required. The contractor shall follow requirements stated in the DelDOT Maintenance of Railroad Traffic Item in the Special Provisions. Contractor shall coordinate railroad flagging with DelDOT's Railroad Program Manager at (302) 760-2183.
  
- Railroad Agreement required. The necessary Railroad Agreement is pending. The Contractor cannot begin work until the Agreement is complete and fully executed. Railroad related work to be undertaken and completed as required for proper coordination with physical construction schedules. The Contractor shall follow requirements stated in the DelDOT Maintenance of Railroad Traffic Item in the Special Provisions. Contractor shall coordinate railroad flagging with DelDOT's Railroad Program Manager at (302) 760-2183.

**Approved As To Form:**

  
 \_\_\_\_\_  
 Robert A. Perrine  
 DelDOT Railroad Program Manager

3May18  
 \_\_\_\_\_  
 DATE

# **BID PROPOSAL FORMS**

**CONTRACT T201880103.01**

UNLESS OTHERWISE DIRECTED, SUBMIT ALL FOLLOWING PAGES TO:

DEPARTMENT OF TRANSPORTATION  
BIDDERS ROOM  
800 BAY ROAD  
DOVER, DELAWARE 19901

Identify the following on the outside of the sealed envelope:  
- Contract Number T201880103.01  
- Name of Contractor

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 NORTH DISTRICT IMPROVEMENTS PHASE 1A. SITE WORK AND CQ.						
0010	201000 CLEARING AND GRUBBING	LUMP	LUMP			
0020	202000 EXCAVATION AND EMBANKMENT	CY	2250.000			
0030	204000 TEST HOLE	CY	12.000			
0040	208000 FLOWABLE FILL	CY	8.000			
0050	209003 FURNISHING BORROW, TYPE B FOR PIPE AND UTILITY TRENCH BACKFILL	CY	688.000			
0060	209004 BORROW, TYPE C	CY	27600.000			
0070	211000 REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	LUMP			
0080	301003 GRADED AGGREGATE BASE COURSE, TYPE B	TON	5993.000			
0090	301004 GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	TON	108.000			

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	302002 DELAWARE NO. 3 STONE	14.000 TON				
0110	401006 SUPERPAVE TYPE C, PG 70-22 (CARBONATE STONE)	1143.000 TON				
0120	401015 SUPERPAVE TYPE B, PG 70-22	2486.000 TON				
0130	401029 SUPERPAVE TYPE C, PG 64-22, PATCHING	17.000 TON				
0140	401030 SUPERPAVE TYPE B, PG 64-22, PATCHING	65.000 TON				
0150	501006 PORTLAND CEMENT CONCRETE PAVEMENT, 12"	80.000 SY				
0160	601010 REINFORCED CONCRETE PIPE, 12" CLASS III	114.000 LF				
0170	601011 REINFORCED CONCRETE PIPE, 15", CLASS III	560.000 LF				
0180	601012 REINFORCED CONCRETE PIPE, 18", CLASS III	117.000 LF				
0190	601031 REINFORCED CONCRETE PIPE, 12" CLASS IV	299.000 LF				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	601053 REINFORCED CONCRETE PIPE, 15", CLASS V	53.000 LF				
0210	601140 REINFORCED CONCRETE FLARED END SECTION, 12"	2.000 EACH				
0220	601141 REINFORCED CONCRETE FLARED END SECTION, 15"	3.000 EACH				
0230	601142 REINFORCED CONCRETE FLARED END SECTION, 18"	1.000 EACH				
0240	601191 PVC PIPE, 6"	248.000 LF				
0250	602003 DRAINAGE INLET, 34" X 24"	6.000 EACH				
0260	602030 MANHOLE, 48" X 30"	3.000 EACH				
0270	602130 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	1.000 EACH				
0280	610009 PORTLAND CEMENT CONCRETE MASONRY, CLASS B	7.000 CY				
0290	701013 PORTLAND CEMENT CONCRETE CURB, TYPE 1-8	353.000 LF				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	701505 PORTLAND CEMENT CONCRETE PARKING BUMPER	30.000 EACH				
0310	705001 PORTLAND CEMENT CONCRETE SIDEWALK, 4"	1620.000 SF				
0320	705002 PORTLAND CEMENT CONCRETE SIDEWALK, 6"	277.000 SF				
0330	705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	20.000 SF				
0340	707001 RIPRAP, R-4	45.000 SY				
0350	707010 RIPRAP, R-4	12.000 CY				
0360	708002 GEOTEXTILES, SEPARATION	57.000 SY				
0370	708003 GEOTEXTILES, RIPRAP	45.000 SY				
0380	710500 INSTALLATION OF WATERMAIN AND ACCESSORIES	LUMP	LUMP			
0390	711002 SANITARY SEWER SYSTEM	LUMP	LUMP			
0400	720556 BOLLARD	2.000 EACH				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0410	727000 CHAIN LINK FENCE	2098.000				
		LF				
0420	727004 WOOD VERTICAL SLAT FENCE	20.000				
		LF				
0430	727010 CHAIN LINK FENCE GATE	3.000				
		EACH				
0440	762000 SAW CUTTING, BITUMINOUS CONCRETE	857.000				
		LF				
0450	763000 INITIAL EXPENSE/DE-MOBILIZATION		LUMP	LUMP		
0460	763501 CONSTRUCTION ENGINEERING		LUMP	LUMP		
0470	763504 SITE WORK		LUMP	LUMP		
0480	763509 CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	18.000				
		EAMO				
0490	763511 MAINTENANCE BUILDING		LUMP	LUMP		
0500	763598 FIELD OFFICE, SPECIAL I	18.000				
		EAMO				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0510	817013 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	2170.000 LF				
0520	817017 PREFORMED RETROREFLECTIVE THERMOPLASTIC MARKINGS, HANDICAP SYMBOL	3.000 EACH				
0530	819018 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	6.000 EACH				
0540	905001 SILT FENCE	1000.000 LF				
0550	905002 REINFORCED SILT FENCE	1160.000 LF				
0560	905004 INLET SEDIMENT CONTROL, DRAINAGE INLET	6.000 EACH				
0570	905005 INLET SEDIMENT CONTROL, CURB INLET	7.000 EACH				
0580	905006 INLET SEDIMENT CONTROL, CULVERT INLET	1.000 EACH				
0590	906004 SKIMMER DEWATERING DEVICE	1.000 EACH				
0600	907017 COMPOST FILTER LOGS	68.000 LF				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0610	908004 TOPSOIL, 6" DEPTH	15172.000 SY				
0620	908014 PERMANENT GRASS SEEDING, DRY GROUND	13604.000 SY				
0630	908015 PERMANENT GRASS SEEDING, STORMWATER	2277.000 SY				
0640	908017 TEMPORARY GRASS SEEDING	30344.000 SY				
0650	908020 EROSION CONTROL BLANKET MULCH	4020.000 SY				
0660	908023 STABILIZED CONSTRUCTION ENTRANCE	42.000 SY				
0670	910002 INFILTRATION STONE, NO. 8	410.000 TON				
0680	910005 CLAY BORROW POND LINER	648.000 CY				
0690	910006 OUTLET STRUCTURE	2.000 EACH				
0700	910008 STORMWATER MANAGEMENT POND	4840.000 CY				

CONTRACT ID: T201880103.01 PROJECT(S): T201880103

All figures must be typewritten.

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0710	910010 BIORETENTION AREA	757.000 CY				
0720	910011 BIOSOIL MIX	186.000 CY				
0730	911500 PLANTINGS, TUBELINGS	1.000 EACH				
0740	911502 DECORATIVE STONE MULCH	189.000 SY				
SECTION 0001 TOTAL						
TOTAL BID						

CANNOT BE USED FOR BIDDING

# BREAKOUT SHEET INSTRUCTIONS

**BREAKOUT SHEET(S) MUST BE SUBMITTED EITHER WITH YOUR BID DOCUMENTS; OR WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE BID DUE DATE BY THE LOWEST APPARENT BIDDER.**

BREAKOUT SHEETS ARE TO BE SUBMITTED TO DELDOT'S CONTRACT ADMINISTRATION AS SHOWN BELOW. BREAKOUT SHEETS CANNOT BE CHANGED AFTER AWARD. THE DEPARTMENT WILL REVIEW THE FIGURES SUBMITTED ON THE BREAKOUT SHEET(S) TO ENSURE THEY MATCH THE RESPECTIVE LUMP SUM BID AMOUNT(S). MATHEMATICALLY INCORRECT BREAKOUT SHEETS WILL BE RETURNED FOR IMMEDIATE CORRECTION.

BREAKOUT SHEETS MAY BE SUBMITTED;

VIA E-MAIL TO: [DOT-ASK@STATE.DE.US](mailto:DOT-ASK@STATE.DE.US)  
SUBJECT: **T201880103.01** Breakout Sheet

OR MAILED TO: DELDOT  
CONTRACT ADMINISTRATION  
PO BOX 778, DOVER, DE 19903

'BREAKOUT SHEET' AND THE PROJECT NUMBER  
MUST APPEAR ON THE ENVELOPE.

CONTRACTOR \_\_\_\_\_

<b>BREAKOUT SHEET - 1</b>						<b>CONTRACT NO. T201880103.01</b>	
<b>Item 763511 – MAINTENANCE BUILDING</b>							
ITEM NO.	APPROX QTY.	UOM	DESCRIPTION	UNIT PRICE	AMOUNT		
1	1	LS	DIVISION 03 - CONCRETE	\$	\$		
2	1	LS	DIVISION 05 - METALS	\$	\$		
3	1	LS	DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES	\$	\$		
4	1	LS	DIVISION 07 - THERMAL AND MOISTURE PROTECTION	\$	\$		
5	1	LS	DIVISION 08 - OPENINGS	\$	\$		
6	1	LS	DIVISION 09 - FINISHES	\$	\$		
7	1	LS	DIVISION 10 - SPECIALTIES	\$	\$		
8	1	LS	DIVISION 12 - FURNISHINGS	\$	\$		
9	1	LS	DIVISION 22 - PLUMBING	\$	\$		
10	1	LS	DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING	\$	\$		
11	1	LS	DIVISION 26 - ELECTRICAL	\$	\$		
12	1	LS	DIVISION 27 - COMMUNICATIONS	\$	\$		
13	1	LS	DIVISION 28 - ELECTRONIC SAFETY AND SECURITY	\$	\$		
<b>TOTAL ITEM 763511 – MAINTENANCE BUILDING \$ _____</b>							
(LUMP SUM BID PRICE FOR ITEM 763511 – MAINTENANCE BUILDING)							

CONTRACTOR \_\_\_\_\_

<b>BREAKOUT SHEET - 2</b>						<b>CONTRACT NO. T201880103.01</b>	
<b>Item 763504 – SITE WORK FOR ELECTRICAL</b>							
ITEM NO.	APPROX QTY.	UOM	DESCRIPTION	UNIT PRICE	AMOUNT		
1	1	LS	SERVICE TRANSFORMER	\$	\$		
2	1	LS	AUTOMATIC TRANSFER SWITCH	\$	\$		
3	1	LS	GENERATOR SET	\$	\$		
4	575	LF	UTILITY CONDUIT	\$	\$		
5	1	LS	GENERATOR TRANSFORMER	\$	\$		
6	1	LS	GENERATOR PANELBOARD	\$	\$		
7	1	LS	SWITCHBOARD	\$	\$		
8	1	LS	UTILITY MANHOLE	\$	\$		
9	1	LS	HIGHLAND TANK, CATWALK & STAIRS	\$	\$		
10	1	LS	REMOTE FILL STATION	\$	\$		
11	1	LS	FUEL FILTERING SYSTEM	\$	\$		
12	1	LS	TANK FITTINGS AND VALVES	\$	\$		
13	160	LF	PIPING TO GENERATORS	\$	\$		
14	1	LS	FUEL MONITORING SYSTEM	\$	\$		
15	1	LS	MINI ME FUEL REMOTE PANEL	\$	\$		
16	1	LS	CONCRETE PAD (GENERATOR, ETC)	\$	\$		
17	1	LS	WIRE, JUNNCTION WELLS, AND CONDUIT FROM MAIN PANELBOARD TO CREW QUARTERS	\$	\$		
<b>TOTAL ITEM 763504 – SITE WORK FOR ELECTRICAL \$ _____</b>							
<b>(LUMP SUM BID PRICE FOR ITEM 763504 – SITE WORK FOR ELECTRICAL</b>							

# "ATTENTION"

## TO BIDDERS

**BREAKOUT SHEET(S) MUST BE SUBMITTED EITHER WITH YOUR BID DOCUMENTS; OR WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE BID DUE DATE BY THE LOWEST APPARENT BIDDER.**

BREAKOUT SHEETS ARE TO BE SUBMITTED TO DELDOT'S CONTRACT ADMINISTRATION AS SHOWN BELOW. BREAKOUT SHEETS CANNOT BE CHANGED AFTER AWARD. THE DEPARTMENT WILL REVIEW THE FIGURES SUBMITTED ON THE BREAKOUT SHEET(S) TO ENSURE THEY MATCH THE RESPECTIVE LUMP SUM BID AMOUNT(S). MATHEMATICALLY INCORRECT BREAKOUT SHEETS WILL BE RETURNED FOR IMMEDIATE CORRECTION.

BREAKOUT SHEETS MAY BE SUBMITTED;

VIA E-MAIL TO: [DOT-ASK@STATE.DE.US](mailto:DOT-ASK@STATE.DE.US)  
SUBJECT: **T201880103.01** Breakout Sheet

OR MAILED TO: DELDOT  
CONTRACT ADMINISTRATION  
PO BOX 778, DOVER, DE 19903

'BREAKOUT SHEET' AND THE PROJECT NUMBER  
MUST APPEAR ON THE ENVELOPE.



**AFFIDAVIT  
OF  
EMPLOYEE DRUG TESTING PROGRAM**

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors implement a program of mandatory drug testing for Employees who work on Large Public Works Contracts funded all or in part with public funds.

We hereby certify that we have in place or will implement during the entire term of the contract a Mandatory Drug Testing Program for our employees on the jobsite, including subcontractors, that complies with this regulation:

**Contractor Name:** \_\_\_\_\_

**Contractor Address:** \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Authorized Representative (typed or printed):** \_\_\_\_\_

**Authorized Representative (signature):** \_\_\_\_\_

**Title:** \_\_\_\_\_

Sworn to and Subscribed before me this \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_.

My Commission expires \_\_\_\_\_ . NOTARY PUBLIC \_\_\_\_\_ .

**THIS PAGE MUST BE SIGNED, NOTARIZED, AND RETURNED WITH YOUR BID.**

**(This form is required from the prime contractor only, not required from subcontractors)**

**LIST OF BUILDING SUBCONTRACTORS**

In accordance with 29 Del.C. §6962(d)10a and 10b, a Pre-Bid Meeting will be held to select the subcontractor categories to be included in the bids for performing the work required for this contract.

This proposal is based on work to be performed by the Subcontractors listed below for the categories selected at the Pre-Bid Meeting.

A bid submitted in the name of an individual should list the individual's name followed by T/A and the name of the company.

EXAMPLE: John Doe, T/A Doe Contracting Company

In accordance with Title 29, Subsection 6962(d)(10)b of the Delaware Code, a penalty of \$2,000.00 will be withheld from the successful bidder for each occurrence for the failure to utilize any or all of the Subcontractors set forth below:

CATEGORIES	SUBCONTRACTOR	ADDRESS CITY AND STATE
------------	---------------	---------------------------

**Sample page only, DO NOT USE! This page will be replaced in an Addendum with a listing of the Subcontractor Categories following the Pre-Bid Meeting.**

**You MUST use the updated form when submitting your bid. For your bid to be accepted, the updated form must be filled out correctly.**

CANNOT BE  
USED FOR  
BIDDING

**CERTIFICATION**  
Contract No. T201880103.01

The undersigned bidder, \_\_\_\_\_

whose address is \_\_\_\_\_

and telephone number is \_\_\_\_\_ hereby certifies the following:

I/We have carefully examined the location of the proposed work, the proposed plans and specifications, and will be bound, upon award of this contract by the Department of Transportation, to execute in accordance with such award, a contract with necessary surety bond, of which contract this proposal and said plans and specifications shall be a part, to provide all necessary machinery, tools, labor and other means of construction, and to do all the work and to furnish all the materials necessary to perform and complete the said contract within the time and as required in accordance with the requirements of the Department of Transportation, and at the unit prices for the various items as listed on the preceding pages.

The foregoing quantities are considered to be approximate only and are given as the basis for comparison of bids. The Department of Transportation may increase or decrease the amount of any item or portion of the work as may be deemed necessary or expedient. Any such increase or decrease in the quantity for any item will not be regarded as a sufficient ground for an increase or decrease in the unit prices, nor in the time allowed for the completion of the work, except as provided in the contract.

Accompanying this proposal is a surety bond or a security of the bidder assigned to the Department of Transportation, for at least ten (10) percentum of total amount of the proposal, which deposit is to be forfeited as liquidated damages in case this proposal is accepted, and the undersigned shall fail to execute a contract with necessary bond, when required, for the performance of said contract with the Department of Transportation, under the conditions of this proposal, within twenty (20) days after date of official notice of the award of the contract as provided in the requirement and specifications hereto attached; otherwise said deposit is to be returned to the undersigned.

I/We are licensed, or have initiated the license application as required by Section 2502, Chapter 25, Title 30, of the Delaware Code.

By submission of this proposal, each bidder and each person signing on behalf of any bidder, certifies as to its own organization, under penalty of perjury, that to the best of each signer's knowledge and belief:

1. The prices in this proposal have been arrived at independently without collusion, consultation, communication, or Agreement with any other bidder or with any competitor for the purpose of restricting competition.
2. Unless required by law, the prices which have been quoted in this proposal have not been knowingly disclosed and will not knowingly be disclosed by the bidder, directly or indirectly, to any other bidder or competitor prior to the opening of proposals.
3. No attempt has been made or will be made by the bidder to induce any other person, partnership, or corporation to submit or not to submit a proposal for the purpose of restricting competition.

=====  
I/We acknowledge receipt and incorporation of addenda to this proposal as follows:

No.	Date								
-----	------	-----	------	-----	------	-----	------	-----	------

\_\_\_\_\_

**BIDDERS MUST ACKNOWLEDGE RECEIPT OF ALL ADDENDA**

**MUST INSERT DATE OF FINAL QUESTIONS AND ANSWERS ON WEBSITE:** \_\_\_\_\_



**AFFIRMATION:**

Within the past five (5) years, has your firm, any affiliate, any predecessor company or entity, owner, Director, officer, partner or proprietor been the subject of a Federal, State, Local government suspension or debarment?

YES \_\_\_\_\_ NO \_\_\_\_\_ if yes, please explain \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

**Agreement to Accept Retainage**

"Bidder acknowledges that if its Performance-Based Rating as defined in 29 Del.C. §6962 and section NEW 2408 of Title 2 of Delaware's Administrative Code is below the required minimum threshold, as a condition to bid, Bidder acknowledges, consents and agrees to the Department withholding retainage of up to 5% from the monies due at the time of each progress payment under the contract."

Sealed and dated this \_\_\_\_\_ day of \_\_\_\_\_ in the year of our Lord two thousand \_\_\_\_\_ (20\_\_\_\_).

CANNOT BE

\_\_\_\_\_  
Name of Bidder (Organization)

Corporate  
Seal

By: \_\_\_\_\_  
Authorized Signature

Attest \_\_\_\_\_  
Title

SWORN TO AND SUBSCRIBED BEFORE ME this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Notary  
Seal

\_\_\_\_\_  
Notary

BIDDING

**BID BOND**

TO ACCOMPANY PROPOSAL  
(Not necessary if security is used)

KNOW ALL MEN BY THESE PRESENTS That: \_\_\_\_\_

of \_\_\_\_\_ in the County of \_\_\_\_\_ and State of \_\_\_\_\_

as **Principal**, and \_\_\_\_\_ of \_\_\_\_\_ in the County  
of \_\_\_\_\_

\_\_\_\_\_ and State of \_\_\_\_\_ as **Surety**, legally authorized to do business in  
the

State of Delaware ("**State**"), are held and firmly bound unto the **State** in the sum of \_\_\_\_\_

\_\_\_\_\_ Dollars (\$ \_\_\_\_\_), or \_\_\_\_\_ percent not to exceed \_\_\_\_\_

\_\_\_\_\_ Dollars (\$ \_\_\_\_\_) of amount of bid on  
Contract No. T201880103.01 , to be paid to the **State** for the use and benefit of its Department of  
Transportation ("**DelDOT**") for which payment well and truly to be made, we do bind ourselves, our and  
each of our heirs, executors, administrators, and successors, jointly and severally for and in the whole  
firmly by these presents.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH That if the above bounden **Principal**  
who has submitted to the **DelDOT** a certain proposal to enter into this contract for the furnishing of  
certain materiel and/or services within the **State**, shall be awarded this Contract, and if said **Principal**  
shall well and truly enter into and execute this Contract as may be required by the terms of this Contract  
and approved by the **DelDOT**, this Contract to be entered into within twenty days after the date of  
official notice of the award thereof in accordance with the terms of said proposal, then this obligation  
shall be void or else to be and remain in full force and virtue.

Sealed with \_\_\_\_\_ seal and dated this \_\_\_\_\_ day of \_\_\_\_\_ in the year of our Lord  
two thousand and \_\_\_\_\_ ( 20\_\_ ).

SEALED, AND DELIVERED IN THE  
presence of

\_\_\_\_\_  
Name of Bidder (Organization)

Corporate  
Seal

By: \_\_\_\_\_

Authorized Signature

Attest \_\_\_\_\_

\_\_\_\_\_  
Title

\_\_\_\_\_  
Name of **Surety**

Witness: \_\_\_\_\_

By: \_\_\_\_\_

\_\_\_\_\_  
Title