



STATE OF DELAWARE  
**DEPARTMENT OF TRANSPORTATION**  
800 BAY ROAD  
P.O. BOX 778  
DOVER, DELAWARE 19903

JENNIFER COHAN  
SECRETARY

**VIA WEBSITE POSTING**

August 8, 2019

Contract No. T201906103.01  
Pavement and Rehabilitation, North III, 2019  
New Castle County

Ladies and Gentlemen:

Enclosed is Addendum No. 1 for the referenced contract consisting of the following:

1. The Bid Proposal Cover, revised, to be substituted for the same page of the Proposal.
2. One (1) sheet, Signing and Striping Plans, sheet 28 of 35, revised, to be substituted for the same page in the Plans.

Please note the revisions listed above and submit your bid based upon this information.

Sincerely,  
*~signature on file~*  
Connie Ivins  
Competitively Bid Contracts Coordinator  
Delaware Department of Transportation

STATE OF DELAWARE



DEPARTMENT OF TRANSPORTATION

BID PROPOSAL

for

CONTRACT T201906103.01

PAVEMENT AND REHABILITATION, NORTH III, 2019

NEW CASTLE COUNTY

ADVERTISEMENT DATE: July 22, 2019

COMPLETION TIME: 60 Calendar Days

SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION  
DELAWARE DEPARTMENT OF TRANSPORTATION  
AUGUST 2016

Bids will be received in the Bidder's Room at the Delaware Department of Transportation's Administration Building, 800 Bay Road, Dover, Delaware prior to 2:00 P.M. local time August 20, 2019



**GUARDRAIL SCHEDULE**

NO.	ITEM DESCRIPTION / TYPE	BEGIN STA.	OFFSET	LENGTH
100	END TREATMENT, ATTENUATOR TYPE 1	328+36.42	LT 16.17'	50'
101	GALVANIZED STEEL GUARDRAIL, TYPE 1-31	328+75.27	LT 16.78'	69'
102	GUARDRAIL OVER CULVERT, SPECIAL *	329+44.05	LT 14.97'	35'
103	GALVANIZED STEEL GUARDRAIL, TYPE 1-31	100+61.59	LT 14.38'	22'
104	END TREATMENT, ATTENUATOR TYPE 1	100+85.16	LT 14.58'	50'
105	END TREATMENT, ATTENUATOR TYPE 1	328+24.41	RT 15.55'	50'
106	GALVANIZED STEEL GUARDRAIL, TYPE 1-31	328+74.55	RT 14.21'	66'
107	GUARDRAIL OVER CULVERT, SPECIAL *	329+42.97	RT 14.44'	72'
108	END TREATMENT, ATTENUATOR TYPE 1	330+15.64	RT 15.56'	50'
109	CURVED GUARDRAIL SECTION (R=35')	329+79.79	LT 15.27'	60'

\* - SEE NOTE 3

**NOTES:**

- SEE STANDARD DETAIL B-1, TYPE 1-31 GUARDRAIL APPLICATION.
- SEE STANDARD DETAIL B-2, GUARDRAIL END TREATMENT ATTENUATOR TYPE 1-31.
- REMOVAL OF EXISTING POSTS AND W-BEAM GUARDRAIL, PAID FOR BY ITEM NO. 211000. CONTRACTOR IS TO SALVAGE AND REUSE EXISTING ANCHOR BOLTS, NUTS, AND WASHERS. FURNISHING AND INSTALLING POSTS, W-BEAM RAIL ELEMENTS, OFFSET BLOCKS, AND HARDWARE INCLUDING DRILLING POSTS AND INSTALLING THREADED ROD, NUTS, BOLTS, AND WASHERS SHALL BE PAID UNDER ITEM NO. ~~702501~~ GUARDRAIL OVER CULVERT, SPECIAL .  
720503
- CONTRACTOR REQUIRED TO PROVIDE FLAT AREA TO MAXIMUM EXTENT POSSIBLE BEHIND CURVED GUARDRAIL SECTIONS PER DELDOT STD. DETAIL B-18.

Addendum #1 - Changing referenced item number 702501 to 720503

LOCATION 5

PLOTTED BY: GABEL DATE: 8/8/2019 FILE LOCATION: Q:\INDE\150151\_000\_TRAFFIC\_ENGINEERING\CADD\303\_PAVE AND REHAB\CP - CREEK ROAD 1.DGN [ SHEET: Sheet 1 ]



ADDENDUMS / REVISIONS	
	REVISED ITEM NUMBER-MAW 08/08/19



**PAVEMENT & REHABILITATION  
NORTH III, 2019**

CONTRACT	PERMIT NO.
T201906103.01	DESIGNED BY: PER (JMT)
COUNTY	CHECKED BY: CGG (JMT)
NEW CASTLE	

**CREEK RD  
GUARDRAIL PLANS**

SHEET NO.
28
TOTAL SHTS.
35